

PREVENTIV

OBJEKTI: RIKONSTRUKSION "BLLOKU LAGJA E RE", BULQIZE

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
1 PUNIME GERMIM-MBUSHJE NE RRUGE						
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	357.94		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	357.94		
SHUMA 1						
2 PUNIME SHITESASH NE RRUGE						
1	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	187.25		
2	3.198	Cilindrim kasonete me rul	m ²	900		
3	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	900		
4	3.212/b	Shtrese stabilizant t=10cm	m ²	900		
5	3.222/2	Shtrese binderi me granil gur kave, 6cm, me makineri	m ²	900		
6	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m ²	900		
7	3.244	Struktura monolite betoni C 20/25, kuneta	m ³	28.1		
SHUMA 2						
3 PUNIME TROTUARI						
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	412		
2	3.244/1	Struktura te holla monolite betoni C 20/25 (bordura e pasme)	m ³	61.6		
3	3.240	Struktura monolite betoni c12/15 (fiksime bordure)	m ³	30.8		
4	3.617/1	F V bordura betoni 15x30 cm	ml	452		
5	An.164/1a	Mbushje me cakell e gur gurore, perhapur e ngjeshur me makineri (t=20cm)	m ³	206		
6	2.261	Shtrese rere per nivelim pllake t=4 cm	m ³	41		
7	3.620	Trotuar me pllaka betoni 20x10x6cm	m ²	1,031		
8	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	412		
SHUMA 3						

4:		PUNIME NE SHESHE DHE PARKIME			
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	622.487	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	622.487	
3	3.198	Cilindrim kasonete me rul	m ²	1,560	
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	1,560	
5	3.212/b	Shtrese stabilizant t=10cm	m ²	1,560	
6	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m ²	1,560	
7	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m ²	1,560	
8	3.617/1	F V bordura betoni 15x30 cm	ml	280	
9	3.240	Struktura monolite betoni c12/15 (fiksim bordure)	m ³	11.20	
10	An/14	F.V. Stola druri	cope	15	
11	An/14.2	Kosha per mbeturina, metalike	cope	15	
12	An/14.3	Mbushje me dhe vegjetal, per lulidhtet =30cm	m ²	2,465	
13	3.643	Mbjellje bari ne skarpas	m ²	2,465	
		SHUMA 4			
5:		PUNIME K.U.B			
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m ³	270	
2	2.261	Shtrese rere	m ³	81	
3	An.164/1a	Mbushje me cakell	m ³	189	
4	3.An/1t	F V tuba te brinjzuar HDPE SN8 d=315 mm	ml	450	
5	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	copë	20	
6	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	270	
		SHUMA 5			
6:		PUNIME ELEKTRIKE			
1	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	copë	19	
2	AN 3	FV Ndricules LED 81.6 w	copë	19	
3	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	19	
4	An	F V kuader komandimi komplet me santeri+fotoelement	copë	1	
5	2. a-106	Automat magneto-termik 380V,40A, 4P,Id=0.03A	copë	19	
6	AN 4	F.V. morseteri shtylle 3P=sig.16A+kapak	copë	19	
7	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	copë	19	
8	4.150/7	F.V. percjellesa Cu 16mm ²	ml	85	
9	AN 3	F.V. Kabell FG7OR 0.6/ 1KV, 5x10mm ²	ml	38	
10	AN 5	F.V. Kabell FG7OR 0.6/ 1KV, 5x6mm ²	ml	402	
11	AN 6	F.V. Kabell FG7OR 0.6/ 1KV, 3x1.5mm ²	m	190	
12	AN 7	F.V. tub fleksibel me 2 shtresa D=75mm per elektrik	ml	225	
13	3.654/1	Furnizim, vendosje tuba plastmasi ø 80 (linjat rezerve inxh.)	ml	450	
14	2.575	Puse kontrolli 1x1x1.5m	cope	3	
15	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	19	
16	3.240	Struktura monolite betoni C 12/15	m ³	11.4	
17	AN 8	Shirit Sinjalizues	ml	225	
18	2.261	Rere	m ³	27	
19	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m	m ³	72	
20	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	72	
		SHUMA 6			

7 PUNIME PER SINJALISTIKE					
1	An130	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Termoplastike (sprajt)	ml	675	
2	An151	Vizime me boje bikomponente (vijzime kembesoreshe, shigjeta drejtimi etj)	m ²	16	
3	An158	FV tabela te ndryshme rrugore D=60cm	cope	12	
SHUMA 7					
8: PUNIME GJELBERIME					
1	An169	F.V mbjellje peme dekorative Bli 16-18cm ne trotuar (cdo 6m)	copë	62	
2	An164	F.V. Fidane Peme dekorative	cope	44	
3	An165	F.V. Fidane shkurre dekorative "Oleander" (cdo 75cm)	copë	150	
SHUMA 8					
PERMBLEDHESE					
SHUMA A (1-8)					
FOND REZERVE			5%		
SHUMA					
T.V.SH.			20%		
TOTALI					

Shenime: Cmimet e preventivit jane ne baze manualit te cmimeve te vitit 2015.

Preventivues :
ERALD-G SH.P.K

Ing. Gezim Islami