

MIRATOI
KRYETARI BASHKISE
Fatos Tushe

P R E V E N T I V

OBJEKTI: "SISTEMIM ASFALTIM RRUGA "GJAZE"

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
I.SEGMENTI 1 L=252m						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	30		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	50		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	80		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1260		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1260		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1020		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1020		
					Shuma 2	
3.Punime te KUB						
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	40		
					Shuma 3	
SHUMA I						
II.SEGMENTI 2 L=252m						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	32		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	75		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	107		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1260		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1260		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1020		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1020		
					Shuma 2	
3.Punime te KUB						
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	40		
2	2.262/3	Shtrese betoni C12/15 (kanal i hapur)	m3	20		
3	2.258	Shtrese zhavorri t=8cm	m ³	9		
					Shuma 3	
SHUMA II						
III.SEGMENTI 3 L=454m						
1.Prishje shtresash						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	57		

2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	120		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	177		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	2200		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	2200		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1770		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1770		
					Shuma 2	
		3.Punime te KUB				
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	60		
					Shuma 3	
SHUMA III						
		IV.DEGEZIMI 1 L=45m				
		1.Prishje shtresash				
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	12		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	12		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	225		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	225		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	180		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	180		
					Shuma 2	
		3.Punime te KUB				
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	60		
					Shuma 3	
SHUMA IV						
		V.DEGEZIMI 2 L=41m				
		1.Prishje shtresash				
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	10		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	10		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	205		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	205		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	164		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	164		
					Shuma 2	
		Punime te KUB				
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	60		
					Shuma 3	
SHUMA V						
		VI.DEGEZIMI 3 L=320m				
		1.Prishje shtresash				
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	40		

2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	91		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	131		
					Shuma1	
		2.Punime shtresash				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1600		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	1600		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1280		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1280		
					Shuma 2	
					SHUMA VI	
VII-Punime Spostim shtylla dhe Ndricimi						
1	An	Cmontim 3 fije teli al S=35 mm2	km	0.187		
2	3.568	Punime izolimi per linja TU 6÷10 kv me izolator mbeshtetes	cope/ shtyll	2.0		
3	3.549/1	Shtirirje terheqje teli 3 fije (percjellsa makineri alumuni seksion 35 mm2)	km	0.187		
4	An	Heqje dhe vendosje shtylla centrifugale b/a, h=8 m	cope	2.0		
					SHUMA VII	
					Shuma I-VII	
					Fond rez.5%	
					Shuma 1	
					Tvsh 20%	
					Totali	

Punoi: Ark. Alban Manoku



Drejtoria e Planifikimit
Ing.Mimoza Haxhiu

Zyra e projekteve
Ark.Maksim Cuko