

**PREVENTIVI I PUNIMEVE**

**Objekti:** Rikonstruksioni i Rruges "Perroi i Zi" & "Shkendi", Bashkia Belsh

**Investitori:** Bashkia Belsh

Nr.	Nr. Analizes	Pershkrimi i Punimeve	Njesia	Sasia	Cmimi	Vlefta
<b>I - Rruga "SHKENDI" (L = 660 ml; Gjeresi = 2.8 m)</b>						
<b>A - Punime Kanalizimi</b>						
1	2,1	Germim dheu me krahe transport	m3	8		
2	3,158/e	Germim dheu me skrep	m3	40		
3	2-37/5a	Transport materiale ndertimi +dheu deri 5 km	m3	40		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.39		
	3.289	F V hekur betoni periodik, Ç - 5, Ø > 12mm	ton	2.23		
4	3.248	Struktura monolite betoni me çakell C 30/37	m3	8.75		
	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	18		
<b>Shuma A</b>						
<b>B - Punime ne Rruge</b>						
2	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	1848.0		
3	An.	Shtrese asfaltobetoni mikser (binder + tapet asfalti ) me granil gur kave, 10 cm, me makineri	m2	1848.0		
<b>Shuma B</b>						
<b>Shuma I ( A+B )</b>						
<b>II - Rruga "PERROI I ZI" (L=930 ml; Gjeresi=2,8m)</b>						
<b>Punime ne Rruge</b>						
2	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	2,604		
3	An.	Shtrese asfaltobetoni mikser (binder + tapet asfalti ) me granil gur kave, 10 cm, me makineri	m2	2,604		
<b>Shuma II</b>						
<b>Shuma I+II</b>						
<b>20% TVSH</b>						
<b>SHUMA TOTALE</b>						

Preventivoi:  
Ing. Kastriot BEGAJ