

**PREVENTIV**

OBJEKTI: Sistemim, asfaltim I bllokut ne lagjen "Beslidhja" tek DTT

NR.	nr.an.	EMERTIMI I PUNUMEVE	NJESIA	SASIA
		<b>a, PUNIME GERMIMI</b>		
1	3.106/b	Germim dheu me eskavator 0.5 m <sup>3</sup> , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m <sup>3</sup>	600.0
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	600.0
		<b>shuma a leke</b>		
		<b>b, PUNIME NE RRUGE</b>		
3	An.164/1a	Mbushje me cakull e gur gurorje ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	-
5	3.212/c	Shtrese stabilizanti t=15cm	m <sup>2</sup>	4,350.0
7	3.228/1	Shtrese binderi me zall lavatrice,4cm,me makineri	m <sup>2</sup>	4,350.0
8	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m <sup>2</sup>	4,350.0
		<b>shuma b leke</b>		
		<b>c, PUNIME NE TROTUARE</b>		
1	3.110/b	Germim dheu me eskavator me zinxhire 1.0m <sup>3</sup> , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ,me shkarkim ne mjet (per ndertimin kasonet)	m <sup>3</sup>	12.0
2	3.158/5a	Transport materiale ndertimi, deri 5.0 km	m <sup>3</sup>	12.0
3	2.258	Mbushje me Nenshtrese zhavori 25cm	m <sup>3</sup>	300.0
5	3.212/b	Shtrese granili 7cm, me makineri	m <sup>2</sup>	300.0
6	3.620	Trotuar me 6 cm beton, me pllaka	m <sup>2</sup>	300.0
7	3.243/1	Beton C16/20, per kuneta	m <sup>3</sup>	42.0
8	3.242	Beton C12/15, per bordurat	m <sup>3</sup>	-
10	3.618	F.V. Bordure betoni 20x35 cm	ml	220.0
		<b>shuma c leke</b>		
		<b>d, PUNIME NE KUB</b>		
1	3.106/b	Germim dheu me eskavator 0.5 m <sup>3</sup> , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m <sup>3</sup>	12.0
2	2.258	Nenshtrese zhavori	m <sup>3</sup>	3.0
4	3.An/2t	F.V. tub PVC Ø400 mm per linjat e jashtme	ml	300.0
5	An - 22/1	Pusete shiu 40x40,h=100cm, me kapak gize	cope	20
6	An - 18	Pusete shkarkimi b/a 50x50cm, h=100cm	cope	2
		<b>shuma d leke</b>		
		<b>SHUMA A-E</b>	<b>Leke</b>	
		<b>TVSH 20%</b>	<b>Leke</b>	
		<b>TOTALI</b>	<b>Leke</b>	

Ing. Gjovalin Marku

