

Nr	Nr.anal	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
A						
Asfaltim i rruges "Baba Sherif Cani" Lagjja "Shenkoll"						
I - Punime ndertimi						
1	3.122/b	Germim shkambi i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m3	650		
2	2,37/5a	Transport dheu deri 5 km	m3	650		
3	An	Skarifikim shtrese asfalti me makineri	m2	4400		
4	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m2	1334		
5	3.212/b	Shtrese stabilizant t=10cm	m2	1334		
6	An	Sperkatje me emulsion bituminoz 0.5 l/m2	m2	3802		
7	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	1103		
8	3.227/1	Shtrese binderi me zall lavatrice,3cm,me makineri per nivelimin e nje krahu te rruges	m2	2710		
9	3.233/2	Shtrese asfaltobetoni me zall lavatrice,5cm,me mak	m2	4946		
10	2.258	Nenshtrese zhavori nen bordure	m3	25		
11	3.240	Struktura monolite betoni C 12/15 nen bordure	m3	34		
12	3.617/2	F V bordura betoni 15x35 cm	m	1823		
13	2.258	Shhtrese zhavori pas bordurave	m3	153		
14	2.258	Nenshtrese zhavori nen kunete	m3	43		
15	3.240	Struktura monolite betoni C 12/15 nen kunete	m3	39		
16	3.244	Struktura monolite betoni C 20/25 kunete	m3	50.4		
Shuma - I			leke			
II-Punime kanalizimet						
1	2An.575	Rikonstruksion i ngritjes pusetave te ujrave te zeza dhe albletekomit	cope	2		
2	3An.1	F.V.Kapak pusetash te rumbullakta	cope	2		
3	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	170		

4	2,37/5a	Transport dheu deri 5 km	m3	170		
5	3.240	Struktura monolite betoni C 12/15 nen tubacione	m3	4.7		
6	3.183/a	Shtrese zhavor lumi 10 cm per kanal	m2	24		
7	2.555	F.V tuba betoni Ø 500 mm	ml	20		
8	An1	Ndertim puseta betoni H=2.5-3m, D=1m + kapak gize	cope	2		
9	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	140		
		Shuma - II	leke			
		III-Punime per ujrart e shiut (KUB)				
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	176		
2	2,37/5a	Transport dheu deri 5 km	m3	176		
3	2.An-22	Puseta b/a shiu 40x40x100 cm me kapak zgare hekuri	cope	32		
4	2.552	F.V tuba betoni Ø 200 mm	ml	880		
		Shuma - III	leke			
		IV-Punime sinjalistike				
1	An158	FV tabela te ndryshme rrugore D=60cm	cope	2		
		Shuma - VI	leke			
		Shuma "A" nga I deri IV per rrugen "Baba Sherif Cani", Lagjia "Shenkoll"	leke			
B		Rikonstruksioni i rruges "Haki Ballshi"				
I		PUNIME PRISHJE				
1	2,426/2	Prishje mure me blloqe betoni	m3	3.48		
2	2.426/3	Prishje shtresa betoni	m3	2.66		
3	3.159/an	Spostim shtylla b/arme H=7 m	cope	3		
		Shuma I	LEKE			
II		PUNIME PER KANALIZIMET E UJRAVE TE BARDHA				
1	2.10	Germim dheu per pusetat e U.B. ne toke te zakonshme me krahe	m3	24.3		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	281.7		

3	3.354	Tombino me tuba betoni, shtrese zhavori Ø 200mm	m	135		
4	3.355	Tombino me tuba betoni, shtrese zhavori Ø 300mm	m	221		
5	An - 23	Puseta beton / arme shiu 40 cm x 60 cm h= 100cm + kapak gize	cope	14		
6	An - 23/an	Puseta beton / arme shiu 40 cm x 60 cm h= 150 cm+ kapak gize	cope	13		
7	2.258	Nenshtrese zhavorri nen pusete t =10 cm ; 0.9 m x 0.7 m	m3	1.701		
8	An-9	Mbushje me zhavorr te kanaleve te u.z.	m3	150		
9	3.158/1a	Transport dheu me auto deri 5.0 km	m3	256		
		SHUMA II PER TOMBINOT UJRAVE TE BARDHA	LEKE			
III		PUNIME PER ASFALTIMIN E RRUGES 1515 m2				
1	3,617/2	F.V bordura betoni C 25 / 35 p.p. 15 cm x 35 cm me nenshtrese beton/arme C 16 / 20 me trashesi 10 cm (shih detajin)	ml	623		
2	3.142/b	Germim dheu, kategoria e III-te,per hapjen e trasese se rruges me gjatesi L = 262 m +48m	m3	115		
3	3.198	Cilindrim kasonete me rul	m2	1705		
4	3.158/1a	Transport dheu me auto deri 5.0 km	m3	115		
5	3.205/1	Shtrese zhavori lumi t mes ~ 15cm, perhapur e ngjeshur me makineri mbushje e nivelim I trupit te rruges	m2	36		
6	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	1515		
7	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	1515		
8	3,212/b - An	shtrese stabilizanti t = 10 cm	m2	1515		
9	An	Sperkatje me emulsion bituminoz 0.5 l/m2	m2	1515		
10	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	1515		
11	3,226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	1515		
		Shuma IV PER NDERTIMIN E TROTUARIT + ASFALTIMI I RRUGES	LEKE			
IV		PUNIME PER SINJALISTIKEN				

1	3.45/1	Germim dheu me krahe per gropat toke te zakonsh me permasat 0.5 x 0.5 h=0.8 x 8 cop	m3	1.6		
2	3.234	betonim per fiksimin e tabelave C 6 / 10 (M-100)	m3	1.6		
3	An-100	F.V. Tabela te sinjalistikes rrugor rrethore D = 60	cope	1		
4	An-105	F.V. Tabela te sinjalistikes rrugor trekendore	cope	3		
5	An-93	F.V.Tabela katrore e vogel me diagonal vertikal 40x25	cope	4		
6	An-142	Vijezi i rruges per kembesoret me boje bikomponente	m2	45		
7	An-152	Vijezi i rruges anesor dhe i aksit me boje bikomponente me gjeresi 15 cm	ml	624		
		SHUMA VI PER SINJALISTIKEN	LEKE			
		SHUMA "B" nga I deri ne IV per Rikonstruksionin e rruges " Haki Ballshi" lagjia "Emin Matraxhiu"	LEKE			
		SHUMA "A" + "B"				
		<i>Fondi rezerve 3%</i>	<i>leke</i>			
		<i>Shuma</i>	<i>leke</i>			29,215,46
		<i>20 % T.V.SH.</i>	<i>leke</i>			1
		SHUMA	leke			