

PREVENTIV pa cmime

OBJEKTI : RIKONSTRUKSION SHKOLLASH

PERMBLEDHESHE E PREVENTIVAVE						
						Vlera
SHKOLLA Bratosh		1	LEK		-	
SHKOLLA Rapsh		2	LEK		-	
SHKOLLA Hysaj		3	LEK		-	
		SHUMA (1+2+3)				-
		TVSH 20%				-
		TOTALI				-
			Njesia	sasia	cmimi	Vlera
SHKOLLA Bratosh						
A.PUNIME NDERTIMI						
1. Punime te ndryshme dhe prishje						
1	An	Heqje e suvatimit te brendshem	m ²	930		-
2	An	Prishje cati	m ²	450		-
3	An	Heqje tavan plastik	m ²	440		-
4	2.426/3	Prishje davanciale ekzistuese betoni	m ³	30		-
5	An	Heqje ulluke ekzistues	ml	42		-
6	An	Heqje dritare	cope	36		-
7	An	Heqje dyer	cope	10		-
8	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	134		-
Shuma 1			Leke			-
2.Punime h/izolimi dhe catie						
1	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m ²	450		-
2	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m ²	450		-
3	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	42		-
4	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	88		-
5	2.206/b	Kasete shkarkimi me llamarine xingat 1.0mm	cope	6		-
Shuma 2			Leke			-
3.Punime shtresa dhe veshje						
1	2.267/B	Shtrese me pllaka grez importi 40 x 40 cm	m ²	230		-
2	2.262/1	Shtresa betoni C 7/10 (per sigurimin e hidroizolimit te katit perdhe) t=10cm	m ³	22		-
3	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama	m ²	242		-
4	2.264	Shtrese lluster per nivelim	m ²	220		-
5	2.324/b	Plintuse grez importi , h=10 cm	ml	155		-
6	2.267/B	Veshje tualete me pllaka gres	m ²	62		-

7	2.267/B	Shtrese me pllaka grez importi 40 x 40 cm(tualete)	m2	14	-
8	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama (tualete)	m2	18	-
9	2.268/a	Davanciale mermeri	m2	30	-
10	2.268a	Shkalle mermer montazhi	m2	12.8	-
11	2.324/2	Plintuse mermeri h = 10cm	ml	18	-
12	2.268a	Shkalle mermer montazhi(jashte)	m2	9	-
13	2.410/b	Parapet shkalle e ballkone me tuba inoksi ngjyre e verdhe ose metalizato, h=30~50cm	m2	12	-
		Shuma 3	Leke		-
		4.Punime suvatimi			
1	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m ²	930	-
2	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	94	-
3	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva.	m2	695	-
4	2.350	Suva xokoli me granil e çimento te zakonshme me spruco	m2	88	-
5	2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m2	440	-
6	2.282	Shtrese derrasa FM 4.0cm	m2	220	-
7	An.	F.V. profile metalike per perforcim dysHEMEJE nderkati	ton	3.6	-
		Shuma 4	Leke		-
		5.Punime dyer dritare			
1	2.375/a	F.V dritare d/alumini dopio xham	m ²	66	-
2	2.383/1	F.V. Der e jashtme druri importi cilesi e I-re.	m ²	4.68	-
3	2.388/1	V F dyer te brendeshme tamburate te rimesuara	m2	18	-
4	2.395/a	Dyer d/alumini dopio xham.	m2	4.2	-
		Shuma 5	Leke		-
		6.Punime bojatisje			
1	2.404/1	Boje hidroplastike importi (jashte)	m ²	783	-
2	2.404	Boje hidroplastike (brenda)	m ²	1024	-
3	2.400	Boje vaji siperfaqe druri	m2	230	-
4	2.401	Boje vaji siperfaqe metalik	m2	12	-
		Shuma 6			-
		7. Punime hidrosanitare			
1	2.495	F.V lavaman porcelani importi me mishelator	cope	2	-
2	2.501	F.V WC allafrenga importi	cope	4	-
		Shuma 7			-
		8.Punime murature			
1	2.65/1	Mur me tulla te plota ne lartesi h~ 8m, llaç I perzier M15	m3	5.4	-
2	2.86	Mur me tulle me 6 vrime, t=12cm, h=3m llaç I perzier M15	m3	2.2	-
		Shuma 8			-
		SHUMA A			-
		B. PUNIME ELEKTRIKE			

1	An.	Panel elektrik metalik brenda murit 36 poste	cope	1	-
2	An.	Sinjalizues tensioni 220V	cope	3	-
3	An.	Automat magnetotermik 2x32A	cope	3	-
4	An.	Mbrojtes diferencial 2x32A/30mA	cope	3	-
5	An.	Automat manjetotermik 2x10A(nje post)	cope	2	-
6	An.	Automat manjetotermik 2x16A(nje post)	cope	1	-
7	An.	Automat manjetotermik 2x20A(nje post)	cope	2	-
8	An.	Percjelles bakri I veshur Cu=1,5mm2	ml	950	-
9	An.	Percjelles bakri I veshur Cu=2,5mm2	ml	340	-
10	An.	Percjelles bakri I veshur Cu=4 mm2	ml	70	-
11	An.	Percjelles bakri I veshur Cu=10mm2	ml	25	-
12	An.	Tub plastik seri e rende Φ 16mm	ml	260	-
13	An.	Tub plastik seri e rende Φ 20mm	ml	180	-
14	An.	Tub plastik seri e rende Φ 25mm	ml	150	-
15	An.	Tub plastik seri e rende Φ 32mm	ml	6	-
16	An.	Priza shuko 16A brenda murit	cope	16	-
17	An.	Celes elektrik 10A brenda murit	cope	24	-
18	An.	Prize telefoni per kuti brenda murit	cope	2	-
19	An.	Prize internet LAN per kuti brenda murit	cope	3	-
20	An.	Pulsant elektrik 10A brenda murit	cope	1	-
21	An.	Kuti 3 poste celes / prize brenda murit	cope	18	-
22	An.	Suport per kuti brenda murit	cope	18	-
23	An.	Kapak kuti brenda murit	cope	18	-
24	An.	Kuti shperndarese jashte murit 250x150mm	cope	2	-
25	An.	Ndricues plafonier LED IP 40 60x60cm jashte murit 4x8W	cope	36	-
26	An.	Ndricues plafonier LED IP 40 120x24cm jashte murit 2x 16W	cope	6	-
27	An.	Ndricues plafonier LED IP 40 D=25cm jashte murit 2x 16W	cope	4	-
28	An.	Ndricues sinjalizim emergjence 4W, autonomi 1 ore	cope	3	-
29	An.	Zile elektrike 12W/220V	cope	1	-
30	An.	Kanaline plastike 100x50mm	ml	18	-
31	An.	Panel elektrik plastik jashte murit 8 poste	cope	1	-
32	An.	Forbox 6 mm2	cope	90	-
33	An.	Forbox 10mm2	cope	32	-
34	An.	Forbox 16mm2	cope	18	-
35	An.	Upa plastik Φ 6 + vida metalike L55mm	cope	245	-
36	An.	Kuti plastike me kapak te rende 300x300x300mm	cope	1	-
37	An.	Elektroda tokezimi L=1,2m, 50x50x4mm	cope	2	-
38	An.	Percjelles bakri I veshur 25 mm2	ml	12	-
		SHUMA B			-
		C.PUNIME HIDROSANITARE			
		1.Rrjeti shperndarjes			
1	2.494/4	F.V saracineska bronzi Φ 1 1/2 " = 40 mm	cope	1	-
2	2.494/3	F.V saracineska bronzi Φ 1 1/4 " = 32 mm	cope	1	-

3	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	3		-
4	2.491/b	F.V Tuba e rakorderi ujesjellesi PPR d=20~25mm, PN 16	ml	65		-
5	2.491/c	F.V Tuba e rakorderi ujesjellesi PPR d=20~32mm, PN 16	ml	32		-
6	2.491/d	F.V Tuba e rakorderi ujesjellesi PPR d=40mm, PN 16	ml	25		-
7	2.575	Puse kontrolli 1x1x1.5m	cope	1		-
8	2.15	Germim e mbushje dheu me krah per kanale kategoria III, h = 1.5 m	m3	122		-
9	3.182/a	Shtrese rere natyrore t=10cm	m2	86		-
10	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	86		-
11	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	45		-
12	2.425/3	Grope septike me V = 16 m3	cope	1		-
		Shuma C				-
		D. PUNIME SISTEMIM I JASHTEM				
1	2.289	Trotuar me lluster cemento, pa borduren e betonit	m2	76		-
2	2.262/4	Shtrese betoni C 16/20 t=10cm (Volejbolli)	m3	22		-
3	3.193/a	Shtrese zhavorri h=10 cm (5-20mm) (Volejbolli)	m2	220		-
4	2.399	Sherbetisje e bojatisje me gelqere (muri i rrethimit)	m ²	230		-
5	2.401	Boje vaji siperfaqe metalik,(porta hyrese,kangjellat e rrethimit,paralele,etj)	m ²	145		-
6	An	F.V. Shtyllat per fushen e volejbollit	cope	2		-
7	An	F.V. Stukturen metalike per paralele (tre modele)	cope	3		-
		SHUMA D				-
		SHUMA				-
Shkolla Rapsh						
		I.PUNIME NDERTIMI				
		1. Punime te ndryshme dhe prishje				
1	An	Heqje e suvatimit te brendshem	m ²	680		-
2	An	Prishje shtrese pllaka ekzistuese + plintusa + pastrim dhe transport mbeturinash	m ²	273		-
3	2.426/3	Prishje davanciale ekzistuese betoni	m3	0.4		-
4	An	Heqje ulluke ekzistues	ml	104		-
5	An	Heqje dyer	cope	22		-
6	An	Prishje cati	m2	260		-
7	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	165		-
		Shuma 1	Leke			-
		2.Punime h/izolimi dhe catie				
2	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	260		-

3	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	18		-
4	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	86		-
5	2.206/b	Kasete shkarkimi me llamarine xingat 1.0mm	cope	6		-
		Shuma 2	Leke			-
		3.Punime shtresa dhe veshje				
1	2.267/B	Shtrese me pllaka grez importi 40 x 40 cm	m ²	273		-
2	2.262/1	Shtresa betoni C 7/10	m ³	27.3		-
3	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama	m ²	356		-
4	2.264	Shtrese lluster per nivelim	m ²	273		-
5	2.324/b	Plintuse grez importi , h=10 cm	ml	210		-
6	2.267/B	Veshje tualete me pllaka gres	m ²	51		-
7	An.	Davanciale mermeri	m ²	14		-
8	2.268a	Shkalle mermer montazhi(jashte)	m ²	13.4		-
		Shuma 3	Leke			-
		4.Punime suvatimi				
1	2.300	Suvatim solete h-4 m me drejtues, me krah	m ²	246		-
2	2.310	Suva brenda mur tulle h-4 m me krah , llac perzier M25	m ²	450		-
3	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva.	m ²	258		-
		Shuma 4	Leke			-
		5.Punime dyer dritare				
1	2.383/1	F.V. Der e jashtme druri importi cilesi e I-re.	m ²	6.2		-
2	2.388/1	V F dyer te brendeshme tamburate te rimesuara	m ²	12.6		-
3	2.395/a	Dyer d/alumini dopio xham.	m ²	8.4		-
4	2.375/a	F.V dritare d/alumini dopio xham	m ²	48.6		-
		Shuma 5	Leke			-
		6.Punime bojatisje				
1	2.404	Boje hidroplastike importi (Brenda)	m ²	696		-
2	2.404/1	Boje hidroplastike importi (Jashte)	m ²	258		-
		Shuma 6				-
		SHUMA I				
		II - PUNIME ELEKTRIKE				
1	2. a-137	Ndricues fluoreshent 4x18w,IP40	cope	18		-
2	2. a-136	Ndricues pllafonier muror 1x100w	cope	8		-
3	2.485/3	F.V Çeles 1 polar 220V 10A "Ticino"	cope	15		-
4	2.481/1	F.V percjelles PV-500 Ø 1.5 mm ²	ml	800		-
5	480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	600		-
6	2.49	F.V kuader ndriçimi	cope	2		-
7	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	4		-
8	2.490/1d	F.V Automat termo/el.manj. diferencial 2P 220V, 32A	cope	2		-
9	2.490/d	F.V Kasete plastike KE me 8 modular (vende)	cope	2		-
10	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	2		-

11	2.487/d	modular Gevis	cope	29		-
12	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	350		-
13	2.485/b	F.V priza bivalente 220V 10A 2P-T Gevis	cope	14		-
14	2.481/3	F.V percjelles PV-500 Ø 4 mm2	ml	50		-
15	2.481/4	F.V percjelles PV-500 Ø 6 mm2	ml	25		-
16	2.487	F.V Kutiderivacioni plastike	cope	6		-
17	2. a-131	Ndricues tip plafoniere, emergjence , 1x18w ,IP65	cope	4		-
		SHUMA II	leke			-
		III - PUNIME UJESJELLES KANALIZIME				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet (per gropen sepstike)	m3	13		-
2	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	1		-
3	2.494/3	F.V saracineska bronzi Ø 1 1/4 " = 32 mm	cope	1		-
4	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	3		-
5	2.491/b	F.V Tuba e rakorderi ujesjellesi PPR d=20~25mm, PN 16	ml	106		-
6	2.491/c	d=20~32mm, PN 16	ml	60		-
7	2.491/d	F.V Tuba e rakorderi ujesjellesi PPR d=40mm, PN 16	ml	25		-
8	2.521	Tub kanalizimi pvc Ø 140 mm	ml	76		-
9	2.575	Puse kontrolli 1x1x1.5m	cope	1		-
10	2.425/3	Grope septike me V = 16 m3	cope	1		-
11	2.513	F.V pilete dyshemeje Ø 30 mm	cope	4		-
12	2.495	F.V lavaman porcelani importi me mishelator	cope	4		-
13	2.501	F.V WC allafrenga importi	cope	3		-
		SHUMA III				-
		SHUMA(I-III)				-
Shkolla Hysaj						
		I.PUNIME NDERTIMI				
		1. Punime te ndryshme dhe prishje				
1	An	Heqje e suvatimit te brendshem	m2	794		-
2	An	Heqje e suvatimit I jashtem	m2	120		-
3	An	Prishje shtrese pllaka ekzistuese + plintusa + pastrim dhe transport mbeturinash	m2	818		-
4	2.426/3	heqje bazamake shkalle betoni ekzistuese	m3	2.7		-
5	2.426/3	Prishje davanciale ekzistuese betoni	m3	2.3		-
6	An	Heqje ulluke ekzistues	ml	36		-
7	An	Heqje dyer	cope	20		-
8	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	340		-
		Shuma 1	Leke			-
		2.Punime h/izolimi dhe catie				
1	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	560		-
2	2.264	Shtrese lluster çimento 1:2	m2	560		-

3	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	36		-
4	2.206/b	Kasete shkarkimi me llamarine xingat 1.0mm	cope	6		-
		Shuma 2	Leke			-
		3.Punime shtresa dhe veshje				
1	2.267/B	Shtrese me pllaka grez importi 40 x 40 cm	m2	918		-
2	2.262/1	Shtresa betoni C 7/10 (per sigurimin e hidroizolimit te katit perdhe)	m3	92		-
3	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama	m ²	1130		-
4	2.264	Shtrese lluster per nivelim	m2	918		-
5	2.324/b	Plintuse grez importi , h=10 cm	ml	578		-
6	2.267/B	Veshje tualete me pllaka gres	m2	68		-
7	An.	Davanciale mermeri	m2	36		-
8	2.268a	Shkalle mermer montazhi	m2	10.2		-
9	2.324/2	Plintuse mermeri h = 10cm	ml	13		-
10	2.268a	Shkalle mermer montazhi(jashte)	m2	5		-
		Shuma 3	Leke			-
		4.Punime suvatimi				
1	2.300	Suvatim solete h-4 m me drejtues, me krah	m ²	560		-
2	2.310	Suva brenda mur tulle h-4 m me krah , llac perzier M25	m ²	460		-
3	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m ²	120		-
4	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva.	m2	452		-
		Shuma 4	Leke			-
		5.Punime dyer dritare				
1	2.383/1	F.V. Der e jashtme druri importi cilesi e I-re.	m ²	4.68		-
2	2.388/1	V F dyer te brendeshme tamburate te rimesuara	m2	36		-
3	2.395/a	Dyer d/alumini dopio xham.	m2	8.4		-
4	2.375/a	Dritare d/alumini dyfish xham.	m2	118		-
		Shuma 5	Leke			-
		6.Punime bojatisje				
1	2.404/1	Boje hidroplastike importi (Brenda)	m ²	2655		-
2	2.404/2	Boje hidroplastike importi (Jashte)	m ²	1240		-
		Shuma 6				-
		7. Punime hidrosanitare				
1	2.495	F.V lavaman porcelani importi me mishelator	cope	4		-
2	2.501	F.V WC allafrenga importi	cope	6		-
		Shuma 7				-
		8. PUNIME ELEKTRIKE				
1	An.	Panel elektrik metalik brenda murit 36 poste	cope	1		-
2	An.	Sinjalizues tensioni 220V	cope	1		-
3	An.	Automat magnetotermik 2x32A	cope	2		-
4	An.	Mbrojtes diferencial 2x32A/30mA	cope	2		-
5	An.	Automat manjetotermik 2x10A(nje post)	cope	1		-
6	An.	Automat manjetotermik 2x16A(nje post)	cope	1		-

7	An.	Automat manjetotermik 2x20A(nje post)	cope	2		-
8	An.	Percjelles bakri I veshur Cu=1,5mm2	ml	700		-
9	An.	Percjelles bakri I veshur Cu=2,5mm2	ml	300		-
10	An.	Percjelles bakri I veshur Cu=4 mm2	ml	200		-
11	An.	Priza shuko 16A brenda murit	cope	16		-
12	An.	Celes elektrik 10A brenda murit	cope	24		-
13	An.	Pulsant elektrik 10A brenda murit	cope	1		-
14	An.	Ndricules plafonier LED IP 40 60x60cm jashte murit 4x8W	cope	24		-
15	An.	Ndricules plafonier LED IP 40 120x24cm jashte murit 2x 16W	cope	3		-
16	An.	Ndricules plafonier LED IP 40 D=25cm jashte murit 2x 16W	cope	3		-
17	An.	Ndricules sinjalizim emergjence 4W, autonomi 1 ore	cope	2		-
18	An.	Zile elektrike 12W/220V	cope	1		-
19	An.	Upa plastik Ø6 + vida metalike L55mm	cope	245		-
20	An.	Elektroda tokezimi L=1,2m, 50x50x4mm	cope	2		-
21	An.	Percjelles bakri I cveshur 25 mm2	ml	12		-
		Shuma 8	Leke			-
		9. PUNIME SISTEMIM I JASHEM				
1	2.262/3	Shtrese betoni C 12/15 t=5cm	m3	22		-
2	3.617	F V bordura betoni 15x25 cm	ml	126		-
3	3.620	Trotuar, me 6 cm beton, me pllaka	m2	240		-
		Shuma 9	Leke			-
		SHUMA				-

PREVENTIVOI

"Novatech Studio"shpk