

Nr	Nr analiz	Përshkrimi i punimeve	Njësia	Sasia	Çmimi	Vlera
1	An3,32 6	Prishje mur mbajtes e themele me gur te thate	m3	410		
2	3.122/b	Germim shkambi i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m3	233		
3	3.235	Struktura monolite b/betoni C 16/20 me 20% gur	m3	561		
4	An-8	Mbushje me cakell pas mureve	m3	444		
5	3.212/b	Shtrese stabilizant t=10cm	m2	75		
6	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	75		
7	3.226/3	Shtrese asfaltobetoni me granil guri kave, 6cm, me makineri	m2	75		
8	3.243	Struktura monolite betoni C 16/20 (bordura)	m3	6.5		
9	3.391	F V tuba plastmasi per vaditje, Ø 32 mm	m	134		
10	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	60		
		SHUMA I				6,512,793
		T.V.SH 20%				
		SHUMA				