

P R E V E N T I V

OBJEKTI: SISTEMIM ASFALTIM I RRUGEVE NE FSHATIN TOSHKEZ

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
SEGMENTI 1 L= 1085 m nga ku 250ml seksioni 4.5 ml+2x 0.5 835ml seksioni 3.5 ml+2x 0.5						
Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	790		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m3	790		
					Shuma1	
Punime shtresash						
1	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	790		
2	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	5700		
3	3.212/a	Shtrese stabilizanti t=5cm	m2	5700		
4	3.212/a	Shtrese stabilizanti t=5cm per bankina	m2	1150		
5	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	4560		
6	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	4560		
					Shuma 2	
Punime te KUB						
1	3.116/a	Germim kanali me gjeresi deri 2m,tok e zak .me shk.ne mjet	m3	650		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m3	650		
3	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	100		
4	3.183/a	Shtrese zhavor lumi t=10cm	m2	616		
5	3.240	Struktura monolite betoni C 12/15	m3	250		
6	2.112/2	Mure buto betoni C 12/15	m3	10		
					Shuma 3	
Punime elektrike						
1	3.654	F.V Tuba Plastik Ø100	ml	1140		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	36		
3	3.59/a	Germim grope per shtullat metalike	m3	9		
4	2.262/3	Beton per fiksimin e shtylles metalike	m3	9		
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	36		
6	3.An/ksh	F.V Krah shtylla metalike	cope	36		
7	3.An	F.V Ndricules Smart me llampe 250W	cope	36		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	36		
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	ml	252		
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	ml	1140		
					Shuma 4	
Tabela rrugore e vijeze						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	20		
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	2540		
					Shuma 5	
					Shuma I	
SEGMENTI 2 L= 365 m seksioni 3ml+2x 0.5						
Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	201		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m3	201		
					Shuma1	
Punime shtresash						
1	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	185		
2	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	1480		
3	3.212/a	Shtrese stabilizanti t=5cm	m2	1480		
4	3.212/a	Shtrese stabilizanti t=5cm per bankina	m2	370		
5	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1110		
6	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1110		
					Shuma 2	
Punime te KUB						
1	3.116/a	Germim kanali me gjeresi deri 2m,tok e zak .me shk.ne mjet	m3	250		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	250		
3	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	20		
					Shuma 3	

Punime elektrike					
1	3.654	F.V Tuba Plastik Ø100	ml	350	
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	12	
3	3.59/a	Germim grope per shtullat metalike	m3	3	
4	2.262/3	Beton per fiksimin e shtylles metalike	m3	3	
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	12	
6	3.An/ksh	F.V Krah shtylla metalike	cope	12	
7	3.An	F.V Ndricues Smart me llampe 250W	cope	12	
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	12	
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	m	84	
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	m	350	
					Shuma 4
Tabela rrugore e vijeze					
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	6	
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	700	
					Shuma 5

					Shuma II
--	--	--	--	--	-----------------

SEGMENTI 3 L= 315 ml seksioni 3ml+2x 0.5

Punime germimi					
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	169.91	
2	3.158/4a	Transport dheu me auto deri 4.0 km	m3	169.85	
					Shuma 1
Punime shtresash					
1	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	170	
2	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	1360	
3	3.212/a	Shtrese stabilizanti t=5cm	m2	1360	
4	3.212/a	Shtrese stabilizanti t=5cm per bankina	m2	350	
5	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1020	
6	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m2	1020	
					Shuma 2
Punime te KUB					
1	3.116/a	Germim kanali me gjeresi deri 2m,tok e zak .me shk.ne mjet	m3	250	
2	3.158/4a	Transport dheu me auto deri 4.0 km	m3	250	
3	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	18	
4	3.183/a	Shtrese zhavor lumi t=10cm	m2	350	
5	3.240	Struktura monolite betoni C 12/15	m3	110	
					Shuma 3
Punime elektrike					
1	3.654	F.V Tuba Plastik Ø100	ml	340	
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	11	
3	3.59/a	Germim grope per shtullat metalike	m3	2	
4	2.262/3	Beton per fiksimin e shtylles metalike	m3	2	
5	3.An/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	11	
6	3.An/ksh	F.V Krah shtylla metalike	cope	11	
7	3.An	F.V Ndricues Smart me llampe 250W	cope	11	
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	11	
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	m	77	
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	m	340	
					Shuma 4
Tabela rrugore e vijeze					
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	8	
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	680	

Shuma 5
Shuma III
Shuma I + II+ III
Fond Rez. 5%
Tvsh 20%
Totali

Punoi:Ark.Enis Manoku
Ing .Ariola Dylia

Zyra e projekteve
Ark.Maksim Cuko

Drejtoria e Planifikimit
Ing.Mimoza Haxhiu



