

PREVENTIV PERMBLEDHES

OBJEKTI : "REHABILITIMI I SKEMES UJITese UJEMBLEDHESI MALAJ -2" (FAZA 3).

BASHKIA MIRDITE

1.KANALI UJITES MALAJ - 2,(Pk.113-Pk.681)

Nr.	NR. AN.	EMERTIMI I PUNIMIT	NJESIA	SASIA	CMIMI	VLEFTA
1	3.119/b	Germim me eksk. shkemb i coptuar per trase	m ³	6,105		
2	3.68/a	Germim me eksk. shkemb i bute per trase	m ³	2,617		
3	3.25/a	Germim dheu per kanal toke e zakonshme	m ³	1,426		
4	3.2	Prerje bime te vogla	m ²	5,292		
5	3.183/a	Nenshtrese zhavorri t = 10 cm	m ²	2,710		
6	3.243/1	Beton C 16/20 per kanal	m ³	1,145		
7	An. III	Renie me Tub PE, Pik. 196-235, L = 370 ml	cope	1		
8	An. VI	Renie me Tub PE,Pik.235-266, L = 485 ml	cope	1		
9	An. VIII	Renie me Tub PE,Pik.325-333, L = 98 ml	cope	1		
10	An. IX	Renie me Tub PE,Pik.406-412, L = 112 ml	cope	1		
11	An. X	Sifon me Tub PE,Pik. 506-558, L = 822 ml	cope	1		
12	An. XIII	Sifon me Tub PE,Pik. 551-736, L = 984 ml	cope	1		
13	An. XV	Sifon me Tub PE,Pik. 659-670, L = 186 ml	cope	1		
14	An XVIII	Pusete Shuarje Pk.113	cope	1		
15	An.X IX	Kalim tub celiku Ø558.8/5 mm L = 10 ml	cope	2		
16	An.X X	Kalim tub celiku Ø558.8/5 mm L = 8 ml	cope	3		
17	An.X XI	Kalim tub celiku Ø406.4/5 mm L = 6 ml	cope	10		
18	An. XXII	Ure kembesore HD = 0.5 m;L = 1.25 ml	cope	6		
19	An. XXIII	Ure auto HD = 0.8 m;L = 4 ml	cope	7		
20	An. XXIV	Priza tip 1	cope	15		
21	An. XXV	Priza tip 2	cope	6		
22	An. XXVI	Mbikalim Perroi HD = 0.8 m;L = 4 ml	cope	8		
		SHUMA				
		FOND REZERVE	3%			
		SHUMA				42,532,808
		TVSH	20%			
		TOTALI				

"ANGERBA"shpk & "ERALD-G"shpk

Ing.Burhan HAFIZI

PREVENTIVA TE NENOBJEKTEVE

1

AN.I. Pusete kontrolli (1.5x1.5x1.5)m

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6		
2	2.19/a	Mbushje me dhe te germuar	m ³	3		
3	3.243/1	Beton C 16/20 per puseten.	m ³	4.13		
4	3.288	Hekur betoni $\Phi > 12$, soleta.	kg	74		
5	3.288	Hekur betoni > 12 , shkalle.	kg	7.9		
6	3.624	Dy duar bitum per mure.	m ²	12.4		
7	Mater.	Kapak gize $\Phi 600$.	cope	1		
8	An	F.V.Adapter 500x200	cope	1		
SHUMA						92,105

AN.II. Pusete ajrimi (1.0x1.0x1.5)m

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	3		
2	2.19/a	Mbushje me dhe te germuar	m ³	1		
3	3.183/c	Shtrese zhavori.	m ²	2.9		
4	3.243/1	Beton C 16/20 per puseten.	m ³	2.5		
5	3.288	Hekur betoni $\Phi > 12$, soleta.	kg	55		
6	3.288	Hekur betoni > 12 , shkalle.	kg	7.9		
7	3.624	Dy duar bitum per mure.	m ²	9		
8	Mater.	Kapak gize $\Phi 600$.	cope	1		
SHUMA						48,064

AN.III.Renie me Tub PE, Pik. 196-235, L = 370 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.138	Germim dheu eksk per trase	m ³	592		
2	3.87/a	Germim me ekskavator per kanal	m ³	312		
3	3.25/b	Germim dheu toke e zakonshme	m ³	26		
4	An.5	F.V. tub PE 100 PN 6 DN 280	ml	370		
5	4.60	F.V. Tub çeliku $\Phi 273/5$ mm, L = 26 m	ton	0.8580		
6	4.112/a	Hidroizolim me 1 dore minjo dhe dy duar boje vaji	m ²	22		
7	An.6	F.V. adapter + flanaxhe DN 280	cope	4		
8	3.48/1c	Mbushje me material te germuar	m ³	320		
9	AN.IV	Pusete Hyrje Pk.196	cope	1		
10	An.V	Pusete Shuarje Pk.235	cope	1		
SHUMA						2,393,400

AN.IV. Pusete Hyrje Pk.196;325;406

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	8		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	4		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3.9		
4	3.644	F.V. Porte metalike (60x50) cm, 1 cope	kg	56.53		
5	4.3	Zgare metalike ne hyrje	kg	10		
SHUMA						58,666

AN.V. Pusete Shuarje Pk.235

2

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	18		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2.5		
3	3.243/1	Beton C 16/20 per mure dhe shtrese.	m ³	8.2		
4	An.7	F.V. tub PE 100 PN 6 DN 110,teperplotes	ml	5		
5	2.19/a	Mbushje me dhe te germuar	m ³	6		
		SHUMA				113,754

AN.VI.Renie me Tub PE, Pik. 235-266, L = 485 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.138	Germim dheu eksk per trase	m ³	776		
2	3.87/a	Germim me ekskavator per kanal	m ³	410		
3	3.25/b	Germim dheu toke e zakonshme	m ³	34		
4	An.8	F.V. tub PE 100 PN 10 DN 280	ml	485		
5	3.48/1c	Mbushje me material te germuar	m ³	380		
6	An.VII	Pusete Shuarje Pk.266	cope	1		
		SHUMA				3,445,651

AN.VII. Pusete Shuarje Pk.266;333;412

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	20		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	6		
3	3.243/1	Beton C 16/20 per mure dhe shtrese.	m ³	8.9		
4	An.7	F.V. tub PE 100 PN 6 DN 110,teperplotes	ml	5		
5	2.19/a	Mbushje me dhe te germuar	m ³	6		
		SHUMA				123,675

AN.VIII.Renie me Tub PE, Pik. 325-333, L = 98 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.138	Germim dheu eksk per trase	m ³	157		
2	3.87/a	Germim me ekskavator per kanal	m ³	82		
3	3.25/b	Germim dheu toke e zakonshme	m ³	7		
4	An.5	F.V. tub PE 100 PN 6 DN 280	ml	98		
7	3.48/1c	Mbushje me material te germuar	m ³	70		
8	AN.IV	Pusete Hyrje Pk.325	cope	1		
9	An.VII	Pusete Shuarje Pk.333	cope	1		
		SHUMA				691,458

AN.IX.Renie me Tub PE, Pik. 406-412, L = 112 ml

Nr.	NR. AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.138	Germim dheu eksk per trase	m ³	179		
2	3.87/a	Germim me ekskavator per kanal	m ³	95		
3	3.25/b	Germim dheu toke e zakonshme	m ³	8		
4	An.8	F.V. tub PE 100 PN 10 DN 280	ml	112		
7	3.48/1c	Mbushje me material te germuar	m ³	80		
8	AN.IV	Pusete Hyrje Pk.406	cope	1		
9	An.VII	Pusete Shuarje Pk.412	cope	1		
		SHUMA				948,090

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.87/a	Germim me ekskavator per kanal	m ³	650		
2	3.25/b	Germim dheu toke e zakonshme	m ³	273		
3	An.9	F.V. tub PE 100 PN 6 DN 355	ml	655		
4	An.10	F.V. tub PE 100 PN 6 DN 315	ml	167		
5	An.11	F.V. Fashete EF PN 6 DN 355x315	cope	1		
6	An.12	F.V. Fashete EF PN 6 DN 315x200	cope	3		
7	An.13	F.V. Bryl Dn 355	cope	2		
8	An.14	F.V. Bryl Dn 315	cope	2		
9	An.15	F.V. Bryl Dn 200	cope	2		
10	4.123/4	F.V.Saraçineske gize Ø 100mm	cope	1		
11	4.123/7	F.V.Saraçineske gize Ø 200mm	cope	1		
12	AN.II	Pusete Shkarkimi (1x1x1.5)m Pk.541	cope	1		
13	AN.I	Pusete Kontrolli(1.5x1.5x1.5)m Pk.551	cope	1		
14	An.16	F.V. Fashete EF PN 6 DN 315x125	cope	1		
15	3.48/1c	Mbushje me material te germuar	m ³	377		
16	AN.XI	Pusete Hyrje Pk.506	cope	1		
17	An.XII	Pusete Dalje Pk.558	cope	1		
		SHUMA				5,920,063

AN.XI. Pusete Hyrje Pk.506

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6.8		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3		
4	An.7	F.V. tub PE 100 PN 6 DN 110,teperplotes	ml	5		
5	2.19/a	Mbushje me dhe te germuar	m ³	2		
6	4.3	Zgare metalike ne hyrje	kg	10		
		SHUMA				48,449

AN.XII. Pusete Dalje Pk.558

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6.8		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3		
4	3.644	F.V. Porte metalike (40x50) cm,2 cope	kg	88.2		
5	2.19/a	Mbushje me dhe te germuar	m ³	2		
6	4.3	Zgare metalike ne hyrje	kg	10		
		SHUMA				52,180

AN.XIII.Sifon me Tub PE, Pik. 551-736, L = 984 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.87/a	Germim me ekskavator per kanal	m ³	590		
2	3.25/b	Germim dheu toke e zakonshme	m ³	205		
3	An.17	F.V. tub PE 100 PN 6 DN 200	ml	984		
4	An.15	F.V. Bryl Dn 200	cope	2		
5	An.18	F.V. Fashete EF PN 6 DN 200x25	cope	5		
6	An.3	F.V. ajrues PN 10 Dn 25	cope	5		
7	2.494/2	F.V. saracineske 1"	cope	5		
8	AN.II	Pusete Ajrimi (1x1x1.5)m	cope	5		
9	3.48/1c	Mbushje me material te germuar	m ³	385		
10	An.XIV	Pusete Dalje Pk.736	cope	1		
		SHUMA				3,300,384

AN.XIV. Pusete Dalje Pk.736

4

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3		
4	3.644	F.V. Porte metalike (40x50) cm,1 cope	kg	44.1		
5	2.19/a	Mbushje me dhe te germuar	m ³	2		
6	4.3	Zgare metalike ne hyrje	kg	10		
		SHUMA				45,763

AN.XV.Sifon me Tub PE, Pik. 659-670, L = 186 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.87/a	Germim me ekskavator per kanal	m ³	112		
2	3.25/b	Germim dheu toke e zakonshme	m ³	37		
3	An.19	F.V. tub PE 100 PN 6 DN 225	ml	186		
4	An.20	F.V. Fashete EF PN 6 DN 225x110	cope	1		
5	An.15	F.V. Bryl Dn 225	cope	2		
6	4.123/4	F.V.Saraçineske gize Ø 100mm	cope	1		
7	AN.II	Pusete Shkarkimi (1x1x1.5)m	cope	1		
8	3.48/1c	Mbushje me material te germuar	m ³	70		
9	AN.XVI	Pusete Hyrje Pk.659	cope	1		
10	An.XVII	Pusete Dalje Pk.670	cope	1		
		SHUMA				838,137

AN.XVI. Pusete Hyrje Pk.659

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3		
4	3.644	F.V. Porte metalike (40x50) cm,1 cope	kg	44.1		
5	2.19/a	Mbushje me dhe te germuar	m ³	2		
6	4.3	Zgare metalike ne hyrje	kg	10		
		SHUMA				45,763

AN.XVII. Pusete Dalje Pk.670

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	2		
3	3.243/1	Beton C 16/20 per puseten.	m ³	3		
4	3.644	F.V. Porte metalike (40x50) cm,2 cope	kg	88.2		
5	2.19/a	Mbushje me dhe te germuar	m ³	2		
6	4.3	Zgare metalike ne hyrje	kg	10		
		SHUMA				51,684

AN.XVIII. Pusete Shuarje Pk.113

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	20		
2	3.183/c	Shtrese zhavori t = 10 cm	m ²	6		
3	3.243/1	Beton C 16/20 per mure dhe shtrese.	m ³	9.7		
4	An.17	F.V. tub PE 100 PN 6 DN 200,teperplots	ml	5		
5	2.19/a	Mbushje me dhe te germuar	m ³	6		
		SHUMA				137,030

AN.XIX.Kalim tub çeliku Ø 558.8/5 mm L = 10 ml

5

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6.0		
2	4.60	F.V. Tub çeliku Ø 558.8/5 mm,L = 10 m	ton	0.683		
3	4.112/a	Hidroizolim me 1 dore minjo dhe dy duar boje vaji	m ²	17.5		
4	3.625	Hidroizolim 1KK + dy duar bitum te muret	m ²	1.4		
5	3.183/c	Shtrese zhavori t = 10 cm	m ²	6.5		
6	4.3	Zgare metalike ne hyrje	kg	10.6		
7	3.243	Beton C 16/20 per H + D	m ³	3.96		
8	3.47/1c	Mbushje me material te germuar	m ³	2.0		
		SHUMA				160,386

AN.XX.Kalim tub çeliku Ø 558.8/5 mm L = 8 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6.0		
2	4.60	F.V. Tub çeliku Ø 558.8/5 mm,L = 8 m	ton	0.5464		
3	4.112/a	Hidroizolim me 1 dore minjo dhe dy duar boje vaji	m ²	14.0		
4	3.625	Hidroizolim 1KK + dy duar bitum te muret	m ²	1.4		
5	3.183/c	Shtrese zhavori t = 10 cm	m ²	6.5		
6	4.3	Zgare metalike ne hyrje	kg	10.6		
7	3.243	Beton C 16/20 per H + D	m ³	3.96		
8	3.47/1c	Mbushje me material te germuar	m ³	2.0		
		SHUMA				138,713

AN.XXI.Kalim tub çeliku Ø 406.4/5 mm L = 6 ml

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	6.0		
2	4.60	F.V. Tub çeliku Ø 406.4/5 mm,L = 6 m	ton	0.297		
3	3.624	Hidroizolim me emulsion,dy duar bitum	m ²	7.7		
4	3.625	Hidroizolim 1KK + dy duar bitum te muret	m ²	1.4		
5	3.183/c	Shtrese zhavori t = 10 cm	m ²	6.5		
6	4.3	Zgare metalike ne hyrje	kg	10.6		
7	3.243	Beton C 16/20 per H + D	m ³	3.96		
8	An.164/1a	Mbushje me çakell	m ³	3.60		
9	3.47/1c	Mbushje me material te germuar	m ³	2.0		
		SHUMA				103,232

AN.XXII.Ure kembesore HD = 0.5 m; L = 1.25 m

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	1.0		
2	3.243	Beton C 16/20 per H + D	m ³	0.90		
3	3.288	F.V. hekur betoni >12mm	kg	9.4		
4	3.183/c	Shtrese zhavori t = 10 cm	m ²	1.4		
5	3.47/1c	Mbushje me material te germuar	m ³	1.0		
		SHUMA				12,160

AN.XXIII.Ure auto Hd = 0.8 m;L = 4 m

6

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	7.0		
2	3.47/1c	Mbushje me material te germuar	m ³	3.00		
3	3.243	Beton C 16/20 mure +shtrese	m ³	5.28		
4	3.243/1	Beton C 16/20 solete	m ³	0.58		
5	3.288	F.V. hekur betoni >12mm	kg	97.00		
6	3.183/c	Shtrese zhavori t = 10 cm	m ²	8.0		
		SHUMA				82,357

AN.XXIV.Priza tip 1

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	3.2		
2	3.183/c	Shtrese zhavorri nen beton t = 10 cm	m ²	3.8		
3	3.243	Beton C 16/20 per mure e shtrese	m ³	2.06		
4	3.644	F.V. porte metalike (40x50) cm 2 cope	kg	74.16		
5	3.47/1c	Mbushje me dhe	m ³	1.00		
		SHUMA				35,912

AN.XXV.Priza tip 2

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	8.0		
2	3.183/c	Shtrese zhavorri nen beton t = 10 cm	m ²	6.6		
3	3.243	Beton C 16/20 per mure e shtrese	m ³	3.20		
4	4.3	Zgare metalike hekur Ø 10 mm	kg	4.0		
5	3.47/1c	Mbushje me dhe	m ³	1.70		
6	An.21.	F.V kosh filter DN 32	cope	1.0		
7	2.491/c	F.V tub PE DN 32	ml	1.5		
8	2.494/1	F.V Saraçineska bronxi Ø 3/4"	cope	4		
		SHUMA				49,350

AN.XXI.Mbikalim Perroi Hd = 0.8 m;L = 4 m

N.R	NR.AN.	EMERTIMI I PUNIMIT	NJES	SASIA	CMIMI	VLEFTA
1	3.25/b	Germim dheu toke e zakonshme	m ³	7.0		
2	3.47/1c	Mbushje me material te germuar	m ³	3.00		
3	3.243	Beton C 16/20 mure +shtrese	m ³	5.28		
4	3.243/1	Beton C 16/20 solete	m ³	0.58		
5	3.288	F.V. hekur betoni >12mm	kg	97.00		
6	3.183/c	Shtrese zhavori t = 10 cm	m ²	8.0		
		SHUMA				82,357

"ANGERBA"shpk & "ERALD-G"shpk
Ing.Burhan HAFIZI