

PREVENTIV

OBJEKTI:"RIKUALIFIKIMI URBAN I LULISHTES QENDRORE PRANE BASHKISE POGRADEC"

NR	ANALIZE	EMERTIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
I. PUNIME UJITJE DHE DRENAZHIMI						
1	3.159/a	Germim e transport dheu kat II-te me skreper, L=100m dhe V=6~6.5m ³	m ³	110		
	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	162		
2	2.491/2b	F V tuba plastmasi per vaditje, Ø 32 mm	ml	48		
3	2.491/1b	F V tuba plastmasi per vaditje, Ø 25 mm	ml	465		
4	3.An-55	F V tub drenazhi Ø 150 mm	ml	401		
5	An	F.V. humus t=5 cm	m ³	77		
6	3.47/1b	Mbushje me dhe te pasuruar me humus 5 kg/m ² , h= 30 cm	m ²	1,535		
7	2.258	Nenshtrese zhavori	m ³	30		
8	3.An. 168*0.7	F.V. trendafila renaissance te ngjyrave baze dhe specifike	cope	4,605		
9	3.An	F. V Stola fiberglass importi cilesi I	cope	10		
SHUMA I						
II. PUNIME PER VENDOSJE LULESH NE LARTESI						
1	2.5	Germim dheu me krah	m ³	2.1		
2	3..243	Bllok betoni per montim konstruksioni metalik	m ³	1.7		
3	2.182+ p	Konsrtuksione metalike te perbera D1	cope	7		
	2.182+ p	Konsrtuksione metalike te perbera D2	cope	2		
4	4..112	Boje minio + boje vaji ne konstruksione metalike	m ²	280		
SHUMA II						
III .PLATFORME DRURI						
1	3.415	Ndertim I kembeve te platformes	m ³	11		
2	3.415/1	Ndertim I struktures mbajtese	m ³	2.23		
3	3.415/3	F.V Shtrese dysHEME derrase 5 cm.	m ²	48		
4	3..243	Beton per shkallet C 16/20	m ³	2.4		
5	3.416	Ura druri. Parmake me lende te sharruar	m	33.5		
SHUMA III						
IV. PUNIME NDRICIMI RRUGOR						
1	3.45/1+3.47/1a	Germim + mbushje rere e cakull kanal linje furnizimi	m ³	22.5		
2	2-480/5pr	FV tub fleksibel Ø 40;60mm me tel bari ne te	ml	170		
3	4-142/2.19.p	FV kabell elektrik Cu(5x2.5) mm ²	ml	170		
14	4.150/2x3	FV kabell elektrik Cu (3x1.5) mm ²	ml	206		
5	2-a-73	FV kunjja tokezimi xingato 4 flete H=1.5 m	cop	12		
6	3-242	Bllok betoni C12/15 fiksime kantelabri	m ³	0.9		
7	Analize	FV klema (kapuc)	cop	36		
8	3.An/53 pr	FV kantelaber ndricimi (xingato), H=3 m	cop	12		
9	3.An 55+p	F.v ndriçues “ LED “ (komplet) 60 W	cop	12		
10	3.An.55+P	F V drita tubolare	ml	28		
11	4-155/3	FV limitatore 10 A	cop	12		
12	2.490/(1d+1e): 2	FV automat 3 fazor 40- 63A	cop	1		
13	2-490/1e	FV leshues 3 fazor 60A	cop	1		
14	2-489	FV automat monofaze 25-32 A ne kasete	cop	12		
12	2-490/f	FV kasete plastike (60x45x40)cm me 2 e 3 dalje fiksuar ne mur, shtylle	kompl	2		
13	3.An/55+p	F V pusete elektrike kontrolli PVC 20x20x20cm	cope	12		
SHUMA IV						
SHUMA I ÷ III			Lek			

		FONDI REZERVE	Lek			
		SHUMA	Lek			
		TVSH 20 %	Lek			
		SHUMA ME TVSH				