

PREVENTIV

Objekti: "Ndricimi rrugor me ndricues solar led 60w per lagjet Dragot, Hyse, Qafeshkalle, Tafan", Bashkia Belsh
Investitor: Bashkia Belsh

Nr.	Anal	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Totali
I - Punime Ndertimi						
1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III (50x50x100)	m3	80		-
2	3.182/c	Shtrese rere natyrore t=20cm (50x50)	m2	60		-
3	2.262/1	Shtrese betoni C 7/10 t=10cm	m3	4		-
4	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	cope	160		-
5	3.An	FV Ndricues Led 60 w l kompletuar(Panel Fotovoltaik, bateri, kontrollor karikimi, sensor levizje	cope	160		-
					SHUMA I	-
					20 % TVSH	-
					SHUMA TOTALE	-

Shenim: Te gjitha cmimet e mesiperme I referohen Manulit te Cmimeve te vitit 2015

MIRATOI:
KRYETARI I BASHKISE BELSH
Arif TAFANI



Preventivoi: Ing. Julmir BOJA

