

PREVENTIV DS 1-2-3 (LOTI 1)

Nr	Nr.An	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
A - PUNIME PRISHJE						
1	An	Prishje pllaka ekzistuese, ulje e materialit poshte	m ²	490.30		
2	2.426/3	Prishje shtresa betoni poshte pllakave	m ³	51.65		
3	An	Prishje tavani me lese kallami	m ²	200.00		
4	An	Prishje çatie	m ²	200.00		
5	An	Prishje suvatim muri	m ²	15,373.00		
6	426	Prishje mur tulle pa pastrim	m ³	1,850.00		
7	3.158/5a	Transport mbeturinash deri 5 km	m ³	1,900.00		
B-PUNIME MURATURE						
8	64/2	Mur me tulla te zakonshme ll. M-25	m ³	350.00		
9	70/2	Mur me tulla te lehtesuara ll. M-25 (dopio)	m ³	950.00		
10	86	Mur tulle 8 vrima t=12 cm ll. M-15	m ³	550.00		
C-PUNIME SUVATIMI						
11	300	Suvatim solete	m ²	2,500.00		
12	310	Suvatim I brendshem mur tulle llac I perzier	m ²	9,000.00		
13	334	Suvatim I jashtem I zakonshem mur tulle	m ²	19,000.00		
14	An	Riparim I plasaritjeve te thella te suvase te lokalizuara me rrjete me fibra xhami alkalorezistente dhe llac I perforcuar me fibra per perforcim te muratures	m ²	500.00		
15	An	Riparim I plasaritjeve sipërfaqesore te suvase me hapje deri ne 5 mm me silixhant me baze rezinash akrilike	m ²	302.00		
16	An	F.V rrjete me fibra xhami alkalorezistente, per perforcim te muratures(1 cm)	m ²	20,000.00		
17	2.358/b	Veshje fasade me polisterol jeshil t=5cm + rrjete + suva grafiato	m ²	3,313.00		
18	2.308/a	Suvatim me grafiato h > 4 m	m ²	1,000.00		
C-NGRITJE KANTIERI						
19	3.837/a	Rrethim kantieri me rrjete teli	m ²	1,500.00		
C-PUNIME DRITARE						
20	2.375/1	FV. Dritare plastike dopio xham	m ²	200.00		
D-PUNIME BETONI						
21	117/1	Punime betoni C 20/25 kollona B/A monolite, trare, mure B/A, soleta, arkitrare	m ³	60.00		
22	166	FV. Hekur ndertimi Φ 6-10 mm	ton	2.00		
23	167	FV. Hekur ndertimi Φ >10 mm	ton	3.00		
24	121/1	Brez b/a C 16/20	m ³	50.00		
25	An	Riparim I plasaritjeve ne elemente betoni me stukim me paste apoxide Adesilex PG1 ose PG4 me rezine per injektim me plasaritje Epoje LV ose SLV	ml	200.00		
E-PUNIME SHTRESASH						
26	2.262	Shtrese betoni C6/10	m ³	37.50		
27	265/a	Shtrese me pllaka qeramike me kolle+llac cemento	m ²	333.00		
28	326/a	Veshje me pllaka majolike	m ²	150.00		
29	268/a	Bazamake shkalle mermeri t= 2.5 cm	m ²	250.00		
30	324/a	FV plintusa qeramike	m ²	160.00		
31	404/1	Lyerje me boje plastike	m ²	26,658.00		
32	404/2	Lyerje me boje plastike me baze akrilik I jashtem	m ²	54,000.00		
33	2.431	Skela metalike me tubo fasade > 12 m	m ²	54,000.00		
F-PUNIME ELEKTRIKE						
34	480/1	F.V tuba plastmasi Φ 18-21 mm	ml	1,480.00		
35	480/2	F.V tuba plastmasi Φ 22-26 mm	ml	1,250.00		
36	480/3	F.V tuba plastmasi Φ 27-31 mm	ml	1,320.00		
37	480/4	F.V tuba plastmasi Φ 31-40 mm	ml	220.00		
38	483	Priza brenda murit 10 A	cope	8.00		
39	483	F.V celesa te zakonshem brenda murit	cope	61.00		
40	An	Kuti shperndarese plastike PT6	cope	6.00		
41	An	Kuader me 5 automate + celes elektromagnetik (salvavita)	cope	2.00		
42	An	F.Vpercjelles NO7-K 1x 1.5 mm2	ml	2,650.00		
43	An	F.Vpercjelles NO7 V-K 1x 1.0 mm2	ml	2,610.00		
44	An	F.Vpercjelles NO7 V-K 1x 2.5 mm2	ml	900.00		
45	An	F.Vpercjelles NO7 V-K 1x 4.0 mm2	ml	800.00		
46	An	F.Vpercjelles NO7 V-K 1x 6.0 mm2	ml	700.00		
47	An	F.Vpercjelles NO7 W-K 1x 35 mm2	ml	1,200.00		
48	An	F.Vpercjelles NO7 W-K 1x 10 mm2	ml	1,500.00		
49	An	Kasete elektrike ne hyrje	cope	1.00		
50	487	Kuti plastike celesa dhe priza	cope	12.00		
51	An	Bokse elektrike me 25 kontator (automat e sahat komplet	cope	5.00		
52	An	Celes elektrik deviat	cope	50.00		
G-PUNIME HIDRAULIKE						
53	494/3	F.v saracineske bronzi 1"	cope	25.00		

54	516	F.V tub I xinguar 1/2"-1" dhe rakorderi	kg	500.00			
		K-PUNIME MBULIMI					
55	255	Mbulese catie me tjegulla vendi	m ²	200.00			
56	297/a	Tavan me kartonxhes	m ²	200.00			
		TOTAL					0