

PROJEKT-ZBATIM

PREVENTIV I PUNIMEVE

Objekti: "Rruget Paralele me Hekurudhen nga Kthesa e Kamzes deri te Stacioni Hekurudhor ne Kashar - Loti 1"

Nr	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.110/b	Germim dheu me ekskavator zinxhir, 1.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	20,370.00		-
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	18,122.00		-
3	An.164/1b	Mbushje me cakell	m ³	12,071.00		-
4	An.164/1a	Mbushje me material te germuar	m ³	2,248.00		-
Shuma 1						-
2 - PUNIME PER TRUPIN E RRUGES						
1	An.164/1b	Shtrese çakelli mbeturine kave t=60cm (2x30cm), perhapur e ngjeshur makineri	m ³	10,690.00		-
2	3.212/d	Shtrese stabilizant t=20cm	m ²	19,696.00		-
3	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	18,106.00		-
4	3.226/1	Shtrese asfaltbetoni me granil gure kave , 4 cm, perhapur e ngjeshur me makineri e ngjeshur me makineri	m ²	18,106.00		-
Shuma 2						-
3 - PUNIME BORDURE + KUNETE						
1	3.244	Beton C20/25 per kunete	m ³	159.00		-
2	3.243	Beton C16/20 per bordure monolite	m ³	51.00		-
3	An	FV bordura betoni 20x30 cm perfshi beton per fiksime	ml	6,075.00		-
Shuma 3						-
4 - PUNIME NE TROTUAR						
1	An	F.V. Pllaka betoni t=6cm per trotuare	m ²	2,155.00		-
2	2.261	F.V. Rere per shtrese t=4cm nen pllaka	m ³	86.20		-
3	3.243	Shtrese Beton C16/20 t=10cm	m ³	215.50		-
4	An.164/1b	Shtrese çakelli mbeturine kave t=30cm, perhapur e ngjeshur makineri	m ³	646.50		-
5	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	13.30		-
Shuma 4						-
5 - PUNIME PER STRUKTURA						
1	3.237	Struktura monolite b/betoni C 12/15 me 20% gur	m ³	3,617.00		-
2	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	ml	698.00		-
3	3.237	Themel e kokol b/betoni C 12/15 me 20% gur	m ³	36.00		-
4	3.237	Mure rrethues b/betoni C 12/15 me 20% gur	m ³	445.00		-
5	3.243	Beton C16/20 per kollona te murit rrethues	m ³	297.00		-
6	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	17.00		-
7	2.181	Konstruksione metalike te perbera	ton	49.00		-
Shuma 5						-
6 - PUNIME NE KANALIZIMET E UJRAVE TE SHIUT						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	2,840.00		-
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	2,840.00		-
3	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	118.00		-
4	An - 22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize	cope	30.00		-
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm (perfshi reren per mbrojten e tubit)	ml	2,061.00		-
6	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm (perfshi reren per mbrojten e tubit)	ml	1,075.00		-
7	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	ml	45.00		-
8	2.258	Mbushje me zhavorr	m ³	1,254.40		-
Shuma 6						-
7 - PUNIME PER NDRITIMIN E NDRICIMIT RRUGOR						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	130.00		-
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	130.00		-
3	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	cope	114.00		-
4	An	F.V. Ndricues rrugor II. Led-60w me aksesore	copë	114.00		-

5	3.An/ksh	F.V. krah nje degesh (150cm)	cope	114.00			-
6	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	114.00			-
7	3.An/et	FV elektroda tokezimi te xinguar 50x3mm, L=150cm	cope	114.00			-
8	AN	FV Morseteri shtylle 3P+sig10A+kapak	cope	114.00			-
9	AN	F.V. Kabell FG7OR 0.6/ 1KV. 5x10mm2	ml	2,841.00			-
10	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	1,026.00			-
11	2.519	Tub I brinjezuar Ø 90 mm	ml	2,841.00			-
12	An-56/M3	F.V. Tuba metalik D=140mm	ml	80.00			-
13	2.261	F.V. Rere per shtylla dhe tubacione + kompaktesim	m ³	34.20			-
14	3.240	Beton C12/15 per inkastrim shtylle	m ³	57.00			-
15	An/M3	FV kuader komandimi komplet me santeri+fotoelement	cope	2.00			-
16	An	Spostimi i shtyllave elektrike ekzistuese TM	cope	17.00			0.00
17	An	Spostimi i linjave elektrike ekzistuese TM	ml	360.00			0.00
Shuma 7							-
8 - FIBRA OPTIKE DHE SHERBIMET INXHINIERIKE NENTOKESORE							
1	3.89/a	Germim dheu	m ³	325.18			-
2	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	325.00			-
3	3.654	Furnizim, vendosje tuba I brinjezuar fleksibel ø 100	ml	5,644.00			-
4	An-56	F.V. Tub metalik D = 140mm	ml	160.00			-
5	An - 19	Puse kontrolli 0.8x0.8x1m	cope	60.00			-
6	2.261	F.V. Rere nen dhe mbi tubacione + kompaktesim	m ³	212.00			-
Shuma 8							-
9 - PUNIME SINJALISTIKE							
1	An142	Vijezime gjatesore me boje bikomponente sprajt	m2	1,021.00			-
2	An143	Vijezime me boje bikomponente paste	m2	87.00			-
3	AN158	F.V. Tabela 60x60cm	cope	13.00			-
4	An97	F V tabela rrugore STOP	cope	12.00			-
5	An	Pervijues Bardh-Kuq per hekurudha	cope	3.00			-
6	An	Tabele Kryq I San Andreas	cope	1.00			-
7	An103	F.V. Tabela Rrethore D=60	cope	25.00			-
8	An106	F.V. Tabela Trekendore 90cm	cope	12.00			-
Shuma 9							-
10 - PUNIME PRISHJE							
1	An-49	Prishje struktura prej betoni + transport	m ³	1,190.00			-
2	2.426/2	Prishje mur tulle, guri ose blloqe + transport	m ³	1,707.00			-
Shuma 10							-
Total (1-10)							-
		Fondi rezerve %	5%				-
		Shuma pa TVSH					-
		TVSH %	20%				-
		Shuma me TVSH					-

InfraKonsult
Drejtuesi Ligjor
Ing. Redi STRUGA