

**MIRATOHET
KRYETARI I BASHKISE
ERISELDA SEFA**

P R E V E N T I V I

Objekt

Objekti: REHABILITIMI I PERROIT LUSHNJE DHE RIKUALIFIKIMI URBAN I ZONAVE RRETH TIJ

A.REHABILITIMI I PERROIT						
Nr.	Nr.An	Lloji i punimeve	Njesia	Sasia	Cmimi	Vlera
		I.Punime Pastrimi				
1	3.2	Prerje bime te vogla fi 10	m ²	27600		
2	3/An-49	Prishje betoni veshje ekzistuese	m ³	280		
3	3.97/b	Gerrmim dheu me eskavator me zinxhir 0.25m ³ me shakrkim ne toke	m ³	7660		
3	3.98/a	Gerrmim dheu me eskavator me zinxhir 0.25m ³ me shakrkim nemjate	m ³	38046		
3	2.37/5a	Transport dheu auto 5Km	m ³	38046		
			SHUMA 1			
		II.Punime Sistemimi Perroi				
1	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m ³	7660		
2	2.258/2	Shtrese zhavori ne territorin e ndertesave(ne shtratin e perroit)	m ³	5424		
3	3.205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri	m ²	28824		
4	3.643	Mbjellje bari ne skarpat	m ²	20000		
5	3.244/1	Struktura te holla monolite betoni C 20/25 (Perroi)	m ³	8120		
6	2.166	F.V hekur betoni fi 6/10cm	ton	179		
7	AN.1	Fuga me polisterol t=2cm	m ²	4640		
	AN.2	Largimi I ujrave me motorr pompe	op	1,440.0		
11	An168	Fv Shkurre dekorative	cope	670		
NDERTIMI I URES PER KEMBESORE TEK PERROI LUSHNJE						
		Punime themeli				
1	2.258	Nenshtrese zhavori (t=10 cm)	m ³	20		
2	2.262/4	Shtrese betoni C16/20	m ³	40		
3	2.167	F.V Hekur periodik Ø>10mm	ton	5		
		Konstruksion Metalik				
1	2.181	Konstruksione metalike te perbera	ton	20		
2	4.109	Bojatisje mbi metal 1m ² pulverizim me alumin	m ²	300		
		Punime shtresash				
1	2.258	Nenshtrese zhavori (t=10 cm)	m ³	3		
2	2.262/4	Shtrese betoni C16/20	m ³	10		
3	2.264	Shtrese lluster cemento 1:2	m ²	26		
4	2.267/1	Shtrese me pllaka porcenalat importi	m ²	130		
		Punime me Sonda(pilota)				
1	2117/1	Kollona B/a monolite C16/20 h deri 4m	m ³	48		
2	2.167	F.V Hekur periodik Ø>10mm	ton	1		
3	An	Shpim me sonda "UKS" Ø 0.6 m, ~ 25 m,	ml	40		
		Punime Ndricimi				
1	An	F.V Krah dy degesh per shtylla metalike per ndricim	cope	4		

2	3.An/ksh	F.V Ndricues Smart me llampe 250W	cope	8		
3	3.An	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	4		
4	4.150/4	F.V Percjellsa Cu te izoluar,me gome,ne izolartor 4mm2	km	0.3		
5	4.167	F.V Togezi me mbrojtje atmosferike ne objekt me hekur shirit	ton	0.4		

SHUMA 2

III.Punime sipërfaqet e qendrimit (10 njesi)						
1	2.258	Shtese zhavori nen murin mbajtes	m3	10		
2	2.110/2	Themel e xokol butobetoni C 12/15	m3	50		
3	3.323	Mur guri mbajtes e themele, llaç çimento M50	m3	112		
4	2.262/3	Shtrese betoni 10cm	m ³	14		
5	2.258	Shtrese zhavorr trotuar 10 cm	m ³	14		
6	2.266/1	Shtrese pllaka granil me boje 30x30cm	m ²	140		
7	3.636	Parmake ure, metalik I gatshem	ton	2		

SHUMA 3

TOTALI A

B.Rruga HARUN SEFA

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
1.Punime Prishje						
1	2.426/2	Prishje mur blloqe betoni	m3	200		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	200		
					Shuma1	
2.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	150		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	150		
					Shuma2	
3.Punime shtresash						
1	3.207	Shtrese çakelli t=2x10cm, perhapur e ngjeshur me makineri	m2	6000		
2	3.212/c	Shtrese stabilizant t=15cm	m2	3000		
3	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	2500		
4	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	2500		
					Shuma 3	
4.Punime shtresash(Kryqezimet)						
1	3.207	Shtrese çakelli t=2x10cm, perhapur e ngjeshur me makineri	m2	240		
2	3.212/c	Shtrese stabilizant t=15cm	m2	120		
3	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	100		
4	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	100		
					Shuma 4	
5.Punime trotuari						
1	3.617/1	F.V bordura betoni 15x30	ml	1000		
2	2262/3	Shtrese betoni C12/15 nen bordure 10cm	m3	40		
3	2262/3	Shtrese betoni nen trotuar 10cm	m3	140		
4	2.258	Shtrese zhavorr trotuar 10 cm	m3	140		
5	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	1400		
6	3.619/a	Bordura betoni 6x20 cm	ml	1500		

7	An164	F.V. Fidane Peme dekorative	cope	83		
					Shuma 5	
		6.Pista e bicikletave				
1	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	2940		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	2940		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	2450		
4	3.224/1a	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	2450		
					Shuma 6	
		7-PUNIME K.U.B				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	378		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	378		
3	2.258	Shtrese zhavori nen tubo	m ³	33		
4	2.262/1	Shtrese betoni nen tub 10cm	m ³	33		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	656		
6	An-22/1	F.v puseta 40x40 cdo 25 cm	copë	52		
7	An-8	Mbushje me çakëll	m ³	250.0		
					Shuma 7	
		8-Punime Muri Mbajtes				
1	3.243	Struktura monolite betoni C 16/20	m3	126		
2	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.5		
3	2.167	F V hekur betoni periodik Ø > 10 mm	ton	3		
					Shuma 8	
		9.Punime elektrike				
1	3.654	F.V Tuba Plastik Ø100	ml	500		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	30		
3	3.59/b	Germim themel i vecuar, gropa sip.10-30 m ² , toke e zak. me h = 1.5 m	m3	8		
4	2.262/3	Beton per fiksimin e shtylles metalike	m3	8		
5	3.AN/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	30		
6	3.An/ksh	F.V Krah shtylla metalike	cope	30		
7	3.An	F.V Ndricues Smart me llampe 250W	cope	30		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	30		
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	m	300		
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	m	500		
					Shuma 9	
		10.Tabela rrugore e vijeze				
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	10		
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	1500		
					Shuma 10	
					TOTALI B	
C.Rruga E RE PAS KOMISARJATIT TE POLICISE L=716ml						
Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
		1.Punime Prishje				

1	2.426/2	Prishje mur blloqe betoni	m3	200		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	200		
					Shuma1	
		2.Punime germimi				
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	150		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	150		
					Shuma2	
		3.Punime shtresash				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	16310		
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	M2	7680		
3	3.207	Shtrese çakelli t=2x10cm, perhapur e ngjeshur me makineri	m2	15360		
4	3.212/c	Shtrese stabilizant t=15cm	m2	7680		
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	3840		
6	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	3840		
7	2262/3	Shtrese betoni C12/15 KUNETE	m3	77		
					Shuma 3	
		4.Punime trotuari				
1	3.617/1	F.V bordura betoni 15x30	ml	1440		
2	2262/3	Shtrese betoni C12/15 nen bordure 10cm	m3	58		
3	2262/3	Shtrese betoni nen trotuar 10cm	m3	100		
4	2.258	Shtrese zhavorr trotuar 10 cm	m3	100		
5	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	1008		
6	3.619/a	Bordura betoni 6x20 cm	ml	720		
7	An164	F.V. Fidane Peme dekorative	cope	120		
					Shuma 4	
		5.Pista e bicekletave				
1	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	860		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	860		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	860		
4	3.224/1a	Shtrese asfaltbetoni me ngjyre me granil guri kave, 3cm, me makineri	m2	860		
					Shuma 5	
		6-PUNIME K.U.B				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	378		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	378		
3	2.258	Shtrese zhavori nen tubo	m ³	31		
4	2.262/1	Shtrese betoni nen tub 10cm	m ³	31		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	768		
6	An-22/1	F.v puseta 40x40 cdo 25 cm	copë	60		
7	An - 20	Pusete shkarkimi 80 x 80, h = 150 cm	copë	15		
8	An-8	Mbushje me çakëll	m ³	300.0		
					Shuma 6	
		7-PUNIME K.U.Z				

1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	576		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	576		
3	2.258	Shtrese zhavori nen tubo	m ³	31		
4	2.262/1	Shtrese betoni nen tub 10cm	m ³	31		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	768		
6	An - 20	Pusete shkarkimi 80 x 80, h = 150 cm	copë	15		
7	An-8	Mbushje me çakëll	m ³	300.0		
						Shuma 7
8.Punime elektrike						
1	3.654	F.V Tuba Plastik Ø100	ml	720		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	60		
3	3.59/b	Germim themel i vecuar, gropa sip.10-30 m ² , toke e zak. me h = 1.5 m	m ³	13		
4	2.262/3	Beton per fiksimin e shtylles metalike	m ³	13		
5	3.AN/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	60		
6	3.An/ksh	F.V Krah shtylla metalike	cope	60		
7	3.An	F.V Ndrices Smart me llampe 250W	cope	60		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	60		
9	4.142/3.15	F.V.kabllo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm ²	m	600		
10	4.131/3.7	F.V.ne toke kabllo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm ²	m	800		
						Shuma 8
9.Tabela rrugore e vijeze						
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	10		
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	2150		
						Shuma 9
TOTALI C						

D.LASGUSH PORADECI L=600ml

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
1.Punime Prishje						
1	2.426/2	Prishje mur blloqe betoni	m ³	152		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m ³	152		
						Shuma1
2.Punime germimi						
1	An	Skarifikim shtrese asfalti me makineri	m ²	2900		
						Shuma2
3.Punime shtresash(Rruge +Degezimet)						
1	3.221/1	Shtrese binderi me granil gur kave,4cm,me makineri	m ²	3000		
2	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	3000		
3	2262/3	Shtrese betoni C12/15 kuneta anesore t=10cm	m ³	59		
4	2.258	Shtrese zhavori nen kunete t=20cm	m ³	116		
						Shuma 3
4.Punime shtresash(Rruga MUHARREM BEJTE)						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m ³	400		

2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	420		
3	2.426/2	Prishje mur blloqe betoni	m3	20		
4	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	826		
5	3.212/c	Shtrese stabilizant t=15cm	m2	826		
6	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	474		
7	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	475		
10	2262/3	Shtrese betoni C12/15 kuneta anesore t=10cm	m3	9.5		
11	2.258	Shtrese zhavori nen kunete t=20cm	m ³	19		
12	3.617/1	F.V bordura betoni 15x30	ml	190		
13	2262/3	Shtrese betoni C12/15 nen bordure 10cm	m3	9.5		
14	2262/3	Shtrese betoni nen trotuar 10cm	m3	15		
15	2.258	Shtrese zhavorr trotuar 10 cm	m3	15		
16	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	143		
17	3.619/a	Bordura betoni 6x20 cm	ml	95		
18	An164	F.V. Fidane Peme dekorative	cope	16		
19	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	114		
20	3.212/a	Shtrese stabilizanti t=5cm	m2	114		
21	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	114		
22	3.224/1a	Shtrese asfaltobetoni me ngjyre me granil guri kave, 3cm, me makineri	m2	114		
					Shuma 4	
		5.Punime trotuari				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(20cm)	m3	210		
2	3.617/1	F.V bordura betoni 15x30	ml	854		
3	2262/3	Shtrese betoni C12/15 nen bordure 10cm	m3	34		
4	3.212/b	Shtrese stabilizant t=10cm	m2	1046		
5	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	1046		
6	3.619/a	Bordura betoni 6x20 cm	ml	200		
7	An164	F.V. Fidane Peme dekorative	cope	100		
					Shuma 5	
		6.Pista e bicikletave				
1	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(20cm)	m3	156		
2	3.212/b	Shtrese stabilizant t=10cm	m2	780		
3	3.221/1	Shtrese binderi me granil gur kave,4cm,me makineri	m2	780		
4	3.224/1a	Shtrese asfaltobetoni me ngjyre me granil guri kave, 3cm, me makineri	m2	780		
5	An1	Guardrail- N2 anesore me 2 valez. ne 1 ane , W2 + aksesor	ml	210		
					Shuma 6	
		7.Mure rrethues				
1	2.109/2	Themel e xokol betoni C - 12/15	m3	70		
2	2.88	Mur me blloqe betoni t=20cm deri 3m me llaç perzier M 15	m3	70		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m +koloneta	m3	15		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.5		
5	AN	Zgare metalike per rrethim h=1ml	m2	350		

					Shuma 7	
		8-PUNIME K.U.B				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	190		
2	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	190		
3	2.258	Shtrese zhavori nen tubo	m ³	15.3		
4	2.262/1	Shtrese betoni nen tub 10cm	m ³	15.3		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	381		
6	An-22/1	F.v puseta 40x40 cdo 25 cm	copë	30		
7	An - 20	Pusete shkarkimi 80 x 80, h = 150 cm	copë	8		
8	An-8	Mbushje me çakëll	m ³	95.0		
					Shuma 8	
		9.Punime elektrike				
1	3.654	F.V Tuba Plastik Ø100	ml	600		
2	3.An/57b	F.V Pusete elektrike PVC 40X40X40 cm	cope	24		
3	3.59/b	Germim themel i vecuar, gropa sip.10-30 m ² , toke e zak. me h = 1.5 m	m3	6		
4	2.262/3	Beton per fiksimin e shtylles metalike	m3	6		
5	3.AN/53	F.v Shtylla metalike per ndricim H=7m d=160mm	cope	24		
6	3.An/ksh	F.V Krah shtylla metalike	cope	24		
7	3.An	F.V Ndrices Smart me llampe 250W	cope	24		
8	3.An/et	F.V Elektroda togezimi te xinguara 50x3 mm l=150cm	cope	24		
9	4.142/3.15	F.V.kablo kontrolli Cu te armuar, ne mure e konstruksione, 4x2.5 mm2	ml	240		
10	4.131/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulesa plastmasi, te armuar, 4x25mm2	ml	600		
11	An	Cmontim 3 fije teli al S=35 mm2	km	0.6		
12	3.568	Punime izolimi per linja TU 6÷10 kv me izolator mbeshtetes	cope/ shtylle	30		
13	3.549/1	Shtirije terheqje teli 3 fije (percjellsa makineri alumuni seksion 35 mm2)	km	0.6		
14	An	Heqje dhe vendosje shtylla centrifugale b/a, h=8 m	cope	30		
					Shuma9	
		10.Tabela rrugore e vijeze				
1	An155	F V tabela rrugore te ndryshme D=90cm	cope	10		
2	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	2304		
					Shuma 10	
					TOTALI D	
					SHUMA A-D	
					Fond.Rez.5%	
					SHUMA	
					Tvsh 20%	
					SHUMA TOTALE	

Ing.Ariola Beqo
Ing.Djana Qorri
Ing.Brunilda Bekaj
Ing.Ersi Veliu

Ing.Fredi Dervishi
Ing.Gani Myzeqari
Ark.Teo Kola
Ing.Arben Muca

Sektori I Zhvillimit te Territorit
Ark. Sajmir Mebelli

Sektori i Projektimit
Ark. Alban Manoku

Drejtoria e Planifikimit dhe Zhvillimit te Territorit
Ing.Mimoza Haxhiu