

## PREVENTIVI I PUNIMEVE

**Objekti: " Mirembajtje e ambienteve te Spitalit Rajonal Diber "Rrahim Xhika"**  
**Autoriteti Kontraktor : Drejtoria Spitalit Rajonal Diber**

Nr.	Nr. An	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
	<b>I</b>	<b>Punime sistemimi parkingu</b>				
1	3.137	Germim dheu me ekskavator goma 0.15 m <sup>3</sup> , ne themele, toke zak, kategoria III,	m3	50		-
2	3.45/1	Germim me krahe, toke e zakonshme	m3	20		-
3	3.158/5a	Transport dheu me auto deri ne 5.0 km	m3	50		-
4	3.47/1b	Mbushje , rrafshim , ngjeshje materialin te germuar me pare	m3	50		-
5	3.193/a	Shtrese zhavor lumi t=10cm, me cilindrim	m2	200		-
6	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, (per sheshimin e bazamentit te trotuarit)	m3	100		-
7	2.261	Shtrese rere t=5 cm	m3	3		-
8	an 18	Shtrese pllaka betoni	m3	4		-
9	3.620 T	Trotuar, me 6 cm beton,	m2	100		-
10	3.619/a	Bordura betoni 6x20 cm	ml	100		-
						-
						-
	<b>II</b>	<b>Punime ne rrjetin e kanalizimeve</b>				
1	3.44/1	Germim kanalesh ne toke te bute, me krahe, me seksion deri 0.75 m <sup>2</sup>	m3	40		-
2	3.48/a	Rrafshim skarpatesh, me krahe, ne germim toke te bute	m2	300		-
						-
						-
						-
	<b>III</b>	<b>Rehabilitim Urgjenca</b>				
1	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	240		-
2	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	100		-
3	an 7	Heqje dyer dritare	cope	10		-
4	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m <sup>3</sup>	55		-
5	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	60		-
6	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	240		-
7	2.328	Patinim muri allçi (stuko)	m <sup>2</sup>	200		-
8	2.33	Patinim tavani allçi (stuko)	m <sup>2</sup>	150		-
9	2.297/b	Veshje muri me kartonxhes	m2	20		-
10	an 13	Veshje dysheme me shtrese gome 5mm	m2	280		-
11	2.375/1	F. v. dritare plastike me dopio xham	m <sup>2</sup>	25		-
395/1	2.395/1	F.v. dyer dritare plastike me dopio xham	m2	6		-
12	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	540		-
13	3.624	Hidroizolim me 2duar bitum I nxehte wc	m2	8		-
14	2.262/3	Shtrese betoni C-12/15 t=2-3cm nivelim	m3	0.2		-
15	2.326	Veshje me pllaka majolike ne wc h=1.5m	m2	8		-
16	2.267/a	Shtrese me pllaka grez porcelanato dysheme	m2	8		-

17	2.495	F.V lavaman porcelani importi me mishelator	cope	1	-
18	2.501	F.V WC allafranga porcelani importi	cope	1	-
19	2.515	F.V pilete dysHEMEJE d = 50 mm	cope	1	-
20	An	F.V tub plastmasi b=42mm(shkarkime)	ml	8	-
21	2.491/1a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.3 mm, PN 20	ml	10	-
					-
					-
					-
	<b>IV</b>	<b>Rehabilitim Urgjenca Pediatrise</b>			
1	2.426	Prishje mur tulle pa pastrim	m <sup>3</sup>	2	-
2	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	240	-
3	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	100	-
4	an 7	Heqje dyer dritare	cope	10	-
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m <sup>3</sup>	55	-
6	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	100	-
7	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	240	-
8	2.375/1	F. v. dritare plastike me dopio xham	m <sup>2</sup>	40	-
9	2.328	Patinim muri allçi (stuko)	m <sup>2</sup>	200	-
10	2.33	Patinim tavani allçi (stuko)	m <sup>2</sup>	150	-
11	2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m <sup>2</sup>	100	-
12	2.375/1	F. v. dritare plastike me dopio xham	m <sup>2</sup>	4	-
13	2.373/1	F. v. vetrare plastike me dopio xham	m <sup>2</sup>	10	-
14	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	100	-
15	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	580	-
16	3.624	Hidroizolim me 2duar bitum I nxehte wc	m <sup>2</sup>	10	-
17	2.262/3	Shtrese betoni C-12/15 t=2-3cm nivelim	m <sup>3</sup>	0.4	-
18	2.326	Veshje me pllaka majolike ne wc h=1.5m	m <sup>2</sup>	20	-
19	2.267/a	Shtrese me pllaka grez porcelanato dysHEME	m <sup>2</sup>	22	-
20	2.495	F.V lavaman porcelani importi me mishelator	cope	2	-
21	2.501	F.V WC allafranga porcelani importi	cope	2	-
22	2.515	F.V pilete dysHEMEJE d = 50 mm	cope	2	-
23	An	F.V tub plastmasi b=42mm(shkarkime)	ml	20	-
24	2.491/1a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.3 mm, PN 20	ml	40	-
					-
					-
					-
	<b>V</b>	<b>Ambientet e guzhines</b>			
1	2.426	Prishje mur tulle pa pastrim	m <sup>3</sup>	3	-
2	an 2	Prishje suva solete	m <sup>2</sup>	100	-
3	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	100	-
4	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	160	-
5	an 7	Heqje dyer dritare	cope	8	-
6	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m <sup>3</sup>	15	-
7	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	60	-
8	2.3	Suva solete, me drejtues, me krah	m <sup>2</sup>	100	-
9	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	100	-
10	2.328	Patinim muri allçi (stuko)	m <sup>2</sup>	150	-
11	2.33	Patinim tavani allçi (stuko)	m <sup>2</sup>	150	-
12	an 14	Veshje mure me shtrese gome 3mm	m <sup>2</sup>	80	-
13	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	100	-
14	2.326	Veshje me pllake majolike	m <sup>2</sup>	100	-

14	2.375/1	F. v. dritare plastike me dopio xham	m <sup>2</sup>	10	-
15	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	400	-
					-
					-
					-
	<b>VI</b>	<b>Korridori I Imazherise</b>			
1	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	200	-
2	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	100	-
4	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m <sup>3</sup>	10	-
5	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	100	-
6	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	200	-
7	an 14	Veshje mure me shtrese gome 3mm	m <sup>2</sup>	100	-
8	2.328	Patinim muri allçi (stuko)	m <sup>2</sup>	120	-
9	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	100	-
10	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	300	-
11	3.624	Hidroizolim me 2duar bitum I nxehte wc	m <sup>2</sup>	8	-
12	2.262/3	Shtrese betoni C-12/15 t=2-3cm nivelim	m <sup>3</sup>	0.4	-
13	2.326	Veshje me pllaka majolike ne wc h=1.5m	m <sup>2</sup>	20	-
14	2.267/a	Shtrese me pllaka grez porcelanato dysHEME	m <sup>2</sup>	10	-
15	2.495	F.V lavaman porcelani importi me mishelator	cope	2	-
16	2.501	F.V WC allafranga porcelani importi	cope	2	-
17	2.515	F.V pilete dysHEMEJE d = 50 mm	cope	2	-
18	An	F.V tub plastmasi b=42mm(shkarkime)	ml	20	-
19	2.491/1a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.3 mm, PN 20	ml	40	-
					-
					-
					-
	<b>VII</b>	<b>Sherbimi kirurgjise dhe Patologjise</b>			
1	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	100	-
2	an 2	Prishje suva solete	m <sup>2</sup>	100	-
3	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	50	-
4	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	140	-
5	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	300	-
6	2.3	Suva solete, me drejtues, me krah	m <sup>2</sup>	100	-
7	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	100	-
8	2.328	Patinim muri allçi (stuko)	m <sup>2</sup>	300	-
9	2.33	Patinim tavani allçi (stuko)	m <sup>2</sup>	300	-
10	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	50	-
11	2.326	Veshje me pllake majolike	m <sup>2</sup>	150	-
12	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	800	-
13	analize	Montim-Cmontim Tub bakri 12 sistemi oksigjenimit	ml	100	-
14	analize	Montim-cmontimTub bakri 15 sistemi oksigjenimit	ml	150	-
15	analize	Montim-cmontim Tub bakri 18 sistemi oksigjenimit	ml	200	-
16	analize	Montim-cmontimTub bakri 22 sistemi oksigjenimit	ml	300	-
17	3.624	Hidroizolim me 2duar bitum I nxehte wc	m <sup>2</sup>	25	-
18	2.262/3	Shtrese betoni C-12/15 t=2-3cm nivelim	m <sup>3</sup>	1	-
19	2.326	Veshje me pllaka majolike ne wc h=1.5m	m <sup>2</sup>	40	-
20	2.267/a	Shtrese me pllaka grez porcelanato dysHEME	m <sup>2</sup>	25	-
21	2.495	F.V lavaman porcelani importi me mishelator	cope	3	-
22	2.501	F.V WC allafranga porcelani importi	cope	3	-
23	2.515	F.V pilete dysHEMEJE d = 50 mm	cope	3	-

24	An	F.V tub plastmasi b=42mm(shkarkime)	ml	60	-
25	2.491/1a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.3 mm, PN 20	ml	100	-
					-
	<b>VII</b>	<b>Punime gipsi ne korridore</b>			
1	2.297/a	Tavan me kartonxhes	m <sup>2</sup>	100	-
2	2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m <sup>2</sup>	200	-
3	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	140	-
					-
	<b>IX</b>	<b>Mirembajtje te brendeshme ne Pavionin e Obstetrike - Gjinekologjise</b>			
1	an 3	Prishje suva brenda mur tulle	m <sup>2</sup>	150	-
2	an 5	Prishje shtres pllaka dhe nenshtresa	m <sup>2</sup>	180	-
3	2.31	Suva brenda mur tulle, me krah, llaç perzier M 25	m <sup>2</sup>	150	-
4	2.267/a	Shtrese me pllaka grez porcelanato	m <sup>2</sup>	180	-
5	3.624	Hidroizolim me 2duar bitum I nxehte wc	m <sup>2</sup>	14	-
6	2.262/3	Shtrese betoni C-12/15 t=2-3cm nivelim	m <sup>3</sup>	0.6	-
7	2.326	Veshje me pllaka majolike ne wc h=1.5m	m <sup>2</sup>	18	-
8	2.267/a	Shtrese me pllaka grez porcelanato dysHEME	m <sup>2</sup>	22	-
9	2.495	F.V lavaman porcelani importi me mishelator	cope	2	-
10	2.501	F.V WC allafranga porcelani importi	cope	2	-
11	2.515	F.V pilete dysHEMEJE d = 50 mm	cope	2	-
12	An	F.V tub plastmasi b=42mm(shkarkime)	ml	51	-
13	2.491/1a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.3 mm, PN 20	ml	80	-
14	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	1350	-
15	analize	Cmontim, pastrim dhe montim tubave dhe radiatoreve te sistemit te ngrohjes	ml	160	-
					-
	<b>X</b>	<b>Mirembajtje te jashteme</b>			
1	an 4	Prishje suva jashte mur tulle	m <sup>2</sup>	290	-
2	2.334	Suva e zakonshme fasade mur tulle mbi 8m lartesi	m <sup>2</sup>	290	-
3	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	700	-
					-
	<b>XI</b>	<b>Punime hidroizolimi</b>			
1	an 1	Prishje çati me tjegulla qeramike	m <sup>2</sup>	100	-
2	2.200	Shtrese lluster cemento 1:2, t = 20 mm	m <sup>2</sup>	100	-
3	2.200/1	Termoizolim solete t=20 cm me polisterol cilesi e I-re	m <sup>2</sup>	100	-
4	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m <sup>2</sup>	100	-
5	2.203/a	Veshje kornize llamarine bakri t = 0.8 mm	m <sup>2</sup>	100	-
6	2.209/b	Ulluk shkarkimi vertikal me baker Ø 120	ml	200	-
7	2.212/b	Ulluk shkarkimi horizontal me baker 33cm	ml	150	-
8	2.206/b	Kasete shkarkimi me llamarine bakri 1.0mm	cope	14	-
9	2.219	Çati vendi zakonshme HD~8m, mbuluar, tjegulla marseleze	m <sup>2</sup>	100	-
9	2.334	Suva e zakonshme fasade mur tulle mbi 8m lartesi	m <sup>2</sup>	130	-

						-
	<b>XII</b>	<b>Punime Elektrike</b>				
1	4.149/2	F.V percjellesa CU te izoluar me gome, per ndricim ne tubot e vendosur me pare, seksion 1.5 mm2.	ml	500		-
2	4.149/3	F.V percjellesa CU te izoluar me gome, per ndricim ne tubot e vendosur me pare, seksion 2.5 mm2.	ml	410		-
3	An.4.149/4	F.V percjellesa CU te izoluar me gome, per ndricim ne tubot e vendosur me pare, seksion 3*4.0 mm2.	ml	200		-
4	An.4.149/3	F.V. Kabell bakri me izolim dhe veshje PVCm ;;K.Z. FG7-OR ; S=3x2.5 mm2	ml	220		-
5	An.4.149/2	F.V. Kabell bakri me izolim dhe veshje PVCm ;;K.Z. FG7-OR ; S=3x1.5 mm2	ml	220		-
						<b>0</b>
		<b>SHUMA I+II+III+IV+V+VI+VII+VIII+IX+X+XI+XII</b>				-
		<b>TVSH</b>				-
		<b>SHUMA TOTALE</b>				-

**Shenime:**

Cmimet e preventivit jane ne baze te VKM Nr.627 date 15.07.2015 (manuali I cmimeve)

Zerat ne shenim tek nr i Analizes An jane mare ne manualin e vitit 2015 dhe kane ne manual po te njejtin shenim An

Ne zerin 2.404/1 te analizes nuk eshte perlogaritur vlera e materialeve pasi AK I disponon vete

Punoi:

**"ARABEL-STUDIO" Sh.p.k.**

Administratore

Ana NISHKU