

PREVENTIV

Objekti :RIKONSTRUKSIONI I INFRASTRUKTURES HYRJE DALJE PARKIMI I QENDRES SPITALORE ELBASAN + FASADA URGJENCA E VJETER DHE ADMINISTRATA BASHKE ME SHPRONESIMIN

Nr.	Nr anal	Emertimi I punimit	Njesia	Sasia	Cmimi	Vlera
1- Punime ne ndertimit e parkimi nr 1			PREVENTIV			
1	3.138	Germim dheu me zinxhir 50 cm , ne themele gjeresi, toke zak, kategoria III, me shkarkim ne toke.	m3	510.00		
2	2.112/2	Mur Buto Betoni C-12/15	m³	150.00		
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m²	1,015.00		
4	2.342	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize	cope	3.00		
5	2.598	Pusete shkarkimi b/a, 50 x 50 cm, h = 150 cm	cope	1.00		
6	2.261	Shtrese rere	m3	50.00		
7	3.An/1t	FV Tuba te brinjezuar HDPE SN8 d=315 mm	ml	50.00		
8	2.37/5b	Transport materiali material ndertimi , dheu deri 10.0 km	m³	510.00		
9	3.618	F.V Bordura betoni 20 x35 cm	m/l	135.00		
10	3.238	Shtrese betoni nen bordura, C6/10, t=10cm	m³	10.00		
11	1.1 Punime ne asfaltim e					
12	2.426/1	Shtrese stabilizant t=15cm	m²	1,015.00		
13	2.426/3	Shtrese binderi me granil gur kave,6cm,me makineri	m²	1,015.00		
14	2.37/5b	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m²	1,015.00		
		Shuma 1				
2- Punime ne ndertimit e parkimi Nr 2						
15	3.138	Germim dheu me zinxhir 50 cm , ne themele gjeresi, toke zak, kategoria III, me shkarkim ne toke.	m3	700.00		
16	An 22	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize	cope	5.00		
17	An-22/1	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	2.00		
18	2.261	Shtrese rere t=50 cm	m3	40.00		
19	3.An/1t	FV Tuba te brinjezuar HDPE SN8 d=315 mm	ml	160.00		
20	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(h20cm)	m²	960.00		
21	2.37/5b	Transport materiali material ndertimi , dheu deri 10.0 km	m³	700.00		
22	3.618	F.V Bordura betoni 20 x35 cm	m/l	100.00		
23	3.238	Shtrese betoni nen bordura, C6/10, t=20cm	m³	10.00		
24	2.1 Punime ne asfaltim e					
25	2.426/1	Shtrese stabilizant t=15cm	m²	960.00		
26	2.426/3	Shtrese binderi me granil gur kave,6cm,me makineri	m²	960.00		

27	2.37/5b	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ²	960.00		
Shuma 2						
3- Punime ne rruge nga parkimi nr-1 deri tek dalja nga						
28	3.104/b	Germim dheu me eskavator 0.5 m ³ , b>2m , toke zak , kategoria IV me shk ne mjet	m ³	900.00		
29	An-22/1	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	15.00		
30	3.An/1t	FV Tuba te brinjezuar HDPE SN8 d=315 mm	ml	360.00		
31	2.261	Shtrese rere t=50 cm	m ³	90.00		
32	an	Shtrese Betoni ne kunete	m ³	36.00		
33	An.164/1a	Mbushje me çakell e gur gurore ne trupin e rruges , perhapur ngjeshur me makineri (h=20cm)	m ³	435.00		
34	3.212/a	Shtrese stabilizant t=15cm	m ²	1,405.00		
35	3.222/2	Shtrese binderi me granil gur kave,6 cm,me makineri	m ²	1,405.00		
36	2.37/5b	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ³	1,405.00		
37	3.158/5a	Transport dheu me auto deri ne 5.0 km	m ³	900.00		
Shuma 3						
4- Punime ne trotuarin e rruges se re						
38	3.104/b	Germim dheu me eskavator 0.5 m ³ , b>2m , toke zak , kategoria IV me shk ne mjet	m ³	430.00		
39	3.158/5a	Transport dheu me auto deri ne 5.0 km	m ³	430.00		
40	An.164/1a	Mbushje me çakell e gur gurore ne trupin e rruges , perhapur ngjeshur me makineri (h=20cm)	m ³	144.00		
41	2.426/1	Shtrese stabilizant t=15cm	m ²	720.00		
42	3.244/1	Shtrese betoni, C20/25, t=10cm	m ³	72.00		
43	3.238	Shtrese betoni nen bordura, C6/10, t=10cm	m ³	14.40		
44	3.618	F.V Bordura betoni 20 x35 cm	m/l	360.00		
45	2.261	Shtrese rere t=50 cm	m ³	72.00		
46	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	540.00		
47	An169	F.V peme dekorative cdo 6 m	cope	100.00		
Shuma 4						
5- Punime ne ri-veshje asfalti prane Godines "Pathologjise dhe urgjences se Vjeter "						
48	2.426/3	Shtrese binderi me granil gur kave,6cm,me makineri	m ²	870.00		
49	2.37/5b	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ²	870.00		
50	An - 19	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	4.00		
Shuma 5						
6- Punime ne trotuarin e hyrjes kembesore						
51	3.244/1	Shtrese betoni, C20/25, t=10cm	m ³	18.00		
52	2.261	Shtrese rere t=10 cm	m ³	18.00		
53	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	185.00		
Shuma 6						
7- Punime Per Sinjalistike						
54	An131	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm.Termoplastike (paste)	ml	1,700.00		

52	An132	Vijezim shirita gjatesor dhe anesor me gjeresi 25 cm. Bikomponente (sprajt)	ml	450.00		
Shuma 7						
8. Punime suvatimi,veshje e bojatisjeje URGJENCA E VJETER						
56	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m2	100.00		
57	2.196	Hidroizolom tarace me 2 shtresa katrama	m2	81		
58	2.404/1	Boje hidroplastike importi cilesi e I-re	m2	800.00		
59	anal	F.V Kornize dekorative fasade	m/l	254.00		
60	anal	F.V Grila per dritare	m2	130.50		
Shuma 8						
9. Punime suvatimi,veshje e bojatisjeje "Godina Administrates"						
61	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m2	280.00		
62	2.404/1	Boje hidroplastike importi cilesi e I-re	m2	780.00		
Shuma 9						
10. Punime ne ndricim dhe inerneti						
63	3.167	FV shtylla metalike konike ndricimi H=9m PAICC-3	cope	26.00		
64	3.175	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	cope	26.00		
65	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	26.00		
66	3.182	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	26.00		
67	4.150/7	F.V. percjellesa Cu te izoluar me gome, per ndricim,ne izolator, sexion 16mm2	km	0.41		
68	3.172	Furnizim Vendorsje Kuader komandimi Komplet me sanferi+fotoelement	cope	1.00		
69	2.521	Tub kanalizimi pvc Ø 140 mm	ml	600.00		
70	3.654	F.V tub plasmasi φ100mm	m	290		
71	2.481/2	F.V percjelles PV-500 Ø 2 x 2.5 mm2 per kamerat e siguris	ml	290		
SHUMA 10						