



BASHKIA BERAT
PREVENTIV

Objekti: Ndertim mur guri mbajtes ne lagjen 28 Nentori ,prane baneses se znj.Monda Shabani

Nr	Analiza	Emertimi i punimeve	Njesia	Sasia
1	2.1/a	Germim dheu pas mureve	m2	352
2	2.1/a	Germim dheu me krah e transport me k dore 10 m ,kategoria e IV	m3	360
3	2.52/2	Mur guri themel e xokol me llaç perzier M 25	m3	132
4	2.54/2	Mur guri ne lartesi deri 3m me llaç çimento M 25	m3	150
5	2.121/1	Brez b/a	m ³	26.0
6	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.9
8	2.37/5a	Transport materiale ndertimi ,dheu me auto deri 5.0 km	m ³	720
9	3.652	Furnizim, vendosje tuba plastmasi ø 200(me vrima per drenazh pas mureve)	m	42
10	3.653	Furnizim, vendosje tuba plastmasi ø 150(ne mur per kullimin e ujrave cdo 10 m)	m	28
11	3.An-9	Mbushje me zhavor pas mureve	m ³	360
		Shuma		
		TVSH		
		SHUMA		