

PREVENTIV
Rikonstruksion i shkollës 9-vjecare Razi Leka

Nr	Nr. Anal	Emertimi	Njesia	Sasia	Cmimi/ Niesi	Vlera
A PUNIME PRISHJE						
1	2.426/5	Prishje mure dhe shtresa betoni	m ³	28		-
3	An	Hegje dritaresh +largim nga objekti	m ²	150		-
4	An	Hegje dyer druri+largim nga objekti	m ²	75		-
5	An	Hegje davancale dritaresh	m ²	65		-
6	An	Hegje kangjella dritaresh dhe largim nga objekti	m ²	42		-
7	An	Prishje pllaka cimentoje	m ²	1,350		-
8	An	Prishje suvatim muri I brendshem + tavan	m ²	2,212		-
9	An	Prishje suvatim muri I jashtem	m ²	755		-
10	2.426	Prishje mur tulle pa pastrim	m ³	6		-
11	2.426/5	Prishje mure dhe shtresa betoni	m ³	41		-
12	An	Prishje e rrjetit elektrik egzistues	njesi	1		-
13	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m ³	235		-
					SHUMA A	-
B PUNIME DHEU						
1	2.25/a	Germim themele e plinta b~2m, ekskavator me goma, kova 0.25m ³ shkarkim toke	m ³	322		-
2	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m ³	75		-
3	2.37/5a	Transport dheu me auto deri 5.0 km	m ³	397		-
4	2.410	Parapet shkalle e ballkone mur tulle+suva+koriman granili	m ²	75		-
					SHUMA B	-
C PUNIME MURATURE						
1	2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m ³	18		-
2	2.86	Mur me tulle me 6 vrima, t=12cm, h~3m, llaç perzier M15	m ³	8		-
3	2.64/1	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 15	m ³	4		-
					SHUMA C	-
D PUNIME BETONI						
1	2.121/1	Brez b/a mbi themel	m ³	135		-
2	2.121/1	Brez b/a mbi mure	m ³	12		-
4	2.119/1	Arkitrare b/a	m ³	18		-
5	2.119/1	Trare themeli b/a	m ³	35		-
6	2.119/1	Trare + kolona b/a	m ³	105		-
7	2.122/1a	Soleta te plota b/a C 20/25 t = 18 cm, h ~ 4m	m ³	95		-
8	2.256/b	Mbulim çatie me panele sanduich	m ²	820		-
9	2.166	Hekur betoni I zakonshem	Ton	85		-
10	2.413	Konstruksion metalik (Shkallet e emergjences, mbulimi I palestres, parmaket)	Ton	15		-
11	An -47	Galvanizim konstruksion metalik	kg	21		-
12	2.117/1	Kollona b/a M-250	m ³	42		-
					SHUMA D	-
D PUNIME TARACE						
1	2.264	Shtrese lluster cemento 1:2 per nivelim	m ²	515		-
2	2.196/c	Hidroizolim 3 duar bitum =2 shtresa	m ²	515		-
4	2.203	Veshje kornize llamarine xingat	m ²	42		-
5	2.66/2	Mure tulle t=12 cm per parapet	m ³	18		-
6	2.209	Ulluge vertikale PWc d.100	ml	166		-
7	2.212	Ulluge horizontale PWc d.101	ml	146		-
8	2.206	Kaseta shkarkimi	cope	20		-
9	2.219	Cati vendi kapriat derrase,tjegulla importi	m ²	795		-
					SHUMA D	-
E PUNIME SHTRRESASH						
1	2.258	Shtrese zhavori	m ³	250		-
2	2.264	Shtrese lluster cemento 1:2 per nivelim	m ²	1,320		-
3	2.283	Shtrese Stirobetoni	m ³	69		-
4	2.423/a	Shtrese avullizoluese gjeotekstil	m ²	750		-
5	2.166	F V hekur betoni periodik Ø 6 - 10 mm	Ton	5		-
6	2.262/4	Shtrese betoni C 16/20	m ³	72		-
7	2.195	Hidroizolim me dy duar bitum dyshemeja	m ²	740		-
8	2.267/a	Shtrese me pllaka grez porcelanato	m ²	1,320		-
9	2.324a	Plintuse pllake Grez	ml	1,150		-
10	2.267/a	Kapak parapeti me mermer 3 cm	m ²	28		-
11	2.267/a	Veshje e shkalleve me mermer 3 cm	m ²	35		-
					SHUMA E	-
F PUNIME SUVATIMI VESHJE						
1	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	2,280		-
2	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm +	m ²	778		-

Nr	Nr. Anal	Emertimi	Njesia	Sasia	Cmimi/ Niesi	Vlera
3	2.340	Suva xokoli me granil e cimento te bardhe	m ²	652		-
4	2.300	Suva solete h ~ 4 m me drejtues, me krah	m ²	1,370		-
5	2.297/a	Tavan me kartonxhes (cementato)	m ²	45		-
SHUMA F						-
G PUNIME DYER E DRITARE						
1	2.375/a	Dritare d/alumini dyfish xham.	m ²	158		-
2	2.383/1	F V dyer te brendeshme druri importi cilesi e l-re.	m ²	81		-
3	2.395/a	Dere d/alumini pa xham,me mbushje d/a.	m ²	18		-
4	2.373	Vetrato xhami	m ²	9		-
SHUMA G						-
H PUNIME BOJATISJE						
1	2.404/1	Boje hidroplastike importi cilesi e l-re	m ²	5,080		-
SHUMA H						-
I PUNIME TE NDRYSHME						
I PUNIME TE NDRYSHME						
1	2.273/1	Shtrese pllaka mermeri t = 30 mm	m ²	35		-
2	2.401	Boje vaji sipërfaqe metalik	m ²	116		-
3	2.412	F.V. Parmake metalizato ne shkalle	ton	0		-
4	2.413	F.V zgara dekorativa hekuri me figuracion mesatare	ton	3		-
5	An	F.V porte metalike dekorative rreshqitese	m ²	10		-
SHUMA I						-
J PUNIME HIDROSANITARE						
1	2.1/a	Germim dheu me krah e transport me k dore 10 m, kategoria IV	m ³	56		-
2	2.425/3	Grop Septik V=16m ³	cope	1		-
3	2.575	Puseta kontrollo 1x1x1.5m	cope	4		-
4	An-7	F.V Tuba PVC Ø 315 mm per linja te jashtme	ml	188		-
5	2.523	Tub kanalizimi pvc Ø 200 mm	ml	56		-
6	2.491/a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.0 mm, PN 10	ml	210		-
7	2.491/b	F.V Tuba e rakorderi ujesjellesi PE d=25mm, t = 2.0 mm, PN 10	ml	82		-
8	2.520	Tub kanalizimi pvc Ø 110 mm	ml	68		-
9	An	Kapuc ajrimi ne tarace ø110 mm	cope	4		-
10	2.494/1	F.V saracineska bronzi Ø 3/4 " = 20 mm	cope	10		-
11	An	Valvula 1	cope	2		-
12	2.494/2	F.V saracineska bronzi Ø 1 " = 25 mm	cope	2		-
13	2.495	F.V lavaman porcelani importi me mishelator	cope	4		-
14	2.501	F.V WC allafrenga importi	cope	6		-
15	2.506	F.V bide importi porcelani	cope	6		-
16	2.515	F.V pilete dyshemeje Ø 50 mm	cope	8		-
17	An-13	F V rezervuari zingato 1000 litra	cope	2		-
SHUMA J						-
K PUNIME ELEKTRIKE						
1	2.1/a	Germim dheu me krah e transport me k dore 10 m, kategoria IV	m ³	38		-
2	2.a-100	Celes me dy pozicione, l-0-2 380V,20A	Cope	1		-
3	2.490/f	F.V Kasete plastike KE me 36 modular (vende)	Cope	4		-
4	An	Rele diferencoale 4P-40 / 380V	Cope	4		-
5	2.a-104	Automat termo-elektro magnetik,4P;380V;100A	Cope	4		-
6	2.490/1a	F.V Automat termo/el.manj. diferencial 2P 220V, 10A	Cope	14		-
7	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	Cope	15		-
8	2.490/1c	F.V Automat termo/el.manj. diferencial 2P 220V, 32A	Cope	5		-
9	2.a-120	Llampe sinjalizimi 220V;1.2w	Cope	24		-
10	2.487	Kuti derivacioni plastike	Cope	110		-
13	2.487/c	F.V kuti suport pllaket 2 modular Gevis	Cope	22		-
14	2.487/d	F.V kuti suport pllaket 4 modular Gevis	Cope	188		-
15	3.An57/b	F V pusete elektrike kontrolli PVC 40x40x40cm	Cope	2		-
16	2.485/d	F.V priza shuko "Gevis" universal	Cope	122		-
17	2.485/b	F.V priza bivalente 220V 10A 2P-T Gevis	Cope	70		-
18	2.485/2	Celes 10A/250V	Cope	60		-
19	2.485/2	Celes deviat 10A/250V	Cope	8		-
20	An	Priza telefoni RJ 11-TF	Cope	8		-
21	An	Priza internet RJ 45 (Data)	Cope	25		-
22	An	Swicher(shperndares sinj. Internet)	Cope	2		-
23	An	Ruter	Cope	2		-
24	4.166/5	Tubo P.V.C. fleksibel ø63	ml	80		-
25	480/5	F.V tub plastmasi Ø 31 ~ 36 mm	ml	120		-
26	480/3	F.V tub plastmasi Ø 22 ~ 26 mm	ml	550		-
27	480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	950		-
28	480/1	F.V tub plastmasi Ø 14 ~ 17 mm	ml	400		-
29	4.150/6	F.V. percjellesa Cu te izoluar me gome, per ndricim,ne izolator, sexion 10mm ²	ml	600		-

Nr	Nr. Anal	Emertimi	Njesia	Sasia	Cmimi/ Niesi	Vlera
30	4.150/4	F.V. percjellesa Cu te izoluar me gome, per ndricim,ne izolator, sexion 4mm2	ml	1,750		-
31	4.150/3	F.V. percjellesa Cu te izoluar me gome, per ndricim,ne izolator, sexion 2.5mm2	ml	2,800		-
32	4.150/2	F.V. percjellesa Cu te izoluar me gome, per ndricim,ne izolator, sexion 1.5mm2	ml	1,100		-
33	4.131/3.7	Kabell P.V.C. 4x25 mm ² , izol.gome armuar	ml	105		-
34	An	Kabell P.V.C. 3x1.5 mm ²	ml	1,850		-
35	An	Kabell internet U.T.P .4(2x0.5)	ml	350		-
36	An	Kabell telefoni 2(2x0.5)	ml	155		-
37	2.a-127	Ndricues fluoreshent 2x36w,IP40	Cope	63		-
38	An	Ndricues FLC-(1x36)w	Cope	165		-
39	2.a-125	Ndricues fluoreshent 1x60w.IP65	Cope	8		-
40	2.a-124	Ndricues fluoreshent 1x40w.IP65	Cope	10		-
41	2.a-139	Ndricues evakuimi me llampe 1x11w,IP40	Cope	16		-
42	2.a-131	Ndricues tip plafoniere, emergjence,1x18w,IP65	Cope	16		-
43	An	Zile elektrike	Cope	4		-
44	An	Shtize rrufepritese l=1m	Cope	20		-
45	An	Shkeputes rrjeti	Cope	8		-
46	4.167	F.V.Tokezime e mbrojtje atmosferike ne objekt me hekur shirit	ton	0		-
47	4.167	Tel zingato φ 10 mm	ton	0		-
48	2.485/2	F.V Çeles 1 polar 220V 10A "Gevis"	Cope	8		-
49	4.167	Elektroda tokezimi	Cope	20		-
50	An	Sistemi i kamerave me (8 kamera per jashte, kabull , pajisje qendrore, monitor 42" total)	total	1		-

SHUMA K

-

L SISTEMI I MBROJTJES KUNDER ZJARRIT

L	Materiali Instalimi, sinjalistika dhe kodi indeksimit					
1	An	F.V. Tubo çeliku pategel Ø 1½" + aksesore	kg	1,125		-
2	An	F.V.Tabele sinjalistike - Hidrant Zjarri	cope	8		-
3	An	F.V.Tabele sinjalistike - Fikse zjarri me pluhur karelato	cope	8		-
4	An	F.V.Tabele sinjalistike - Fikse zjarri me pluhur 6 kg	cope	8		-
5	An	F.V.Tabele sinjalistike - Buton alarmi	cope	8		-
6	An	F.V.Tabele sinjalistike - Ndalim i shuarjes me uje	cope	4		-
7	An	F.V.Tabele sinjalistike - Drejtim l daljes se emergjences	cope	15		-
8	2.510	F.V hidrante Ø 50 mm	cope	8		-
9	An	F. V Kasete per hidrantin me aksesore	cope	8		-
10	An	Detektor tymi	cope	55		-
11	An	Centralino per sistemin e zjarit	cope	1		-

SHUMA L

-

M PUNIME TE INSTALIMIT TE NGROHJES

1	An	Radiator alumini me 12 elemente	Cope	63		-
2	An	Kaseta per kolektor 1850	Cope	6		-
3	An	Stafa per kolektor	Cope	6		-
4	An	Kolektor 1 1/4x11 dalje	Cope	16		-
5	An	Valvula kendore termostatikr 1/2	Cope	51		-
6	An	Detentor kenor 1/2	Cope	51		-
7	An	Rekord multi-fit 16x2x1/2	Cope	280		-
8	An	Kit universal 1/2 me ganxha per radiator	Cope	51		-
9	An	Saracineske kendore per kolektore 1 1/4	Cope	8		-
10	An	Rekord l drejte filet mashkull 1 1/4x40	Cope	35		-
11	An	Niple 1/2x1/2 per kolektor	Cope	50		-
12	An	Rekord fundor per fil mashkull 1 1/4	Cope	16		-
13	An	Valvola automatike per nxjerrje ajri 1/2	Cope	16		-
14	An	Valvola sferike per shkarkim uji 1/2	Cope	16		-
15	An	Bryla 40x40	Cope	16		-
16	An	Rekord l ndermjetem	Cope	51		-
17	An	Tubo multistrade 40x3.5	ml	40		-
18	An	Tubo multistrade l izoluar 16x2	ml	3,500		-
19	An	Rozeta φ16	cope	70		-
20	An	Komande termostatike me element te ndjeshem vaji	cope	70		-
21	An	Ti 40x40x40	cope	12		-
22	2.492	Tubo xingate φ 89x4.5 mm 135 ml	kg	2,805		-
24	4.35	F.V.Tubo ventilimi me kthim buzesh, rrethore, Ll.zeze	ton	0		-
25	4.170	Montim l kaldajes 80 kw	Cope	1		-
26	An	Kaldaje	cope	1		-

SHUMA M

-

N PUNIME TE SISTEMIT TE SHESHIT

1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m ³	175		-
2	3.377	Ndertim drenazhi, mbushje me gure lumi	m ³	425		-
3	An-55	F V tub drenazhi Ø 150 mm	ml	225		-

Nr	Nr. Anal	Emertimi	Njesia	Sasia	Cmimi/ Niesi	Vlera
4	2.575	Puse kontrolli 1x1x1.5m	cope	4		-
5	An - 22/1	Pusete b/a shiu 40 x 40, h = 100 cm, me kapak gize	cope	17		-
6	3.An/1t	F V tuba te brinjzuar HDPE SN8 d=315 mm	ml	562		-
7	2.258	Nenshtrese zhavori	m ³	155		-
8	3.246	Struktura monolite betoni me çakell C 20/25	m ³	123		-
9	2.166	F V hekur betoni periodik Ø 8 (zgara te elektrosalduara 15x15 cm)	ton	12		-
10	3.616	F V bordura betoni 12x25 cm	ml	1,450		-
11	An	Zorre per sistemin e vaditjes Ø 32 mm	ml	465		-
12	An	Bilbila te fshehte per vaditje lulishte	cope	62		-
13	3.643	Mbjellje bari ne skarpat	m ²	1,250		-
14	3.An.164	F.V. Fidane Peme dekorative perimenter 20 cm	cope	25		-
15	3.An.163	F.v Fidane Lule dekorative	cope	155		-
16	An	F.V pompe 3 fazore 2 polshe	cope	2		-
17	3.An/53	F.V e shtyllave ndricimi dekorative , pme lartesi h = 7 m	cope	8		-
18	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	8		-
19	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	8		-
20	3.An/55	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	8		-
21	An	F.V te kuadrit elektrik me automat mgt 4p 32A, automat diferencial 4p 40A 5d=0,3A, 4 automatë mgt 1p 16A 16kA, 4 kontaktorë modular 4p 40A, 4 celësa seksionues 1p 16A	cope	2		-
22	An	Tub fleksibel Ø 64 mm	ml	330		-
23	An	Kabell FGOR 3x2.5mm	ml	230		-
24	An	Kabell FGOR 3x6mm	ml	130		-
25	An	F.V ndricues dekorative LED 75 wat per ambiente te jashtme	cope	10		-
26	An	Nivelim betoni me helikopter me stampe	m ²	1,150		-
27	An	F.v Stola te Thjeshte	cope	12		-
28	An	F.v Stola Trekendesh	cope	3		-
					SHUMA N	-

O PUNIME TE NDETIMIT TE PALESTRES

1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III (PALESTRA)	m ³	145		-
2	2.25a	Germim dheu themele plinta b-2 m ekskavator me goma kova 0.25 m3 shkarkim ne toke	m3	85		-
3	3.158/5a	Transport dheu me auto 5km	m ³	230		-
4	2.121/1	Brez b/a mbi themel	m ³	6		-
5	2.121/1	Brez b/a mbi mure	m ³	6		-
6	An	Plinta bazamente b/a monolite deri 20m3 C20/25	m3	52		-
7	2.119/1	Arkitrare b/a	m ³	8		-
8	2.119/1	Trare themeli b/a	m ³	32		-
9	2.119/1	Trare b/a	m ³	34		-
10	2.256/b	Mbulim çatie me panele sanduich	m ²	775		-
11	2.413	Konstruksion metalik (, mbulimi I palestres)	Ton	25		-
12	An -47	Galvanizim konstruksion metalik	kg	20		-
13	2.262/4	Shtrese betoni C 16/20	m ³	82		-
14	2.404/1	Boje hidroplastike importi cilesi e I-re	m ²	1,348		-
15	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m2	1,348		-
16	2.276	Shtrese parketi ne palester	m ²	650		-
17	An - 13	F.V Igloo per hidroizolim in e palestres	m ²	715		-
18	2.258	Shtrese zhavori	m ³	85		-
19	2.423/a	Shtrese avullizoluese gjeotekstil	m2	850		-
20	2.262/4	Shtrese betoni I varfer nen igloo C 16/20	m ³	85		-
21	2.166	F.V hekur periodik 6-10mm	ton	12		-
22	2.167	F.V hekur periodik >12 mm	ton	18		-
23	2.195	Hidroizolim me dy duar bitum dyshemeja	m ²	850		-
24	An	Mur me tulle me 6 vrima, t=25cm, h~7m, llaç perzier M25	m ³	172		-
25	2.117/1a	Kollona b/a M-250	m ³	26		-
26	2.375/a	Dritare d/alumini dyfish xham.	m ²	108		-
28	2.395/a	Dere d/alumini pa xham,me mbushje d/a.	m ²	6		-
29	3.287	Zgare hekuri e elektrosalduar Φ 6mm 200mmx200mm	ton	2		-
30	3.208	Shtrese cakulli t=10cm, makadam, perhapur ngjeshur me	m ²	605		-
31	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3 cm, me makineri	m ²	493		-
32	2.109/2	Themel betoni C12/15 per tabelat	m ³	2		-
33	An.1	F.V shtrese niveluese elastike Mapecoat TNS Grey Base Coat 3mm (ose ekuivalent)	m ²	450		-
34	An.3	Vizime me boje resina acrilica Mapecoat TNS Line d=8cm me tre ngjyra sipas seciles disipline (ose ekuivalent)	m ²	50		-
35	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	6		-
36	3.An/57/	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	6		-
37	An.7	Tub fleksibel Ø 64 mm	ml	160		-
38	An	F.V te kuadrit elektrik me automat mgt 4p 32A, automat diferencial 4p 40A 5d=0,3A, 4 automatë mgt 1p 16A 16kA, 4 kontaktorë modular 4p 40A, 4 celësa seksionues 1p 16A	cope	1		-
39	An	Tub fleksibel Ø 90 mm	ml	145		-

Nr	Nr. Anal	Emertimi	Njesia	Sasia	Cmimi/ Niesi	Vlera
40	An	Kabell FGOR 3x2.5mm	ml	90		-
41	An	Kabell FGOR 3x6mm	ml	255		-
42	3.An	F.V prozhektore asimetrik me llampe joduro metalike me stafa mbeshtetese. Fluksi I nje llampe 30.5klm, fugia 400wa	cope	6		-
43	An	F. V porta minifutbolli	cope	2		-
44	An	F. V impiant basketbolli (2kosha,2tabele, struktura metalike, mbajtese)	cope	2		-
45	An	F.V. impiant volejbolli (shtylla 2.8m + rrije+arganele+tub inkastrimi 8cm)	cope	2		-
					SHUMA O	-
P PUNIME TE MURIT RRETHUES						
1	3.137	Germim dheu me ekskavator, kategoria III	m ³	180		-
2	3.183/a	Shtrese zhavor lumi t=10cm	m ²	280		-
3	3.244	Struktura monolite betoni C20/25	m ³	120		-
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm (per murin rrethues)	ton	10		-
5	2.182	Konstruksione metalike te thjeshta (muret rrethuese Kangjellat)	ton	5		-
6	2.401	Boje vaji siperfaqe metalike (lyerja e konstruksioneve metalike - Kangjellat)	m ²	280		-
7	2.340	Suva xokoli me granil e çimento te bardhe (Suvatimi_i-murit-	m ²	280		-
8	2.404/1	Boje hidroplastike importi cilesi e l-re	m ²	280		-
					SHUMA P	-
R PUNIME TE URES MBI KANAL						
1	2.25/a	Germim themele e plinta b~2m, ekskavator me goma, kova 0.25m ³ shkarkim toke	m ³	386		-
2	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m ³	112		-
3	2.37/5a	Transport dheu me auto deri 5.0 km	m ³	498		-
4	3.183/a	Shtrese zhavor lumi t=10cm	m ²	145		-
5	2.262/4	Shtrese betoni C 16/20	m ³	18		-
6	3.245	Struktura monolite betoni C 25/30	m ³	225		-
7	2.166	F.V hekur periodik 6-10mm	ton	5		-
8	2.167	F.V hekur periodik >12 mm	ton	18		-
9	3.636	Parmake ure, metalik l gatshem	ton	2		-
					SHUMA R	-
					SHUMA A-H	-
					FONDI REZERVE 5%	-
					TOTALI	-