

PREVENTIV

Objekti : SISTEMIM ASFALTIM RRUGA" ZEQIR MEMA"

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
		I.PUNIME NE RRUGE L=1100 m				
1	3.89/a + 3.158/a	Germim dheu me ekskavator 0.25 m ³ , toke zak, kategoria III, me shk ne mjet + Transport dheu me auto deri 5 km	m ³	440	-	-
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	850	-	-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	3,608	-	-
5	3.212/b	Shtrese stabilizanti 10cm per bankine	m ²	802	-	-
6	3.228/1	Shtrese binderi me zall lavatrice,4cm,me makineri	m2	354	-	-
7	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	3,608	-	-
8	3.240	Struktura monolite betoni C 12/15 (kunete+trotuar+portale)	m3	14.7	-	-
9	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	12	-	-
		SHUMA				-
		TVSH 20%				-
		TOTAL				-

PREVENTIVOI
"Novatech Studio"shpk
Ing.Emil Nova