



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**  
**PREVENTIV**

**OBJEKTI : NDERTIM "Rruget Ylberi + Rrugicat + Usaid +Hamburg "Valias**

NR	Analize	EMERTIMI I PUNIMEVE	Njesia	Sasia		
<b>1</b>		<b>PUNIME TE NDRYSHME (Germime,Prishje, Çmontime, Mbushje, etj.)</b>				
1	An	Spostim shtylla ekzistuese(perfshi linjen)	copë	5		
2	An-49	Prishje struktura prej betoni,mure,bodura,kuneta etj,	m3	12		
3	3.139	Germim dheu me ekskavator goma 0.35~0.40m <sup>3</sup> , ne themele, toke zak, kat III, me shkarkim ne toke	m3	4,313		
4	3.352	Mbushje me gur kave	m3	256		
5	An.164/1 b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri,per nivelete	m3	606		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m3	4,313		
		<b>SHUMA 1</b>				
<b>2</b>		<b>PUNIME SHITESASH PER TRUPIN E RRUGES</b>				
1	An.164/1 b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri t=30cm	m <sup>3</sup>	2,300		
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	3,402		
3	3.212/c	Shtrese stabilizant t=15cm	m <sup>2</sup>	2,552		
4	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m <sup>2</sup>	2,552		
5	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m <sup>2</sup>	2,552		
		<b>SHUMA 2</b>				
<b>3. PUNIME TROTUARI</b>						
1	3.620	Trotuar, me 6 cm beton me kuarc , me pllaka betoni me kuarc te presuara 30x30 dhe 15x15 m per trotuare t=6 cm	m2	1,701		
2	An-8	Shtrese çakelli t=20cm per trotuar	m3	340		
3	3.617/2	F V bordura betoni 15x25 cm	m	1,134		
4	3.244	Struktura monolite betoni C 20/25,kuneta	m3	28.4		
		<b>SHUMA 3</b>				
<b>4. PUNIME K.U.B</b>						
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m3	284		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	284		
3	An-8	Mbushje me cakell	m3	142		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	567		
6	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	16		
		<b>SHUMA 4</b>				
<b>5. PUNIME K.U.Z</b>						
1	3.103/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~ 2m kategoria IV, me shk ne toke	m3	1,408		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,408		
3	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	345		
4	An-8	Mbushje me cakell	m3	1,294		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	200		
6	2.575	Puset kontrolli 1x1x1.5m	cope	6		
7	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	10		
8	2.584	Puse kontrolli 2x2x1,5m	cope	6		
		<b>SHUMA 5</b>				
<b>6. PUNIME VEPRA ARTI</b>						

1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m <sup>3</sup> , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m3	113			
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	113			
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m3	98			
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	1.12			
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1.32			
<b>SHUMA 6</b>							
<b>7 PUNIME ELEKTRIKE</b>							
1	An	F V shtylla dekorative dy degeshe per ndricim, H=8m,	cope	15			
2	An	F V krah dy degesh per shtulla metalike per ndricim	cope	15			
3	An	F.V Ndricules LED 94W per rrugen	cope	15			
4	An	F V kuader komandimi komplet me santeri+fotoelement	cope	1			
5	An	F.V. morseteri shtylle 3P=sig.16A+kapak	cope	15			
6	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	15			
7	An	F.V. kabell FG7OR 0.6I 1KV 3X10 mm2	ml	580			
8	132/2.2	F.V. Kabell elektrik FROR 2x2.5 per shtylla 7ml	ml	112			
9	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	16			
10	An	F.V. tub fleksibel me D=80mm per ndricim	ml	567			
12	An	F.V. tub fleksibel me D=80mm per linje rezerve	ml	567			
13	An-57	FV tub metalik D=219mm	ml	26			
14	3.24	Fiksimit shtylle metalike beton C - 12/15 0.3m3/shtylle	m3	2.4			
15	3.An/57b	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	16			
<b>SHUMA 7</b>							
<b>8</b>	<b>PUNIME PER SINJALISTIKE DHE SISTEMIM URBAN</b>						
1	An152	Vizime me boje bikomponente me gjeresi 15 cm	ml	1,725			
2	An151	Boje bikomponente (paste) per kalim kembesoresh me ngjyre te kuqe dhe shirita te bardhe sipas detajit	m2	68			
3	An155	F V tabela rrugore te ndryshme D=90cm	cope	12			
4	An157	F V tabela rrugore treguese 60x20cm	cope	3			
<b>SHUMA 8</b>							
<b>SHUMA 1-8 e Rruges Hamburg</b>							
<b>OBJEKTI : Ndertim RRUGET YLBERI + RRUGICAT + USAID VALIAS L = 704 m B= 5.5 m Basft 4.5m,</b>							
1	3.139	Germim Dheu e shtresash me Eskavator Kt III	m <sup>3</sup>	704.0			
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	704.0			
3	An.	Spostim Shtyllash Elektrike ( komplet me Kabllo )	cope	11			
<b>SHUMA I</b>							
<b>II</b>	<b>PUNIME NE RRUGE</b>						
1	3. an 8	Mbushje me çakell shkembor trest =10 cm	m <sup>3</sup>	381.623			
2	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m <sup>2</sup>	3872			
3	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	3168			
4	3.222/2	Shtrese binderi 1x6 cm	m <sup>2</sup>	3168			
5	3.226/1	Shtrese asfaltbetoni 1x4cm	m <sup>2</sup>	3168			
7	An.	Ngritje pusete+kapak gize	cope	8			
<b>SHUMA II</b>							
<b>SHUMA 1-8 e RRUGES USAID + YLBERI</b>							
<b>SHUMA</b>			20%				
<b>TOTALI ME TVSH</b>							

**Preventivues:**

Ing. Hajredin MURGU

Drejtori P.I-se

Ing. Flora MUÇA

**Drejtori i Pergjithshem**

Z.Elvis Gjika

**MIRATOI  
Rakip SULI**

**K R Y E T A R**