

PREVENTIV

Objekti: Rikonstruksioni i palestrave dhe terreneve sportive te shkolles se bashkuar "Luigj Gurakuqi-Petagogjika"

Adresa: Lagjia Luigj Gurakuqi, Njesia Administrative nr.1, Bashkia Elbasan

Investitori : Bashkia ELBASAN

Nr	Nr.anal	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
I		PUNIME PER PALESTREN E VOGEL				
A		<i>Punime prishje (Objekti egzistues)</i>				
1	An.2.292	Prishje tavane lende e sharruar	m2	151		
2	An.2.300	Prishje suvatime muresh	m2	856.5		
3	An2,331	Prishje suvatime mure jashte H~8m(fasada)	m2	317.2		
4	An.2.276	Prishje shtrese parketi	m2	156.2		
5	An.2.504	Heqje WC allaturka importi	cope	4		
6	An.2.495	Heqje lavaman importi	cope	1		
7	An.2.267/a	Prishje dysHEMEJE me pllaka qeramike	m2	28.9		
8	2.426/3	Prishje shtrese e varferuar nen pllaka t~5-10 cm	m3	1.445		
9	2.426/3	Prishje shtrese betoni (WC e vjeter trotuari (52.7x1mx0.12 m)	m3	6.324		
10	2.426	Prishje mure tulle (1 x 2.1 x0.25 hapje dere)	m3	0.525		
11	An2,370	Heqje dritare druri (12 x1.6mx0.5)	m2	9.6		
12	An2,383	Heqje dyer druri (6 x 1 x2.05)	m2	12.3		
13	An2.413	Heqje zgara dekorativa hekuri me figuracion mesatare cope 13 x 17 kg/cop	ton	0.221		
14	An2.405	Prishje davancale dritare (Pragje dritare me pllake granili te armuar me bojra) cope 12	m2	7.92		
15	An2.326	Prishje pllake majolike	m2	73.44		
16	2.426/3	Prishje shtresa betoni (Prishje trotuari I palestres x 1.2 m x 42 m x 0.1 m)	m3	5.04		
17	An2.206	Heqje Kasete shkarkimi me llamarine xingat	cope	6		
18	An2.209	Heqje ullukesh vertikale	ml	31		
19	An2.212	Heqje ullukesh horizontale	ml	53		
20	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	28.2252		
		Shuma - A	leke			
		Punime per rikonstruksionin				

B		PUNIME ÇATIE				
1	2.219	Riparim çati vendi e zakonshme me HD~8m, tjegulla marseljeze ne masen 30%	m2	234		
2	2,196	Shtrese H/Izoluese nen tjegulla (HIDROIZOLIM ÇATIE)	m2	234		
3	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m2	234		
4	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	31		
5	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	53		
6	2.206	Kasete shkarkimi me llamarine xingat	cope	6		
		SHUMA B				
C		PUNIME SUVATIMI DHE VESHJE				
1	2.297/a	Tavan me kartonxhes	m2	151		
2	2.33	Patinim tavani allçi (stuko)	m2	151		
3	2.64/2	Mur me tulle plotë ne lartesi deri 3m me llaç perzier M 25 (1.9 x 2+2.7) x 2.2 m x 0.125 m	m3	1.315		
4	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	856		
5	2.295	Suvatim i strehes se catise me rrjete teli + suva (0,45x 52.7 m)	m2	23.715		
6	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suvatim me grafiato.	m2	317		
7	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama (dysHEMEJE te palestres) muri anesor 198 ml x 1m + dysHEME 240 m2	m2	438		
8	2.276	Shtrese parketi + plintuesi me parket 10 cm	m2	157		
9	2.328	Patinim muri allçi (stuko) 3 m lartesi	m2	155.7		
		SHUMA C				
D		PUNIME LYERJE				
1	2.404/1	Boje hidroplastike importi cilesi e l-re (lyerje te palestres se brendeshme)	m2	857		
2	2.404/1	Boje hidroplastike importi cilesi e l-re (lyerje fasade sipas projektit)	m2	341		
3	2.401	Lyerje boje vaji	m2	68		
4	2.400	Boje vaji siperfaqe druri (vijezimet per fushat)	m2	25		
		SHUMA D				
E		PUNIME DYER DRITARE				

1	2.268/a	F.V. Pragje dyersh me permasat 30 cm x 1.05 me pllake mermeri me trashesi 2 cm cope 6	m2	1.89		
2	2.268/a	Davancale mermeri dritare (1.6 x 0,45 x 12 cope x trashesi 2 cm)	m2	8.64		
3	2,375/1	F V dritare d/alumini plastike me dopio xham 1.6 m gjeresi x 1 m x 12 cop	m2	19		
4	2.386/1	F V dyer te brendeshme metalike te blinduara. Dere e blinduara importi .(Dera e jashtme)	m2	4.4		
5	2.395/1	F V dyer d/alumini plastike me xham me rrjete teli	m2	4.2		
6	2.383/1	F V dyer te brendeshme druri importi cilesi e l-re. (4 cope x 1m x 2.1 m)	m2	8.4		
7	2.An	F.V porte metalike dekorative rreshqitese	m2	9.9		
8	2.413	F.V zgara dekorativa hekuri me figuracion mesatare	kg	1500		
		SHUMA E				
F	PUNIME SHITRESASH + VESHJE					
1	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	28.9		
2	2.324/b	Plintuse grez importi h = 10 cm	ml	41		
3	2.326	Veshje me pllake majolike (me lartesi 2.1 m)	m2	25.4		
4	2.258/2	Shtrese zhavori (L 42 m x B 1.2 m x t 0.15 m	m3	7.56		
5	2.262/4	Shtrese betoni C 16/20 (L = 42 m x B =1.2 m x t =0.1 m)	m3	5.04		
6	2.266	Shtrese me pllaka granili te zakonshme, 30x30cm	m2	50.4		
7	2.291	Bordura betoni trotuari 12x25 cm	ml	42		
		SHUMA F				
G	PUNIME HIDRO-SANITARE					
1	2.504	F.V.WC allaturka	cope	2		
2	2.495	F.V.lavaman me kollone me mishelator	cope	3		
3	2.520	Tub kanalizimi pvc Ø 110 mm	ml	9		
4	2,491/e	F.V.tubo plastike pvc 50 mm (shkarkim lavamanesh)	ml	24		
5	2.491/1c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 3.6 mm, PN 20	ml	56		
6	2.491/a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.0 mm, PN 10	ml	23		
7	2.An10	F.V. sarcineska 3/4'	cope	4		

8	3.116/b	Germim dheu me ekskavator 2.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet (GERMIM DHEU KANAL PER UJRAT E ZEZA L = 15 m B=0.5m H=1.2 m)	m3	9		
9	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar	ml	15		
10	An - 20	Pusete shkarkimi 80 x 80, h = 150 cm	cope	1		
11	An-9	Mbushje me zhavorr pas mureve	m3	6		
12	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	9		
13	2.492	F.V tub xingato dhe rakorderi Ø -2 "	kg	25		
14	An	F.V.Tubo xingato 1/2" + rakorderi	ml	6		
15	An	F.V.Tubo xingato 1 1/4" + rakorderi	ml	6		
16	2.515	F.V pilete dysHEMEJE Ø 50	cope	3		
17	2.516	Tuba plastmasi dhe rakorderi	ton	0.02		
		SHUMA G	LEKE			
H		PUNIME DRENAZHI				
1	3.116/b	Germim dheu me ekskavator 2.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet (GERMIM DHEU KANAL PER UJRAT E ZEZA L = 52 m B=0.5m H=1.2 m)	m3	31		
2	2.523/1	F V tub drenazhi Ø 200 mm	ml	52.0		
3	3.378	Ndertim drenazhi,mbushje me zhavorr prodhuar mak	m3	21		
4	An - 22/1	Pusete b/a shiu 40 x 40, h = 120 cm, me kapak gize	cope	4		
		SHUMA H				
M		PUNIME MNZ				
1	2.492	F.V tub xingato dhe rakorderi Ø -2 "	kg	5		
2	An	F.V.Tubo xingato 1/2" + rakorderi	ml	12		
3	An	F.V.Tubo xingato 1 1/4" + rakorderi	ml	12		
4	2.494/3	F.V saracineska bronzi Ø 1 1/4 " = 32 mm	cope	1		
5	An	Koka sprinkleri G5 STANDART RESPONSE	cope	1		
6	2.512	F.V hidrante Ø 100 mm i jashtem	cope	1		
7	2.510	F.V kasete+ hidrante Ø 50 mm(me markuq najloni 25m)	cope	1		
8	An	Shuars te thate kategoria A,B, C, D, E 6 kg	cope	2		
9	2.An - 11	F V rezervuari zingato 5000 litra	cope	1		
10	An - 104	Sensor termik tymi temperature	copë	1		
11	2.An - 17	F V pompe me pulmon 24 litra	cope	1		

		Shuma - M	leke			
		SHUMA A - M	leke			
II		PUNIME PER PALESTREN E MADHE				
A		<i>Punime prishje (Objekti egzistues)</i>				
1	2.426	Prishje mure tulle (1 x 2.1 x0.25 hapje dere)	m3	13		
2	2.426/4	Prishje soleta b/a	m3	7.5		
3	2.426/3	Prishje shtrese e betoni t = 10 cm	m3	5		
4	An.2.300	Prishje suvatime muresh + kollona + tavan	m2	741		
5	An2,331	Prishje suvatime mure jashte H~8m(fasada)	m2	382		
6	An.2.276	Prishje shtrese parketi	m2	300		
7	An.2.504	Heqje WC allaturka importi	cope	2		
8	An.2.495	Heqje lavaman importi	cope	2		
11	An2,370	Heqje dritare druri 24 dritare	m2	134		
12	An2,383	Heqje dyer druri 4 dyer	m2	15		
13	An2.413	Heqje zgara dekorativa hekuri me figuracion mesatare cope 23 x 17 kg/cop	ton	0.391		
14	An2.405	Prishje davancale dritare (Pragje dritare me pllake granili te armuar me bojra) cope 24	m2	12		
15	2.426/3	Prishje shtresa betoni (Prishje trotuari i palestres x 1.0 m x 27 m x 0.1 m)	m3	2.7		
16	An2.209	Heqje ullukesh vertikale	ml	21		
17	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	68.96		
		Shuma - A	leke			
		<i>Punime per rikonstruksionin e palestres</i>				
B		PUNIME TARACE				
1	2.200	Shtrese lluster cemento 1:2 t = 20 mm	m2	345		
2	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m2	345		
3	2.200	Shtrese lluster cemento 1:2 t = 20 mm	m2	345		
4	2,197	Hidroizolim me 2 duar emulsion bitumi dhe 2 k katrama (HIDROIZOLIM TARACE)	m2	345		
5	2.200	Shtrese lluster cemento 1:2 t = 20 mm	m2	345		
6	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	51.2		
7	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	28		

8	2.206	Kasete shkarkimi me llamarine xingat	cope	8		
		SHUMA B				
C		PUNIME SUVATIMI DHE VESHJE				
1	2.300	Suva solete ~ 4 m me drejtues, me krah	m2	360		
2	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	412		
3	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suvatim me grafiato.	m2	215		
4	2,196	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama (dysHEMEJE te palestres) muri anesor 68 ml x 1m + dysHEME 296 m2	m2	364		
5	2.276	Shtrese parketi + plintuesi me parket 10 cm	m2	303		
6	2.328	Patinim muri allçi (stuko) 3 m lartesi	m2	204		
		SHUMA C				
D		PUNIME LYERJE				
1	2.404/1	Boje hidroplastike importi cilesi e l-re (lyerje te palestres se brendeshme)	m2	772		
2	2.404/1	Boje hidroplastike importi cilesi e l-re (lyerje fasade sipas projektit)	m2	15		
3	2.401	Lyerje boje vaji	m2	67		
4	2.400	Boje vaji siperfaqe druri (vijezimet per fushat)	m2	25		
		shuma D				
E		PUNIME DYER DRITARE				
1	2.268/a	F.V. Pragje dyersh me permasat 30 cm x 3.5 me pllake mermeri me trashesi 2 cm cope 1	m2	1.05		
2	2.268/a	Davancale mermeri dritare (21cope x 0,45 x 3.5m x trashesi 2 cm)	m2	33.075		
3	2,375/1	F V dritare d/alumini plastike me dopio xham 3.5 m gjeresi x 1.8 m x 21 cop	m2	132		
4	2.386/1	F V dyer te brendeshme metalike te blinduara. Dere e blinduara importi .(Dera e jashtme)	m2	9.5		
7	2.An	F.V porte metalike dekorative rreshqitese	m2	9.9		
8	2.413	F.V zgara dekorativa hekuri me figuracion mesatare	kg	392		
		SHUMA E				
F		PUNIME SHTRESASH + VESHJE				
1	2.258/2	Shtrese zhavori (L 24 m x B 1.0 m x t 0.15 m	m3	4.05		

2	2.262/4	Shtrese betoni C 16/20 (L = 42 m x B =1.2 m x t =0.1 m)	m3	2.7		
3	2.266	Shtrese me pllaka granili te zakonshme, 30x30cm	m2	27		
4	2.291	Bordura betoni trotuari 12x25 cm	ml	27		
SHUMA F						
H		<i>PUNIME DRENAZHI 45 ml</i>				
1	3.116/b	Germim dheu me ekskavator 2.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet (GERMIM DHEU KANAL PER UJRAT DRENAZHIT L = 45 m B=0.5m H=1.2 m)	m3	27		
2	2.523/1	F V tub drenazhi Ø 200 mm	ml	45.0		
3	3.378	Ndertim drenazhi, mbushje me zhavor prodhuar mak	m3	18		
4	An - 22/1	Pusete b/a shiu 40 x 40, h = 120 cm, me kapak gize	cope	4		
SHUMA H						
I		<i>Punime per ndertimin e ambjenteve ndihmese te palestres</i>				
1	2.30	Germim dheu themele e plinta me b>2m, ekskavator me zinxhir 0.5m ³ , shkarkimi ne auto (heqja e dherave mbi nivelin e xoglatures ne krahun lindor me siperfaqe 166 m ² x 0.25 m thellesi)	m3	42		
2	2.37/5a	Trasport dherash te dale nga germimi deri 1 km	m3	42		
3	2.258	Nenshtrese zhavori (t=10cm) nen pllake 166 m ²	m3	16.6		
4	2,262	Shtrese betoni C 6/10 s=166 m ² x t= 5 cm per bazament te montimit te armatures)	m3	8.3		
5	2.114/1	Plinta e bazamente b/a monolite deri 20 m ³ C - 16/20 S= 166 m ² x 0.4 m	m3	66.4		
6	2,166	F.V. hekur betoni i periodik nga Ø 6 deri Ø 10 mm	kg	1830		
7	2,167	F.V. hekur betoni i periodik mbi Ø 10 mm	kg	3425		
8	2,117/1a	Kollona b/a monolite C 16/20 h ~ 8m =16 cope x 0.4 m x 0.25m x 3.2	m3	5.12		
9	2.121/1	Brez b/a C 16 / 20 3.06 m	m3	2.8		
10	2,158/1/an	Soleta te plota b/a C20/25, t = 15 cm	m3	23.1		
11	2.64/2	Mur me tulle ne lartesi deri 3m me llaç perzier M 25 =56.4 m x 0.25 m x 2.9m + 42 m x 0.25m x 2.9m	m3	71		
12	2.119/1a	Trare e arkitrare b/a C20/25 h ~ 4m	m3	3.2		

13	2,197	Hidroizolim me emulsion bitumi dhe 2 k katrama (dyshemeje ambjenteve ndihmese te palestres) dysHEME 154 m2 + 16 m x 1 m	m2	170		
14	2.267/b	Shtrese me pllaka grez importi 40 cm x 40 cm cil. I (ambjentet para palestres 154 m2)	m2	154.0		
15	2.324/b	Plintuse grez h = 10 cm	ml	56.4		
16	2.326	Veshje me pllake majolike (me lartesi 2.1 m)	m2	18		
17	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	454.72		
18	2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suvatim me grafiato.	m2	158		
19	2.404/1	Boje hidroplastike importi cilesi e l-re (lyerje te ambjenteve ndihmese te palestres se madhe)	m2	599		
20	2.297/a	Tavan me kartonxhes	m2	145		
21	2.268/a	F.V. Pragje dyersh me permasat 30 cm x 1.05 me pllake mermeri me trashesi 2 cm cope 10	m2	3.15		
22	2.268/a	Davancale mermeri dritare (1.6 x 0,30 x 8 cope x trashesi 2 cm)	m2	3.84		
23	2,375/1	F V dritare d/alumini plastike me dopio xham 1.6 m gjeresi x 1.5 m x 8 cop	m2	19		
24	2.386/1	F V dyer te brendeshme metalike te blinduara. Dere e blinduara importi .(Dera e jashtme)	m2	4.4		
25	2.395/1	F V dyer d/alumini plastike me xham me rrjete teli (3 cope x 1 m x 2.1m)	m2	6.3		
26	2.383/1	F V dyer te brendeshme druri importi cilesi e l-re. (5 cope x 1m x 2.1 m)	m2	10.5		
27	2.An	F.V porte metalike dekorative rreshqitese	m2	4.4		
28	2.413	F.V zgara dekorativa hekuri me figuracion mesatare	kg	184		
29	2.504	F.V.WC allaturka	cope	3		
30	2.495	F.V.lavaman me kollone me mishelator	cope	9		
31	2.506	F.V bide importi porcelan	cope	3		
32	2.520	Tub kanalizimi pvc Ø 110 mm	ml	9		
33	2,491/e	F.V.tubo plastike pvc 50 mm (shkarkim lavamanesh)	ml	24		
34	2.491/1c	F.V Tuba e rakorderi ujesjellesi PE	ml	65		

		d=32mm, t = 3.6 mm, PN 20				
35	2.491/a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.0 mm, PN 10	ml	35		
36	2.An10	F.V. sarcineska 3/4'	cope	3		
37	3.116/b	Germim dheu me ekskavator 2.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet (GERMIM DHEU KANAL PER UJRAT E ZEZA L = 7 m B=0.5m H=1.2 m)	m3	4		
38	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar	ml	7		
39	An - 20	Pusete shkarkimi 80 x 80, h = 150 cm	cope	2		
40	An-9	Mbushje me zhavorr	m3	6		
41	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	9		
42	2.492	F.V tub xingato dhe rakorderi Ø -2 "	kg	25		
43	An	F.V.Tubo xingato 1/2" + rakorderi	ml	6		
44	An	F.V.Tubo xingato 1 1/4" + rakorderi	ml	6		
45	2.515	F.V pilete dysHEMEJE Ø 50	cope	3		
46	2.516	Tuba plastmasi dhe rakorderi	ton	0.02		
85	2.481/1	F.V Percjeles interneti FTP,Cat 6	ml	220		
86	2.492	F.V tub xingato dhe rakorderi Ø -2 "	kg	5		
87	An	F.V.Tubo xingato 1/2" + rakorderi	ml	6		
88	An	F.V.Tubo xingato 1 1/4" + rakorderi	ml	12		
89	2.494/3	F.V saracineska bronzi Ø 1 1/4 " = 32 mm	cope	1		
90	2.512	F.V hidrante Ø 100 mm i jashtem	cope	1		
91	2.510	F.V kasete+ hidrante Ø 50 mm(me markuq najloni 25m)	cope	1		
92	An	Shuars te thate kategoria A,B, C, D, E 6 kg	cope	2		
93	An - 14	F V rezervuari zingato 500 litra	cope	1		
94	An - 104	Sensor termik tymi temperature	copë	1		
95	2.An - 17	F V pompe me pulmon 24 litra	cope	1		
		SHUMA I	LEKE			
		SHUMA A- I	LEKE			
III		PUNIME PER RESTAURIMIN E FUSHAVE				
		I- Punime ndertimi (Fusha e mini futbollit)				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	104		
2	3.198	Cilindrim kasonete me rul	m2	521		

3	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	521		
4	3.212/a	Shtrese stabilizanti t=5cm	m2	521		
5	3.226/2	Shtrese asfaltobetoni me granil guri kave, 5cm, me makineri	m2	521		
6	2.261	Shtrese rere t= 5 cm	m3	26		
7	An	F.V. tapet bari per fushe minifutbolli + shtresa e gomes	m2	521		
8	An.3.837	Rrethimi i fushes minifutbollit me rrjete teli te plastifikuar jeshile (H=3m)	m2	276.0		
9	An	Rrethimi i fushes minifutbollit me rrjete nailoni (H=3m)	m2	276		
10	2.182	Konstruksione metalike te thjeshta	ton	2.6		
11	2.An	Porte metalike dekorative (1.5x2.5m)hyrja ne fushen e minifutbollit	m2	3.8		
12	2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20	m3	1.4		
13	2.116/1	Trare themeli monolit b/a C - 16/20 (trau lidhes)	m3	4		
14	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.4		
15	3.183/a	Shtrese zhavor lumi t=10cm nen traun lidhes dhe nen plinta	m2	28.0		
16	3.240	Shtrese betoni C 12/15 t=10 cm nen traun lidhes dhe nen plita	m3	2.8		
17	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	104		
		Shuma - I	leke			
		II- Punime ndertimi (Fusha e basketbollit 32.6 m x 19.6 m = 640 m2)				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	128		
2	3.198	Cilindrim kasonete me rul	m2	640		
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	640		
4	3.205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri (me zhavor sipas te dhenave ne specifikime)	m2	640		
5	2.262/4	Shtrese beton/arme C 16/20 me trashesi 10 cm	m3	64		
6	2.166	F.V. Hekur betoni periodik Ø6 - 10 mm (10 ml/m2 - 0.616 kg/m2 x 640 m2)	kg	3,942		
7	An - 47	F.V. shtrese niveluese gome 4 mm	m2	640		

8	An - 48	F.V. tapaete rezine sintetike me ngjyra per terrene sportive (Mapecoat TNS Finish)	m2	640		
9	An - 49	Vizatime me boje resina akrelica Mapecoat TNS Line) D= 8 cm me ngjyra sipas projektit	m2	640		
10	3.183/a	Shtrese zhavor lumi t=10cm nen traun lidhes dhe nen plinta	m2	32.0		
11	3.240	Shtrese betoni C 12/15 t=10 cm nen traun lidhes dhe nen plita	m3	3.2		
12	An.3.837	Rrethimi i fushes se basketbollit me rrjete teli te plastifikuar jeshile (H=3m)	m2	294.0		
13	An	Rrethimi i fushes minifutbollit me rrjete nailoni (H=3m)	m2	294		
14	2.182	Konstruksione metalike te thjeshta	ton	2.8		
15	2.An	Porte metalike dekorative (1.5x2.5m)hyrja ne fushen e minifutbollit	m2	3.8		
16	2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20	m3	1.6		
17	2.116/1	Trare themeli monolit b/a C - 16/20 (trau lidhes)	m3	4.8		
18	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.5		
19	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	128		
		Shuma - II	leke			
1		III- Punime ndertimi (Fusha e gjimnastikes)				
2	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	60		
3	3.198	Cilindrim kasonete me rul	m2	300		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	300		
5	3.An.164/1a	Mbushje me dhe, perhapur e ngjeshur me makineri (dhe i ngjeshur t=10 cm)	m3	30		
6	3.617/1	F V bordura betoni 15x30 cm	m	72		
7	3.183/a	Shtrese zhavor lumi t=10cm nen bordura	m2	11.0		
8	3.240	Shtrese betoni C 12/15 t=10 cm nen bordura	m3	1.1		
9	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	60		
		Shuma - III	leke			
		IV- Veglat gjimnastikore				
1	3.183/a	Shtrese zhavor lumi t=10cm nen nen	m2	6.0		

		plinta			
2	3.240	Shtrese betoni C 12/15 t=10 cm nen plita	m3	0.6	
3	2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20	m3	5.0	
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm (ganxhat)	kg	27.0	
5	2.182	Konstruksione metalike te thjeshta (veglat gjimnastikore +portat e minifutbollit + koshat e basket bollit)	ton	1.3	
6	an	F.V tabela basketbolli (komplet)	cope	2.0	
7	2.421	Pergatitje e vendosje lende e sharruar	m3	0.7	
8	2.400	Boje vaji siperfaqe druri	m2	2	
9	An	Rrethimi i fushes minifutbollit me rrjete nailoni (H=4m)	m2	12	
10	2.401	Boje vaji siperfaqe metalik	m2	33	
		Shuma - IV	leke		
		V- Ndërtimi I stolave 4 copë			
1	2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	1	
2	2.116/1	Trare themeli monolit b/a C - 16/20	m3	0.7	
3	2.122/1a	Soleta te plota b/a C 20/25 t = 10 cm, h ~ 4m	m3	1	
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.24	
5	2.282	Shtrese derrasa FM 4.0cm	m2	4	
6	2.4	Boje vaji siperfaqe druri	m2	85	
		Shuma - V	leke		
		VI- Punime te ndryshme			
1	3.An143	Boje bikomponente (paste)	m2	43	
2	3.An128	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Bikomponente (paste)	ml	201.0	
3	An164	F.V. Fidane Peme dekorative	cope	14	
4	3.617/1	F V bordura betoni 15x30 cm	m	148	
5	3.183/a	Shtrese zhavor lumi t=10cm nen bordura	m2	22.0	
6	3.240	Shtrese betoni C 12/15 t=10 cm nen bordura	m3	2.2	
7	3.89/b	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	86	
8	3.198	Cilindrim kasonete me rul	m2	710	
9	3.183/a	Shtrese zhavor lumi t=10cm nen trotuar	m2	710.0	
10	3.620	Trotuar, me 6 cm beton, me pllaka	m2	710	
11	3.643	Mbjellje bari	m2	370	
		Shuma - VI	leke		

		SHUMA PER PUNIMET TE FUSHAT	LEKE			
		INSTALIME DHE PAJISJE ELEKTRIKE				
1	An1	F.V Rigit 32	ml	350		
2	An2	Automat 3F+N 25A	cope	6		
3	An3	Automat 3F+N 50A	cope	4		
4	An5	Automat 3F+N 16A	cope	2		
5	An6	Diferencial 0.03mA 3F+N 25A	cope	1		
6	2.490/1a	Automat Mag-Termik 10A 2P-220V	cope	10		
7	2.490/1b	Automat Mag-Termik 16A 2P-220V	cope	16		
8	2. a-106	Automat magneto-termik 380V,63A, 4P,Id=0.03A	cope	2		
9	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	9		
10	2.485/d	Priza 2P+T 16-25A/250V shuko universale	cope	26		
11	2.485/b	Priza 2P+T 10A/250V	cope	17		
12	2.485/5	F.v Çeles 10A/250V me dy pulla (Deviat)	cope	6		
13	2.485/2	F.v Çeles 10A/250V me nje pulla(te thjesht)	cope	13		
14	An12	Sensore Levizje	cope	5		
15	2. a-139	Ndricules evakuimi me llampe 1x11w,IP40	cope	7		
16	2.487	Kuti Shperndarese jashte murit dim. 100x100 mm IP40 (per ndricues)	cope	32		
17	2.487	Kuti derivacioni PT-3	cope	16		
18	An13	Ndricules te varur Led 100 wat(kompletuar me zinxhire kit)	cope	15		
19	An48	Ndricules Led 100 wat Led (projektore)		28		
20	An14	Ndricules Led 60x60 36W inkaso	cope	16		
21	An15	Ndricules led 18-20 wat rrethore(D150-220 mm2)	cope	8		
22	2.481/2	Percjelles CU-1x2.5 mm2	ml	1300		
23	2.481/1	Percjelles CU-1x1.5 mm2	ml	800		
24	2. a-115	Kontator magnetik,220V,25A	cope	10		
25	An17	Kabell 3x1.5mm2	ml	200		
26	An18	Percielles tokezimi 1*10mm2	ml	30		
27	2.a-97	Percjelles tokezimi bakri , Cu, S=50mm2 i zhveshur	ml	80		
28	2.a-73	Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	cope	20		
29	An49	Kuti 3M /4M	cope	24		
30	480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	1000		
31	480/3	F.V tub plastmasi Ø 22 ~ 26 mm	ml	300		
32	An19	Kabell 5x10 funizimi palestra e vogel	ml	100		

33	An20	Kabell 5x16	ml	20		
34	An50	Kabell 5x4	ml	400		
35	An21	kabell 5x25	ml	100		
36	An22	Panelet elektrike sipas skemes ne projekte	cope	3		
37	An51	Tube korrugato 95mm	ml	200		
38	An52	Tube korrugato 63mm	ml	400		
39	An53	Ndricues per fushat jashte 250 wat led IP67	cope	24		
40	An	Shtylla ndricimi me aksesore	cope	8		
41	An54	Kabell 3x2.5	ml	100		
42	2. a-104	Automat termo-elektro magnetik,4P;380V;100A	cope	1		
43	2. a-105	Automat termo-elektro magnetik,4P;380V;40A	cope	2		
		Shuma 1	Leke			
		Instalimi rjeti data				
44	An23	Prize Telefoni/Data RJ45 Cat 6 FTP	cope	10		
45	An24	Kabell Fiber Optike me 6 fibra multi mode	ml	200		
46	An25	Kabell Telefoni/Data FTP Cat 6	ml	500		
47	An27	swich	cope	1		
48	An28	Kabinet Stand Alone 40U, 600x400X400	cope	1		
49	An29	Ventilator (2x) me termostat	cope	1		
50	An30	Grup Prize (9) per kabinet 19", me sigurese	cope	1		
		Shuma 2	Leke			
		Instalimi Sistemi I Sinjalizimit Kundra Zjarrit				
51	An31	Kabell 2x0.8 mm2+skermo per Alarm zjarri EN-54	ml	900		
52	An32	Central Per Sinjalizim Alarm Zjarri	cope	2		
53	An33	Detektor Tymi te kompletuar me baza	cope	14		
54	An35	Pulsant manual komplet	cope	2		

55	An36	Sirene e Brendeshme	cope	2		
		Shuma 3	Leke			
		Instalimi Sistemi Televiziv				
56	An39	F+V Coaxial Cable per sistemin	ml	200		
57	An40	LNB 4 dalje H/V (kaskad)	Cope	1		
58	An42	Antene UHF 15db BLUHD	Cope	1		
59	An44	Prize TV/SAT 10db (next)(P)	Cope	6		
		Shuma 4	Leke			
		Instalimi Sistemi I Survejimit				
60	An45	Kamera	cope	3		
61	An46	Monitor per sallin operative 22" per CCTV jo TV	cope	1		
62	An47	Regjistrues Digitale NVR	cope	1		
		Shuma 5	Leke			
		SHUMA PER PUNIMET ELEKTRIKE	LEKE			
		SHUMA TOTALE PALESTRA + FUSHAT	LEKE			
		Fondi rezerve 5%				
		SHUMA				
		20 % T.V.SH.	leke			
		SHUMA TOTALE	LEKE			