



REPUBLIKA E SHQIPERISE
BASHKIA E QYTETIT KORCE
D.P.K.ZH.T
Sektori I Projekteve

PREVENTIV

OBJEKTI: PËRMIRËSIMI I BANESAVE EKZISTUESE

Nr An	PERSHKRIMI I PUNIMEVE	NJESL	SASIA	CMIMI	VLERA
I	Punime çatie, Pall nr. 4, (1KT), Rr. "Mihallaq Qirinxi", lagja 5				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	446.0		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	446.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	92.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	18.0		
2/37/5a	Transport mbeturina 5km	m3	31.0		
	Shuma I				
II	Punime çatie, Pall nr 26, (2KT) Rr. "Pandi Kërëku", lagja 6				
1	Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	453.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	31.0		
An	Heqje dritare druri (kafazet e shkalles)	m2	3.9		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	453.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	87.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	23.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	31.0		
2/370	F.V dritare druri (kafazet e shkalles)	m2	3.9		
2/310	Suvatim muri I brendshem (kafazet e shkalles)	m2	14.0		
2/37/5a	Transport mbeturina 5km	m3	34.0		
	Shuma 1				
2	Punime Elektrike (kafazet e shkalles)				
2/481/3	F.V percjelles PV - 500 , 4m/m2	ml	32.0		
2/481/2	F.V percjelles PV - 500 , 2.5m/m2	ml	52.0		
2/481/1	F.V percjelles PV - 500 , 1.5m/m2	ml	14.0		
2/483	F.V celsa e priza	cope	4.0		
	Shuma 3				
	Shuma II				
III	Hidroizolim tarace Pallati nr 18, H/3 (5KT), Rr. "Insan Korca" lagja 17				
An	Prishje shtrese hidroizoluese tarace	m2	330.0		
2/426	Prishje mur tulle parapet	m3	1.6		
2/426/3	Prishje kornize betoni	m3	0.7		
2/64/2	Berje mur tulle parapet ll.b. M-25	m3	1.6		
2/334	Suvatim parapeti I thjeshte	m2	37.0		
2/121/1	Beton kornize parapet C-16/20	m3	0.7		
2/200	Lluster cemento 1:2 3cm	m2	330.0		
2/197	Hidroizolim tarace me emulsion bitumi + 2kk	m2	330.0		
2/203	F.V impjuve llamarine	m2	14.0		

2/206	F.V kasete llamarine	cope	4.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120m/m	ml	64.0		
2/37/5a	Transport mbeturina 5km	m3	28.0		
	Shuma III				
IV	Punime çatie, Pall nr. 12 dhe 13 (1KT), Rr. "Ismail Latifllari" dhe Rr "Mihallaq Qirinxhi", lagja 5				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	460.0		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	460.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	93.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	18.0		
2/37/5a	Transport mbeturina 5km	m3	34.0		
	Shuma IV				
V	Punime çatie, Pall nr. 2, (2KT), Rr. "Naum Karanxha", lagja 4				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	144.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	12.2		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	144.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	57.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	23.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	12.2		
An	Heqje dritare druri (kafazet e shkalles)	m2	1.8		
2/370	F.V dritare druri (kafazet e shkalles)	m2	1.8		
2/37/5a	Transport mbeturina 5km	m3	5.0		
	Shuma V				
VI	Punime çatie, Pall nr. 4, (2KT), Rr. "Jorgji Shtika", lagja 4				
1	Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	250.0		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	250.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	60.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	25.0		
2/37/5a	Transport mbeturina 5km	m3	12.0		
	Shuma VI				
VII	Punime çatie, Pall nr. 6, (2KT) Rr. "Jorgji Shtika", lagja 4				
1	Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	250.0		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	250.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	60.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	25.0		
2/37/5a	Transport mbeturina 5km	m3	12.0		
	Shuma VII				
VIII	Punime çatie, Pall nr 3, (3KT) Rr. "Xhafer Cenko Lubonja", lagja 17				
1	Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	352.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	25.0		
An	Heqje dritare druri (kafazet e shkalles)	m2	10.6		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	352.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	77.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	34.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	31.0		
2/370	F.V dritare druri (kafazet e shkalles)	m2	10.6		
2/310	Suvatim muri I brendshem (kafazet e shkalles)	m2	25.0		
2/37/5a	Transport mbeturina 5km	m3	28.0		
	Shuma 1				

	2 Punime Elektrike (kafazet e shkalles)				
2/481/3	F.V percjelles PV - 500 , 4m/m2	ml	48.0		
2/481/2	F.V percjelles PV - 500 , 2.5m/m2	ml	73.0		
2/481/1	F.V percjelles PV - 500 , 1.5m/m2	ml	21.0		
2/483	F.V celsa e priza	cope	6.0		
	Shuma 2				
	Shuma VIII				
IX	Punime çatie, Pall nr. 7, (3KT), Rr. "Xhafer Cenko Lubonja", lagja 17				
	1 Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	415.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	25.0		
An	Heqje dritare druri (kafazet e shkalles)	m2	10.6		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	415.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	92.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	34.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	25.0		
2/370	F.V dritare druri (kafazet e shkalles)	m2	10.6		
2/310	Suvatim muri I brendshem (kafazet e shkalles)	m2	23.0		
2/37/5a	Transport mbeturina 5km	m3	31.0		
	Shuma 1				
	2 Punime Elektrike (kafazet e shkalles)				
2/481/3	F.V percjelles PV - 500 , 4m/m2	ml	48.0		
2/481/2	F.V percjelles PV - 500 , 2.5m/m2	ml	73.0		
2/481/1	F.V percjelles PV - 500 , 1.5m/m2	ml	21.0		
2/483	F.V celsa e priza	cope	6.0		
	Shuma 3				
	Shuma IX				
X	Punime çatie, Pall nr 15, (2KT) Rr. "Branko Kadia", lagja 6				
	1 Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	406.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	31.0		
An	Heqje dritare druri (kafazet e shkalles)	m2	7.8		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	406.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	80.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	34.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	31.0		
2/370	F.V dritare druri (kafazet e shkalles)	m2	7.8		
2/310	Suvatim muri I brendshem (kafazet e shkalles)	m2	23.0		
2/37/5a	Transport mbeturina 5km	m3	31.0		
	Shuma 1				
	2 Punime Elektrike (kafazet e shkalles)				
2/481/3	F.V percjelles PV - 500 , 4m/m2	ml	48.0		
2/481/2	F.V percjelles PV - 500 , 2.5m/m2	ml	73.0		
2/481/1	F.V percjelles PV - 500 , 1.5m/m2	ml	21.0		
2/483	F.V celsa e priza	cope	6.0		
	Shuma 3				
	Shuma X				
XI	Punime çatie, Pall nr. 37, (2KT), Rr. "Sabaudin Kacidhja", lagja 17				
	1 Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	181.0		
An	Heqje dritare druri (kafazet e shkalles)	m2	1.5		

An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	181.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	50.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	23.0		
2/370	F.V dritare druri (kafazet e shkalles)	m2	1.5		
2/37/5a	Transport mbeturina 5km	m3	7.0		
	Shuma XI				
XII	Punime çatie, Pall nr 30, (3KT), Rr. "Petro Strugji", lagja 6				
1	Punime Ndertimore				
An	Heqje tjegulla ekzistuese cati (e zhvilluar)	m2	288.0		
An	Prishje tavan me koce (kafazet e shkalles)	m2	14.4		
An	Heqje dritare druri (kafazet e shkalles)	m2	5.9		
An	Mbulim cati me tjegulla importi + lende e sharuar+H/izolim	m2	288.0		
2/212	Ulluk shkarkimi horizontal me llamarine xingato d=33cm	ml	57.0		
2/209/a	Ulluk shkarkimi vertikal me P.V.C d=120 m/m	ml	48.0		
2/295	Berje tavan me rrjete teli + suva (kafazet e shkalles)	m2	14.4		
2/370	F.V dritare druri (kafazet e shkalles)	m2	5.9		
2/310	Suvatim muri I brendshem (kafazet e shkalles)	m2	10.0		
2/37/5a	Transport mbeturina 5km	m3	16.0		
	Shuma 1				
2	Punime Elektrike (kafazet e shkalles)				
2/481/2	F.V percjelles PV - 500 , 2.5m/m2	ml	31.0		
2/481/1	F.V percjelles PV - 500 , 1.5m/m2	ml	14.0		
2/483	F.V celsa e priza	cope	3.0		
	Shuma 3				
	Shuma XII				

	Shuma I - XII				
	Fondi rezerve 5%				
	Shuma				
	T.V.SH 20%				
	SHUMA				