

PREVENTIV

Nr	Nr Analizez	Emërtimi i punimeve	Njesia	Sasia	Çmimi	Totali
I		nr.6 Objekti: Shkolla 9-vjecare Abdyl Paralloi,				
1	An.2 2.310	Prishje suvatime muresh 2.57 m x 2 m x 2 ane (tavanet te holli i hyrjes se shkolles)	m2	10.28		
2	An.2 2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	145.6		
3	An.2 2.206	Heqje kasete shkarkimi me llamarine xingat e demtuar	cope	14		
4	2.196/an	Prishje hidroizolimi + shtresave ekzistuese (2.57 m x 26.7m)	m ²	69		
5	2.200	Shtrese lluster cemento 1:2, t = 20 mm (2.57 m x 26.7m)	m ²	97		
6	2.197	Hidroizolim me emulsion bitumi dhe 2 k katrama (taraca e hollit ne hyrjen e shkolles 3 m x 27.7 m)	m ²	83		
7	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	13		
8	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	6		

9	An 2, 2.407	Riparim i pllakes b/a granili mbi parapet tarace ne pjeset e kasetave te shirave	m ²	5.6		
10	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	1315		
11	2.399	Shërbetisje e bojatisje me gëlqere	m ²	4270		
12	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	1340		
13	2.206	Kasete shkarkimi me llamarine xingat	cope	14		
14	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	145.6		
15	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm (3 cop x 2.57 m)	ml	8		
16	2.426/3	Prishje shtresa betoni L = 40 m me trashesi mbi 10 cm deri 15 cm me gjeresi 40 cm	m ³	2.4		
17	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet (tub= 40)x b=0.4 m x h=0.7m + germim per puseten e u.b. 70 x 70 cm x 100 cm	m ³	11.2		
18	An - 22/1	Puseta beton / arme shiu 40 cm x 40 cm h= 100cm + kapak gize	cope	3		
19	2.552	F.V. tubo betoni Db= 200 mm mbi shtrese zhavori	ml	38		
20	2.258	Nenshtrese zhavori nen pllaka trotuari, kunete ,bordure, etj.	m ³	9.12		
21	3.243	Struktura monolite betoni/arme C 16/20 mbi kanal me gjeresi 40 cm me trashesi 15 cm + veshje e tubacionit ne 1m lartese te ullukut te shkarkimit	m ³	2.9394		

22	2.399	Shërbetisje e bojatisje me gëlqere muri rrethues te shkolles me gjatesi 125 ml x 1 m x 2 anet + 2.8 m x 2 ane x 155 m	m ²	1230		
		Shuma per lyerjen e shkolles Abdyl Paralloi	leke			
II		nr.9 Objekti: Shkolla 9-vjecare Naim Frasheri,				
1	An.2 2.209	Heqje ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	47.7		
2	An.2 2.206	Heqje kasete shkarkimi me llamarine xingat e demtuar	cope	9		
3	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m ²	9.8		
4	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	14		
5	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	1339		
6	2.399	Shërbetisje e bojatisje me gëlqere	m ²	3861		
7	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	1159		

8	2.206	Kasete shkarkimi me llamarine xingat	cope	9		
9	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	95.4		
10	2.426/3	Prishje shtresa betoni L = 60 m me trashesi mbi 10 cm deri 15 cm me gjeresi 40 cm	m3	3.6		
11	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet (tub= 40)x b=0.4 m x h=0.7m + germim per puseten e u.b. 70 x 70 cm x 100 cm	m3	16.8		
12	An - 22/1	Puseta beton / arme shiu 40 cm x 40 cm h= 100cm + kapak gize	cope	4		
13	2.552	F.V. tubo betoni Db= 200 mm mbi shtrese zhavori	ml	60		
14	2.258	Nenshtrese zhavori nen pllaka trotuari, kunete ,bordure, etj.	m3	13.92		
15	3.243	Struktura monolite betoni/arme C 16/20 mbi kanal me gjeresi 40 cm me trashesi 15 cm + veshje e tubacionit ne 1m lartese te ullukut te shkarkimit	m3	3.9039		
16	2.312	Suva brenda mur guri ~ 4m, me krah, llaç perzier M 25 (150 m x 1.2 m x 2 ane)	m2	360		

17	2.399	Shërbetisje e bojatisje me gëlqere muri rrethues te shkolles me gjatesi 150 ml x 1.2 m x 2 anet	m ²	360			
Shuma per lyerjen e shkolles Naim Frasheri			leke				
III	nr.14 Objekti: Shkolla e mesme e bashkuar''11 Deshmoret'' Labinot Mal ,						
1	3.303	Skele metalike deri 10m	m2	91			
2	An.2 2.209 An	Heqje ulluk shkarkimi vertikal me llamarine xingat Ø 100 te de	ml	29.6			
3	An.2 2.206 An	Heqje kasete shkarkimi me llamarine xingat e demtuar	cope	8.0			
4	An 2 2.212 An	Heqje ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	44.4			
5	2.295	Suvatim i strehes se catise me rrjete teli + suva (0,35x 98 m)	m2	34.3			
6	2.310	Riparim suvatim mure tulle brenda	m2	45			

7	2.404/1	Boje hidroplastike importi cilesi e I-re (lyerje fasade sipas projektit)	m2	572.6		
8	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	158		
9	2.399	Shërbetisje e bojatisje me gëlqere + tavanet	m ²	2322		
10	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	88.8		
11	2.206	Kasete shkarkimi me llamarine xingat	cope	8		
12	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	59.2		
		Shuma per lyerjen e shkolles 11 Dëshmorët	leke			
IV		nr.10 Objekti: Shkolla 9-vjecare Jeronin De Rada				
1	An.2 2.209	Heqje ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	104		

2	An.2 2.206	Heqje kasete shkarkimi me llamarine xingat e demtuar	cope	10		
3	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	13		
4	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	6		
5	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	312		
6	2.399	Shërbetisje e bojatisje me gëlqere	m ²	2860.7		
7	2,404/1	Boje hidroplastike cilesi e larte (fasada)+ palestra	m ²	1461.2		
8	2.206	Kasete shkarkimi me llamarine xingat	cope	10		
9	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	104.0		
10	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	119		
		Shuma per lyerjen e shkolles Jeronin De Rada	leke			
V		Nr. 1. Objekti: Kopshti publik Nr.3				

1	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	6.5		
2	2,310/an	Riparim suva brenda mur tulle h~4m me krah, Ilaç perzier M 25	m ²	9.8		
3	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	377.96		
4	2.399	Shërbetisje e bojatisje me gëlqere	m ²	895.01		
5	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	424.212		
		Shuma per lyerjen e kopshtit nr.3	leke			
VI		nr.16 Objekti: Shkolla 9-vjecare "Themistokli Kaçi", Trepsenisht				
1	An.2.218	Prishje çatie ekzistuese (prishje ne krahun verior 21 m *6.5 m)	m2	136.5		

2	An2,370	Heqje dritare druri	m2	51.52		
3	An2,383	Heqje dyer druri	m2	23.65		
4	An.2.310	Prishje suvatime muresh	m2	12		
5	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	85.1		
6	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	112		
7	2.206	Kasete shkarkimi me llamarine xingat	cope	6		
8	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	14		
9	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	88		

10	2.375/1	F V dritare d/alumini plastike me dopio xham	m2	51.52		
11	2.383	F.V dyer druri	m2	23.65		
12	2.219	Rindertim çati vendi e zakonshme me HD~8m,tjegulla marseljeze. (21 m x 6.5 m pjesa e demtuar duke bere perforcimet e trareve, binareve , ristelave dhe zevendesimin e tjegullave dhe riparimi I pjeses tjetër sipas kushteve teknike)	m2	136.5		
13	2.219	Ndertim çati vendi e zakonshme me HD~8m,tjegulla marseljeze. (tenda para shkolles me permasat 10 m x 3.5 m)	m2	35		
14	2.196/b	Hidroizolim me nje shtres llaci me baze cemento. Pergatitur nga dy komponente A+B (Hidroizolim me nje shtrese mapej)	m2	464.68		
15	2.273	Davancale mermeri dritare (1.6 x 0,31 x 23 cope)	m2	11.408		
16	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	315		
17	2.399	Shërbetisje e bojatisje me gëlqere	m ²	1086.6		

18	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	226.8		
		Shuma per riparimin e shkolles Themistokli Kaçi	leke			
VII		<u>nr. 5</u> Objekti: Qendra Ekonomike e Arsimit (mag.ind-ushq)				
1	2.404	Boje hidroplastike	m ²	250		
2	2.399	Shërbetisje e bojatisje me gëlqere	m ²	150		
3	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	5		
		Shuma per lyerjen e ambjenteve te qendres ekonomike te arsimit	leke			
VIII		<u>Nr. 4.</u> Objekti: Kopshti publik Nr.15				

1	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	21.5		
2	2,310/an	Riparim suva brenda mur tulle h~4m me krah, Ilaç perzier M 25	m ²	15.5		
3	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	104.46		
4	2.399	Shërbetisje e bojatisje me gëlqere	m ²	790.36		
5	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	565.825		
		Shuma per lyerjen e kopshtit nr.15	leke			
IX		<u>Nr.3.</u> Objekti: Kopshti publik Nr. 9				
1	2.331	Riparim suva e zakonshme fasade mur tulle ~ 8m	m2	23.5		

2	2,310/an	Riparim suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	33.5		
3	2.404	Boje hidroplastike (ambjentet e brendeshme deri 1m lartesi)	m ²	186		
4	2.399	Shërbetisje e bojatisje me gëlqere	m ²	860.4		
5	2,404/1	Boje hidroplastike cilesi e larte (fasada)	m ²	604.5		
6	2.206	Kasete shkarkimi me llamarine xingat	cope	9		
7	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	58		
8	2,404/1	Boje hidroplastike cilesi e larte (muri rrethues)	m ²	225		
9	2.399	Shërbetisje e bojatisje me gëlqere muri rrethues te kopshtit ne anen e brendeshme	m ²	225		

		Shuma per lysterjen e kopshtit nr.9	leke			
		SHUMA I - IX	lek			
		FONDI REZERVE 2 %	lek			
		SHUMA	lek			
		T.V.SH 20 %	lek			
		TOTALI ME T.V.SH.	lek			
		SUPERVIZIMI I OBJEKTEVE	lek			
		KOLAUDIMI I OBJEKTEVE	lek			
		VLERA TOTALE	lek			