

PREVENTIV

I ripare sipas manualeve te ndertimit te vitit 2015

OBJEKTI: NDERTIM I RRJETIT UJSELLES BRADASHESH

N R	Manuali	EMERTIMI I PUNIMIT	NJESI A	SASI A	CMI MI	VLERA
I		Linja e dergimit				
1	anal	Prerje asfalti me makine prerese	ml	600		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	932		
3	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	451		
5	2.37/4 b	Transport materiale ndertimi, dheu me auto deri 9.0 km	m3	1146		
6	2,261	Shtrese rere (per mbrojtje tubi)	m3	162		
7	2.491/i	F.V.Tubo PEHD+rakorderi dn 125 PE 100 PN 10	ml	1973		
8	2,258	Nenshtrese zhavori	m3	164		
9	3.47/1 b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	164		
10	3,205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri	m2	800		
11	3,207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	800		
12	3.212/ b	Shtrese stabilizant t=10cm	m2	800		
13	An	Sperkatje me emulsion bituminoz 1 l/m2	m2	300		
14	3.222/ 2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	300		
15	3.226/ 1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	300		
		Shuma I				
II		Rrjeti Shperndares				
1	anal	Prerje asfalti me makine prerese	ml	800		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	3546		

3	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	2344		
4	2.37/4 b	Transport materiale ndertimi, dheu me auto deri 9.0 km	m3	1320		
5	2,261	Shtrese rere (per mbrojtje tubi)	m3	844		
6	2.491/g	F.V.Tubo PEHD+rakorderi dn 90 PE 100 PN 10	ml	1812		
7	2.491/f	F.V.Tubo PEHD+rakorderi, dn 63, PE 100, PN 10	ml	1683		
8	2.491/e	F.V.Tubo PEHD+rakorderi, dn 50, PE 100, PN 10	ml	1591		
9	2.491/d	F.V.Tubo PEHD+rakorderi, dn 40, PE 100, PN 10	ml	1219		
10	2.491/c	F.V.Tubo PEHD+rakorderi, dn 32, PE 100, PN 10	ml	1587		
11	2,258	Nenshtrese zhavori	m3	149		
12	3.47/1 b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	150		
13	3,205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri L=150ml	m2	237		
14	3,207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri L=150ml	m2	89		
15	3.212/b	Shtrese stabilizant t=10cm , L = 500 ml	m2	400		
16	An	Sperkatje me emulsion bituminoz 1 l/m2 , L = 500 ml	m2	400		
17	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri , L = 500 ml	m2	400		
18	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri , L = 500 ml	m2	400		
19	2.262/4	Shtresë betoni C 16/20 për rrugë t= 10 cm	m ³	51		
20	AN	F.V. Kasete Plastike + Mates+ Rakorderi	cope	75		
21	2.109/2	Themek xokel betoni C- 12/15 per suport kasetash plasitke	m3	0,75		
		Shuma II				
III		Rikonstrukcion Depo Ekzistuese				
1	Analize	Rikonstrukcion depo ekzistuese	cope	1		
		Shuma III	cope			
		SHUMA (I + II + III)				
		Fond rezerve	5%			

		SHUMA				
		T.V.SH.	20%			
		TOTALI	LEKE			