



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**  
**PREVENTIV**

**OBJEKTI : Ndertim "Kongresi i Dibres " Bathore 7**  
**( L = 930 ml, B 9 m, basf= 6m, 2x0.5 kunete, 2x1.0 m, )**

| <b>A</b>   | <b>An.</b>                         | <b>Emertimi i Punimeve</b>                               | <b>Njesia</b>  | <b>Sasia</b> | <b>Cmimi</b> | <b>Vlera</b> |
|------------|------------------------------------|--|----------------|--------------|--------------|--------------|
| <b>I</b>   | <b>PUNIME NE RRUGE</b>             |  |                |              |              |              |
| <b>NR.</b> | <b>Nr.An</b>                       | <b>PERSHKRIMI I PUNIMEVE</b>                             | <b>NJESIA</b>  | <b>SASIA</b> | <b>CMIMI</b> | <b>VLERA</b> |
| 1          | 3.139                              | Germim dheu me eskavator                                 | m <sup>3</sup> | 65           |              |              |
| 2          | 3.158/5a                           | Transport dheu me auto 5km                               | m <sup>3</sup> | 65           |              |              |
| 3          | Man 3 An. 8                        | Mbushje me çakell shkembor                               | m <sup>3</sup> | 168          |              |              |
| 4          | 3.211                              | Shtrese çakelli T=20cm                                   | m <sup>2</sup> | 600          |              |              |
| 5          | 3.212/b                            | Shtrese stabilizanti t=10cm                              | m <sup>2</sup> | 600          |              |              |
| 6          | 3.222/2                            | Shtrese binderi 1x6 cm                                   | m <sup>2</sup> | 600          |              |              |
| 7          | 3.226/1                            | Shtrese asfaltobetoni 1x4cm                              | m <sup>2</sup> | 4700         |              |              |
| 8          | 2/111/2                            | Mure betoni C12/15(themel,xokol betoni)                  | m <sup>3</sup> | 316.2        |              |              |
| 9          | 3.288                              | F.V Hekur betoni I zakonshem O > 10 mm                   | ton            | 3.6          |              |              |
| 10         | An.                                | Ngritje pusete+kapak gize                                | cope           | 20           |              |              |
| 11         | An.152                             | Vizime me boje bikomponente 15cm                         | ml             | 2790         |              |              |
| 12         | An.96                              | Tabele sinjalistike 60-90cm                              | cope           | 16           |              |              |
|            |                                    | <b>SHUMA I</b>   |                |              |              |              |
| <b>II</b>  | <b>PUNIME TROTUARE( 1.1+1.1 m)</b> |  |                |              |              |              |
| <b>NR.</b> | <b>Nr.An</b>                       | <b>PERSHKRIMI I PUNIMEVE</b>                             | <b>NJESIA</b>  | <b>SASIA</b> | <b>CMIMI</b> | <b>VLERA</b> |
| 1          | 3.139                              | Germim dheu me eskavator                                 | m <sup>3</sup> | 465          |              |              |
| 2          | 3.158/5a                           | Transport dheu me auto 5km                               | m <sup>3</sup> | 465          |              |              |
| 3          | Man 3 An. 8                        | Mbushje me çakell shkembor t=10 cm                       | m <sup>3</sup> | 372          |              |              |
| 4          | 3.208                              | Shtrese çakelli T=10cm                                   | m <sup>2</sup> | 1581         |              |              |
| 5          | 3.212/b                            | Shtrese stabilizanti ne trotuar T=10cm                   | m <sup>2</sup> | 1581         |              |              |
| 6          | 3.617                              | F.V. Bordura betoni e parapregatitur M-250 15x25cm       | ml             | 120          |              |              |
| 7          | 2/262/4                            | Beton per fiksim bordure C16/20                          | m <sup>3</sup> | 13.8         |              |              |
| 8          | 3.620                              | Shtrese betoni t=10cm trotuari                           | m <sup>3</sup> | 158.1        |              |              |
|            |                                    | <b>SHUMA II</b>  |                |              |              |              |
| <b>III</b> | <b>PUNIME PER NDRICIMIN</b>        |  |                |              |              |              |
| <b>NR.</b> | <b>Nr.An</b>                       | <b>PERSHKRIMI I PUNIMEVE</b>                             | <b>NJESIA</b>  | <b>SASIA</b> | <b>CMIMI</b> | <b>VLERA</b> |
| 1          | 3.654/1                            | F.V. Tub korrogato Ø80 per telefonine                    | ml             | 1860         |              |              |
| 2          | 3.654/1                            | F.V. Tub korrogato Ø80 per elektrikun, ndriçimin         | ml             | 930          |              |              |
| 3          | 3.an/1sh                           | F.V. Shtylla metalike konike ndriçimi H-9m PAICC-3       | cope           | 32           |              |              |
| 4          | 3.an/ksh                           | F.V. Krah shtylla metalike KRH-MSI 1500/1500/10          | cope           | 32           |              |              |
| 5          | An                                 | F.V Ndricules Led 94W                                    | cope           | 32           |              |              |
| 6          | An                                 | F.V. morsete tre fazore +siguresa+kapak per shtyllen     | cope           | 32           |              |              |
| 7          | An                                 | F.V Elektroda tokezim komplet l=150m                     | cope           | 32           |              |              |
| 8          | 4.131/3.6                          | F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk) | ml             | 956          |              |              |
| 9          | An                                 | F.V kabell tokezimi 1x3.5mmk                             | ml             | 56           |              |              |
| 10         | An                                 | F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A      | cope           | 1            |              |              |
| 11         | 3An/55                             | F.v puseta elektrike kontrolli PVC 40x40 x40             | cope           | 32           |              |              |
| 12         | An-19                              | F.v puseta betoni me kapak gize 80x80x100mm              | cope           | 4            |              |              |
| 13         | An.                                | F.V kuader komandimi per ndriçim rrugor                  | cope           | 1            |              |              |
| 14         | An.                                | F.V kasete shperndarese                                  | cope           | 1            |              |              |
| 15         | 3.139                              | Germime dheu me ekskavator me goma                       | m <sup>3</sup> | 465          |              |              |
| 16         | 3.158/5a                           | Transport dheu me auto 5km                               | m <sup>3</sup> | 465          |              |              |

|    |             |                                    |                |     |  |  |
|----|-------------|------------------------------------|----------------|-----|--|--|
| 17 | 2.261       | Mbushje me rere                    | m <sup>3</sup> | 93  |  |  |
| 18 | Man 3 An. 8 | Mbushje me cakull shkembor (kanal) | m <sup>3</sup> | 230 |  |  |
|    |             | <b>SHUMA III</b>                   |                |     |  |  |
|    |             | <b>SHUMA A</b>                     |                |     |  |  |
|    |             | <b>TVSH 20%</b>                    |                |     |  |  |
|    |             | <b>TVSH TOTALE</b>                 |                |     |  |  |

PREVENTIVUES :  
Ing. Hajredin Murgu

Drejtores Projektive dhe Investimeve  
Ing. Flora MUÇA

Drejtore i Pergjithshem  
Elvis Gjika

**MIRATOI**  
**Rakip SULI**

---

**K R Y E T A R**