

PREVENTIV

OBJEKTI :RIKONSTRUKSION RRUGE BASHKIA DURRES

RRUGA "LEKE DUKAGJINI" 655 ML

| Nr | Nr.AN | ZERAT E PUNIMEVE | NJESIA | SASIA | ÇMIMI | VLERA |
|-----------|-----------------------------------|---|-------------------------|--------------|--------------|--------------|
| I | PUNIME GERMIMI DHE PRISHJE | | | | | |
| 1 | 3.90/b | Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, prani uji, me shk ne mjet. | m ³ | 400 | | |
| 2 | 3.158/5a | Transport dheu me auto deri 5.0 km. | m ³ | 340 | | |
| | | SHUMA I | | | | - |
| II | PUNIME SHITESASH RRUGORE | | | | | |
| 1 | An.164/1a | Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri | m ³ | 136 | | |
| 5 | 3.212/a | Shtrese stabilizanti t = 5 cm | m ² | 1960 | | |
| 6 | 3.222/2 | Shtrese binder me granil gure kave, t=6 cm, perhapur e ngjeshur me makineri | m ² | 1960 | | |
| 7 | 3.226/1 | Shtrese asfaltobetoni me granil gure kave, t=4 cm, perhapur e ngjeshur me makineri | m ² | 1960 | | |
| 4 | An.164/1a | Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri | m ³ | 60 | | |
| | | SHUMA II | | | | |
| | | | SHUMA A (I - II) | | | |
| | | TVSH 20% | | | | |
| | | SHUMA ME TVSH | | | | |

Grupi i punes: