

PREVENTIVI

OBJEKTII: REHABILITIM URA

Nr.	Nr. AN	EMËRTIMI I PUNIMEVE	Njesi	Sasi	Çmimi	Vlera
A		URA "BAILEY" FSHATI KOLANEC (16X4.5)ml				
1	2.25	Germim dheu me ekskavator me goma 0.25m ³ ,kanal me gjeresi deri 2m,tok e zak,kat.III,shka ne toke	m ³	35		
2	2.166	F,.V. Hekur betoni Ø 6 ÷10mm	ton	0.4		
3	2.167	F,.V. Hekur betoni Ø > 10mm	ton	0.34		
4	An164/1b	Mbushje me cakell	m ³	14		
5	2,262/4	Shtrese betoni C 16/20	m ³	3		
6	3.247	Plinta e bazamente b/a monolite C25/30	m ³	12		
7	An	F.V Lllmarine e kodrinuar t= 5 mm, pesha 45kg/m ²	ton	3.220		
		SHUMA A				
		RIKOSTRUKSION URA FSHATI BABIEN (50X3.5)ml				
1	An	Heqje drasash	m ²	150		
2	An	F.V Lllmarine e kodrinuar t= 5 mm, pesha 45kg/m ²	ton	6.620		
3	3.158/1a	Trasport materiale me auto.deris 1 km	m ³	20		
4	2.182	Kostruksione metalike te thjeshta(parmake anesore)	ton	2.25		
		SHUMA B				
		URA "BAILEY" FSHATI PIRG (10x4.5)ml				
1	2.25	Germim dheu me ekskavator me goma 0.25m ³ ,kanal me gjeresi deri 2m,tok e zak,kat.III,shka ne toke	m ³	84		
2	An164/1b	Mbushje me cakell	m ³	3		
3	2.112/2	Mure butobetoni C-12/15	m ³	51		
4	An	F.V Lllmarine e kodrinuar t= 5 mm, pesha 45kg/m ²	ton	2.00		
		SHUMA C				
		URA "BAILEY" FSHATI LIBONIK (7.6x4)ml				
1	2.25	Germim dheu me ekskavator me goma 0.25m ³ ,kanal me gjeresi deri 2m,tok e zak,kat.III,shka ne toke	m ³	11		
2	An	F.V Lllmarine e kodrinuar t= 5 mm, pesha 45kg/m ²	ton	1.360		
3	2.112/2	Mure butobetoni C-12/15	m ³	11		
		SHUMA D				

