



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

PREVENTIV

OBJEKTI: Ndertim Rruga Argjiture Loti 1 nga bathore 5 - Kamez 5

(L = 1350 ml, B =8m, basf= 5m, 2x0.5kunete, 2x1m trotuar-bankine)

I PUNIME PRISHJEJE						
N	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	
1	2.426/1	Prishje mur tulle rrethues me pastrim	m ³	50		
2	2.426/7	Prishje kollonçina b/a ne murin rrethues	m ³	30		
SHUMA I						
II PUNIME NE RRUGE						
N	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	
1	3.139	Germim dheu me eskavator	m ³	675		
2	3.158/5a	Transport dheu me auto 5km	m ³	675		
3	3/353	Mbushje me çakell shkembor	m ³	1687		
4	3.158/5a	Transport çakelli me auto 5km	m ³	1687		
5	3.208	Shtrese çakelli T=10cm	m ²	6750		
5	3.212/c	Shtrese stabilizanti t=15cm	m ²	6750		
6	3.229/4	Shtrese binderi 1x8 cm	m ²	6750		
7	3.233/3	Shtrese asfaltobetoni 1x6cm	m ²	6750		
8	An.	Spostim shtyllash ekzistuese	cope	10		
SHUMA II						
IV PUNIME NE KUB						
N	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	405		
2	3.158/5a	Transport çakelli me auto 5km	m ³	405		
3	3/353	Mbushje me çakell shkembor	m ³	380		
4	3.158/5a	Transport çakelli me auto 5km	m ³	380		
5	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	2700		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	270		
5	2.261	Mbushje me rere	m ³	473		
5	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	108		
SHUMA III						
V PUNIME TROTUARE - bankine(2*1 m)						
N	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	202		
2	3.158/5a	Transport dheu me auto 5km	m ³	202		
2	3/353	Mbushje me çakell shkembor	m ³	337.5		
3	3.158/5a	Transport çakelli me auto 5km	m ³	337.5		

3	3.617	F.V. Bordura betoni e parapregatitur M-25015x25cm	ml	2700		
4	2/262/4	Beton per fiksime bordure C16/20	m ³	270		
		SHUMA IV				
XI	PUNIME PER GJELBERIMIN DHE PER RRETHRROTULLIM TEK RRUGA DAJTI+Berisha					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.617/1	F.V. Bordura betoni per rrethrotullimin dhe bordura pemesh 0.6 x 0.2 x 0.8 ml	ml	120		
2	3.643	Mbjellje bari ne rrethrotullim	m ²	80		
3	An	Punime dheu dhe mbushje me humus	m ²	80		
		SHUMA V				
		SHUMA TOTALE				
		TVSH 20%				
		TOTALI				

Preventivues:

Ing. Eglantina Disha

Drejtori D.P.K.ZH.T

Ing. Flora Muça

MIRATOI
Rakip SULI

K R Y E T A R