

PREVENTIVI

PREVENTIVI I OBJEKTIT "NDERTIMI I RRJETIT TE KANALIZIMEVE TE UJRAVE TE ZEZA DOMJE"

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
<b>I Punime ne rrjetin e kanalizimeve</b>						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m <sup>2</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	2,591.00		0.00
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	1,448.00	0	0.00
3	an3.An/1t	F V tuba te brinjezuar HDPE SN8 d=200 mm	ml	250.00	0	0.00
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	430.00	0	0.00
5	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	64.00	0	0.00
6	An-1	Ndertim puseta betoni H=1-2m, D=1m + kapak gize	cope	9.00	0	0.00
7	An-2	Ndertim puseta betoni H=2-3.5m, D=1.5m + kapak gize	cope	7.00	0	0.00
8	An-3	Ndertim puseta betoni H=3.5-4.5m, D=2m + kapak gize	cope	5.00	0	0.00
9	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	270.00	0	0.00
10	2.19	Hedhje, rrafshim, mbushje dheu me krah, kategoria III (kanalet)	m <sup>3</sup>	1,143.00	0	0.00
11	2.261	Shtrese rere (ne perimeter te tubave)	m <sup>3</sup>	251.57	0	0.00
12	2.258	Nenshtrese zhavori (mbi tuba)	m <sup>3</sup>	650.00	0	0.00
13	2.425/2	Grope septike 12 m3	cope	1.00	0	0.00
<b>SHUMA</b>						<b>0.00</b>
<b>TVSH</b>						<b>0.00</b>
<b>TOTALI</b>						<b>0.00</b>

**Projektues**  
 Shoqëria "MCE" sh.p.k  
**Administrator**  
 Inxh. Petrit MUJA  
**Firma / Vula**