

PREVENTIV

Objekti: *Rrethimi i Stadiumit te Lojrave me Dore*

Nr	Analiza	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefte
Punuime Prishje						
1	2.426	Prishje mshtrese pllakash trotuari me pastrim	m2	120		
2	2.426/3	Prishje shtresa betoni	m3	26		
3	2.288	Trotuar me pllaka granili (me pllakat ekzistuese)	m2	123		
4	2. 1a	Germim e transport dheu me krah per plinta	m3	34		
shuma -1-						
Punime B/Arme						
1	2.109/2	Themel e xokol betoni C - 12/15	m3	26		
2	An	Kollona Dekorative H-6m Skena	cope	6		
3	An	Kollona Dekorative H-3m Rrethimi	cope	26		
4	2.122/1a	Solete b/a beton C20/25 (Korrniza e Skenes)	m3	6		
5	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	4.2		
6	2.181	Konstruksione metalike te perbera	ton	0.5		
shuma -2-						
Punime te Ndryshme						
1	2.411	Parapet Dekorativ b/a granili parafabrikuar	m2	128		
2	2.138	Brez B/Arme ne forme parabilike (korimo rrethimi)	m3	6		
3	2.373	Vetrat me xham te temperuar (tavani i skenes)	m2	20		
4	2.439/1	Panele derrase per skele	m2	54		
5	2.440	Kambaleca metalike	cope	8		
shuma -3-						
Punime Elektrike						
1	480/4	F.V tub plastmasi Ø 27 ~ 30 mm	ml	300		
2	2.482/1	F.V percjelles PPV, Ø 2 x 1.5 mm2	ml	500		
3	2.482/1	F.V percjelles PPV, Ø 4 x 6.0 mm2	ml	200		
4	2. a-102	Kasete metalike me zbara bakri 50x40x25cm per I=330A	cope	1		
5	2. a-104	Automat termo-elektro magnetik,4P;380V;100A	cope	2		
6	An	F V kuader komandimi komplet me santeri+fotoelem.	cope	1		
7	2.a-74	Elektroda tokezimi, profil zingato e bakeriz., L=1.5m	cope	14		
8	2.a-93	Percjelles tokezimi bakri , Cu, S=35mm2 i zhveshur	ml	30		
9	2. a-128	Ndricues tip Glob,shkarkim me avuj zhive, Sap,75w	cope	26		
shuma -4-						
Shuma 1 ~ 4						
Fonde Rezerve 3%						
Shuma						
TVSH 20%						
Shuma Totale						

PREVENTIVUES

Tek. Mustaf VATOCI

Ing. Egzon MUHAMETAJ

MIRATOI

DREJTORI I PZHT

Ark. Hazir ISUFAJ