

## PREVENTIV ZBATIMI

### OBJEKTI:

PROJEKT ZBATIMI SISTEMIM ASFALTIM I RRUGES SE VARREZAVE TE QYTETIT BULQIZE , BASHKIA BULQIZE

BASHKIA BULQIZE

Gjatesia L =862 ml

Nr.	Nr. Analize	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1	3.160/a	Germim e transport dheu kat III-te me skreper, L=100m dhe V=6~6.5m3	m <sup>3</sup>	652		-
2	3.87/a	Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	152		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	286		-
		<b>Shuma 1</b>				-
<b>2</b>		<b>PUNIME SHITESASH NE RRUGE</b>				
1	An-8	Mbushje me cakell t = 15 cm	m <sup>3</sup>	711		-
2	3.47/1b	Shtrese me material rrethor per bankine t=20cm	m <sup>3</sup>	259		-
3	3.212/b	Shtrese stabilizant t=10cm	m <sup>2</sup>	3,448		-
4	3.229/1	Shtrese binderi me zall lavatrice,5cm,me makineri	m <sup>2</sup>	3,448		-
5	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m <sup>2</sup>	3,448		-
6	An151	Vizime me boje bikomponente	m <sup>2</sup>	207		-
7	An155	F V tabela rrugore te ndryshme D=90cm	cope	6		-
		<b>Shuma 2</b>				-
<b>3</b>		<b>PUNIMET E VEPRAVE TE ARTIT</b>				
<b>A</b>		<b>Ndertim TOMBINO (5x2 )</b>				
1	3.87/a	Germim dheu me ekskavator goma 0.15 m <sup>3</sup> , ne themele, toke zak, kategoria III, me shkarkim ne toke	m <sup>3</sup>	126		-
2	3.243	Ndertim Tombino (5x2 )	cope	3.0		-
3	An-8	Mbushje me cakell	m <sup>3</sup>	78		-
4	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	12		-
5	3.352	Mbushje me gur kromi	m <sup>3</sup>	568		-
		<b>Shuma A</b>				-
		<b>SHUMA</b>				-
		T.V.SH	20%			-
		<b>SHUMA TOTALE</b>				-

V.O . Cmimet jane bere ne baze te vkm 619 date 15.07.2015

**PREVENTIVUES:**  
**Ing.Hajredin MURGU**