

PREVENTIVI I OBJEKTIT: "REHABILITIM I QENDRES LAGJE GOSTIL LOTI -1, PROJEKTI PERMIRESIM I INFRASTRUKTURES ME TROTUARE, DREJTORIA E POLICISE-LAGJE GOSTIL|"

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
I PUNIME PRISHJE NE OBJEKTE PALLATE						
1	An-1	Prishje suvatim I jashtem	m ²	698.00		
2	2.426/3	Prishje shtresa betoni(trotuare betoni ekzistues)	m ³	15.00		
3	2.426/1	Prishje mur tulle me pastrim	m ³	1.00		
4	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	185.00		
5	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	185.00		
SHUMA I						
II PUNIME NE TARRACA NE OBJEKTE PALLATE						
1	2.426/3	Prishje shtresa betoni(tarrace)	m ³	67.00		
2	2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m ²	711.00		
3	3.243	Struktura monolite betoni C 16/20	m ³	33.40		
4	2.197	Hidroizolim me emulsion bitumi dhe 2 k katrama	m ²	920.00		
5	2.2	Shtrese lluster cemento 1:2 t = 20 mm	m ²	835.00		
6	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	171.00		
7	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	60.00		
8	2.206	Kasete shkarkimi me llamarine xingat	cope	16.00		
9	2.203	Veshje kornize llamarine xingat	m ²	140.00		
SHUMA II						
III PUNIME SHTRESASH SUVATIMI DHE MURE NE OBJEKTE PALLATE						
1	2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m ³	1.00		
2	2.334	Suva e zakonshme fasade mur tulle mbi 8m lartesi	m ²	698.00		
3	2.358/b	Veshje fasade me polisterol jeshil t=5cm + rrjete + suva.	m ²	1,770.00		
4	2.273/5	Shtrese me pllaka mermeri t=3cm "JANINA"	m ²	10.00		
5	2.273/4	Shtrese me pllaka mermeri t=2cm "JANINA"	m ²	30.00		
6	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	910.00		
7	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	910.00		
8	3.212/b	Shtrese stabilizanti t=10cm	m ²	910.00		
9	2.29	Bordura trotuari 20x35cm te parapergatitura	ml	200.00		
SHUMA III						
IV PUNIME BOJATISJE NE OBJEKTE PALLATE						
1	2.404/1	Boje hidroplastike cilesi e larte	m ²	2,110.00		
SHUMA IV						
V PUNIME PRISHJE NE LULISHTE						
1	An-1	Prishje suvatim I jashtem(muri rrethues)	m ²	390.00		
2	An-2	Heqje pllaka t=6cm ekzistuese	m ²	225.00		
3	An-3	Heqje Bordura trotuari	ml	295.00		
4	An-4	Ç'montim stola ekzistues	cope	10.00		
5	3.197/1	Prishje shtrese çakelli t = 15 cm, me makineri	m ²	225.00		
6	2.1	Germim dheu me krah e transport k dore 10m,kat III	m ³	130.00		
7	2.5	Germim e mbushje dheu me krah kat III	m ³	54.00		
8	2.1a	Germim dheu me krah e transport k dore 10m,kat IV(shtrimi I rrjetit elektrik+puseta)	m ³	10.00		
9	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	86.00		
SHUMA V						
VI PUNIME SHTRESASH SUVATIMI BOJATISJE NE LULISHTE						
1	2.348	Suva xokoli me granil e çimento te zak me çokitje(muri rrethues)	m ²	390.00		
2	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri(fusha)	m ²	190.00		
3	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri (lulishtja)	m ²	375.00		
4	3.212/a	Shtrese stabilizanti t=5cm(fusha)	m ²	190.00		
5	3.212/b	Shtrese stabilizanti t=10cm (lulishtja)	m ²	375.00		
6	3.243	Struktura monolite betoni C 16/20(fusha)	m ³	19.00		
7	3.243	Struktura monolite betoni C 16/20(lulishtja)	m ³	40.00		
8	2.291	Bordura trotuari 25x12cm derdhur ne vend(fusha e basketbollit)	ml	58.00		
9	2.291	Bordura trotuari 25x12cm derdhur ne vend(lulishtja)	ml	300.00		

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
10	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	300.00		
11	2.258	Nenshtrese zhavori(kendi I lojrave)	m ³	26.00		
12	An-5	Shtrese derrasa FM 4.0cm	m ²	81.00		
13	An-6	Rashinim llakim	m ²	81.00		
14	M.3An151	Vizime me boje bikomponente(per fushat)	m ²	12.00		
15	2.237/a	Lyerje betoni me hyperdesimo te fushes se basketbollit)	m ²	190.00		
16	2.237/a	Lyerje betoni me hyperdesimo (davancial muri rrethues)	m ²	255.00		
17	2.401	Boje vaji siperfaqe metalik	m ²	350.00		
SHUMA VI						
VII	PUNIME HEKURI NE LULISHTE					
1	3.29	F V hekur betoni ne b/arme Ø 3 ~ 5mm(fushat 15x15)	ton	0.50		
2	3.29	F V hekur betoni ne b/arme Ø 3 ~ 5mm(betonet 15x15)	ton	0.60		
3	An-7	Rrethim me konstruksion metalik dhe rrjete teli te plastifikuar	m ²	174.00		
4	2.182	F V konstruksione metalike te thjeshta(riparime per rrethimin ekzistues)	ton	0.80		
SHUMA VII						
VIII	PUNIME ELEKTRIKE NE LULISHTE					
1	3.An/1sh	FV shtylla metalike konike ndricimi H=9m PAICC-3(fusha e basketbollit)	cope	3.00		
2	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	3.00		
3	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	3.00		
4	4.133/3.7	F.V.ne toke kablo Cu fuqie ÷1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm ²	ml	20.00		
5	An-8	F.V. Kabell elektrik FROR 2x2.5 per shtylla 9ml	ml	27.00		
6	An-9	Ndricues LED 94W	cope	3.00		
7	3.An	F V kuader komandimi komplet me santeri+fotoelement	cope	1.00		
8	3.An/et	FV elektroda tokezimi te xinguara 50x3mm L=150cm	cope	3.00		
9	An-10	F.V. morseteri shtylle 3P=sig.16A+kapak	cope	3.00		
10	An-11	F V shtylla metalike per ndricim, H=6m, d=160mm(lulishtja)	cope	9.00		
11	An-12	F V Ndricues Clima Led 80W me lente simetrike	cope	9.00		
12	An-13	F V Morseteri, kapak,Sigurese	cope	9.00		
13	An-14	F V Elektrod Tokzimi te xinguara 50X3mm,kapigorde togezimi	cope	9.00		
14	3An.pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	9.00		
15	An-15	F V Kabell Fror 3x1.5	ml	9.00		
16	An-16	Kabull elektrik AL NA2XY4X25mm	ml	150.00		
17	An-17	Kabull PVC, Per togzim	ml	9.00		
18	An-18	Tub PVC fleksibel Ø 75 mm	ml	200.00		
19	An-19	Kasete metalike me zbara	cope	1.00		
20	An-20	Automat 3P	cope	1.00		
21	An-21	Kontaktor (Leshues)	cope	1.00		
22	An-22	Mbrojtje termike	cope	1.00		
23	An-23	Automat kryesor	cope	1.00		
24	An-24	Automat diferencial	cope	1.00		
25	An-25	F.V. Tub plastik d=200mm (per vendosjen e shtyllave)	ml	9.00		
26	2.261	Shtrese rere (nen dhe mbi tubacione + kompaktesim)	m ³	5.00		
27	3.243	Struktura monolite betoni C 16/20 (per fiksimin e shtyllave)	m ³	2.00		
SHUMA VIII						
IX	PUNIME SISTEMIMI NE LULISHTE					
1	3.2	Prerje bime te vogla ø ~ 10cm	m ²	2,094.00		
2	3.643	Mbjellje bari	m ²	2,094.00		
3	3.1	Skarifikim bari me lopate	m ²	2,094.00		
4	M.3-An165	F.V. Fidane shkurre dekorative "Oleander"	cope	15.00		
5	M.3-An169	F.V mbjellje peme dekorative Bli 16-18cm	cope	15.00		
6	An-26	F.V Stola urbane 2	cope	8.00		
7	An-27	F.V Kosha Mbeturinash drejtekendore (sipas Detajit me Veshje Druri)	cope	10.00		
8	An-28	F.V. Kosha Basketbolli (kompletuar)	cope	2.00		
9	An-29	F.V. Porta per Futbollin (kompletuar)	cope	2.00		
10	An-30	F.V. Rrjete Volebolli + Shtyllat (kopletuar)	cope	1.00		
11	An-31	Topa Futbolli Profesional	cope	10.00		
12	An-32	Topa basketbolli Profesional	cope	10.00		

VLERESUAR SIPAS VKM Nr. 629 Dt.05.11.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
13	An-33	Topa volejbolli Profesional	cope	10.00		
14	An-34	F.V Kende lojrash per femije(Loje multifunkzionale)	cope	1.00		
15	An-35	F.V Kende lojrash per femije(Lisharese)	cope	1.00		
		SHUMA IX				
		SHUMA I-IX				
		TVSH	20%			
		TOTALI				

Preventivoi: Ark.Andrit SHEHU