

**PREVENTIV
OBJEKTI: SISTEMIM ASFALTIM RRUGA RRASH VORFË-VORFË**

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
		PUNIME NE TRUP TE RRUGES L=580ml				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III, me shk ne mjet	m ³	181.72		-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ²	181.72		-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri (segmenti perpara dhe pas ures)	m ³	176		-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	2,088.0		-
5	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m ²	2,088.0		-
6	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	1,856.0		-
7	3.212/b	Shtrese stabilizanti t=10cm (bankina)	m ²	232		-
8	3.240	Struktura monolite betoni C 12/15 (bordura monolite , kuneta)	m ³	50.0		-
		Shuma 1				-
		PUNIME NE URE DHE VEPRA ARTI				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	12.0		-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	12.0		-
3	3.244	Struktura monolite betoni C 20/25	m ³	6		-
4	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.7		-
5	2.112/2	Mure buto betoni C - 12/15	m ³	7.3		-
		Shuma 2				-
		SHUMA				-
		TVSH 20%				-
		TOTAL				-

**PREVENTIVOI
"Novatech Studio"shpk
Ing.Emil Nova**