

PREVENTIV

Objekti : “Sistemim asfaltim rruga Degezim i rruges Koplík Razem per tek Rruga e Reçit”

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
PUNIME NE TRUP TE RRUGES						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , toke zak, kategoria III, me shk ne mjet	m ³	1,431	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	1,431	-	-
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri (segmenti perpara dhe pas ures)	m ³	3,734.89	-	-
4	3.206	Shtrese zhavori lumi t=30cm, perhapur e ngjeshur me makineri (segmenti perpara dhe pas ures)	m ²	700	-	-
5	3.212/b	Shtrese stabilizanti 10cm per rrugen	m ²	1,800	-	-
6	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	1,150.0	-	-
7	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	1,700.0	-	-
8	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m ²	7,200.0	-	-
9	3.212/b	Shtrese stabilizanti 10cm per bankinen	m ²	1,800	-	-
PUNIME NE URE DHE VEPRA ARTI						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	30.0	-	-
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	30.0	-	-
3	3.245	Struktura monolite betoni C 25/30 per uren	m ³	93	-	-
4	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	10.5	-	-
5	3.206	Shtrese zhavori lumi t=30cm, perhapur e ngjeshur me makineri (kembet e ures)	m ²	20	-	-
6	3.294	F V detaje metalike ne b/a	ton	0.1	-	-
7	3.240	Struktura monolite betoni C 12/15	m ³	7.0	-	-
8	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	m	10.0	-	-
SHUMA						-
TVSH 20%						-
TOTAL						-

**PREVENTIVOI
"Novatech Studio"shpk
Ing.Emil Nova**