

PREVENTIV

Objekti: Sistemim Asfaltim Rruga Fshati Brest i Eperm
Bashkia Dibër

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
1		PUNIME GERMIMI DHE MBUSHJE NE RRUGE				
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet (prishje e shtreses egzistuese t=10 cm)	m ³	2,466		
2	An-9	Mbushje me zhavor ne trupin e rruges, perhapur e ngjeshur me makineri (seksionim +kasonete)	m ³	200		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	2,466		
		Shuma 1				
2		PUNIME ASFALTIMI				
1	An.164/1a	Shtresa me cakell e gur gurore,perhapur e ngjeshur me makineri 30 cm	m ³	1,500		
2	3.212/b	Shtrese stabilizant 10 cm	m ²	5,000		
3	3.212/b	Shtrese stabilizant 10 cm per bankine	m ²	1,000		
4	3.229/1	Shtrese binderi me zall lavatrice, 5cm, me makineri	m ²	4,000		
5	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m ²	4,000		
		Shuma 2				
3		PUNIME PER TOMBINO DHE KANALE BETONI				
		Ndertim Tombino Box (2x2)				
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	48		
2	3.An-8	Mbushje me cakell pas mureve	m ³	44		
3	3.248	Struktura monolite betoni me çakell C 30/37 (mure+soletone)	m ³	24		
4	3.240	Struktura monolite betoni C 12/15	m ³	5		
5	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.40		
6	3.289	F V hekur betoni periodik, Ç - 5, Ø > 12mm	ton	2.72		
7	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	48		
		Shuma 3				

4 PUNIME NE SINJALISTIKE					
1	An129	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Akrelike	ml	2,000	
2	An139	Vijezim shirita me gjeresi 30 cm, kalim kembesoresh. Akrelike	ml	16	
3	An158	FV tabela te ndryshme rrugore D=60cm	copë	10	
4	An157	F V tabela rrugore treguese 60x20cm	cope	1	
SHUMA 4					
SHUMA (1-4)					
T.V.SH.			20%		
SHUMA ME T.V.SH.					

Shenime: Çmimet e preventivit jane ne baze manualit te çmimeve te vitit 2015.

Preventivues :
ERALD-G SH.P.K

Ing. Gezim Islami