



**BASHKIA SHKODER**

**MIRATOHET**

**KRYETAR**

**BARDH SPAHLA**

**PREVENTIV I PUNIMEVE**

**Objekti: Rikonstruksion rruga "Memej"**

<b>Nr</b>	<b>Analiza</b>	<b>Emertimi i zerit te punes</b>	<b>Njesia</b>	<b>Sasia</b>
		<b>Kap I. Shtresa rrugore</b>		
3	2.426/3	Prishje shtresa betoni ( Bordura, trotuar, puseta, shtresa betoni hyrese , rrugore etj)	m3	25.00
5	3.89/b	Germim kanali me eskavator me gom 0.25m3, ne kanale me gjeresi<2m.	m3	415.00
6	3.158/5a	Transport dheu me auto deri 5.0 km	m3	440.00
8	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	980.00
9	3.212/b	Shtrese stabilizant t=10cm	m2	980.00
11	3.222/1	Shtrese binderi me gur kave t=5cm me makineri	m2	980.00
12	3.224/1	Shtrese asfaltobetoni, me gur kave 3 cm, me makineri	m2	980.00
	2.288	Trotuar me pllaka granili me boje	m2	215.00
	2.261	Shtrese rere t= 5cm	m3	11.00
	2.262/1	Shtrese betoni C 7/10 (per trotuarin) t = 7cm	m3	15.00
13	3.183/a	Shtrese zhavori t=10cm per trotuare	m2	280.00
15	3.243	Shtrese betoni C16/20 ( per hapsirat anesore)	m3	7.00
17	3.617	Fv bordura betoni 15*25cm	ml	440.00
18	2.262/3	Shtrese betoni C12/15 t=10cm per fiksimin e bordurave	m3	10.00

<b>Kap II. Ujesjellesi</b>				
1	3.89/a	Germim kanali me eskavator me gom 0.25m <sup>3</sup> , ne kanale me gjeresi<2m.	m <sup>3</sup>	100.00
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	100.00
3	2.491/g	F.V Tuba e rakorderi ujesjellesi PE d=90mm, t = 6.7 mm, PN 10	ml	190.00
4	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10 (lidhjet me banesat)	ml	105.00
5	2.261	Shtrese rere per mbulimin e tubit	m <sup>3</sup>	29.00
	2.258	Nenshtrese zhavori per kanale	m <sup>3</sup>	60.00
10	An	F.v saricineske d=90 Pn 10Standart EN 1074;En 1171	cope	5.00
13	An	Pusete kontrolli 1x1x1 m b/a 20/25,kapak gize	cope	6.00
	An1	Lidhje me rrjetin ekzistues	cope	1.00
<b>Kap III.Linja e KUZ</b>				
1	3.89/a	Germim kanali me eskavator me gom 0.25m <sup>3</sup> , ne kanale me gjeresi<2m.	m <sup>3</sup>	210.00
2	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	210.00
3	2.261	Shtrese rere per mbulimin e tubit	m <sup>3</sup>	40.00
	2.258	Nenshtrese zhavori per kanale	m <sup>3</sup>	90.00
4	3.An/1t	Fv Tub I brinjezuar HDPE SN8 Dj315mm	ml	195.00
5	2.575	Pusete kontrolli 1x1x1.5m	cope	9.00
8	An-8	Fv Tub I brinjezuar HDPE SN8 Dj200mm	ml	90.00
	An1	Lidhje me rrjetin ekzistues	cope	2.00
<b>Kap IV. Linja e KUB</b>				
1	3.89/a	Germim kanali me eskavator me gom 0.25m <sup>3</sup> , ne kanale me gjeresi<2m.	m <sup>3</sup>	115.00
4	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	115.00
5	3.An/1t	Fv Tub I brinjezuar HDPE SN8 Dj315mm	ml	215.00
8	2.261	Shtrese rere per mbulimin e tubit	m <sup>3</sup>	23.00
9	2.258	Nenshtrese zhavori per kanale	m <sup>3</sup>	65.00
16	3.An-23	Puseta b/a shiu 40*60cm me kapak zgare gize	cope	13.00
18	3.243/1	Struktura te holla monolite betoni C 16/20 per kuneta	m <sup>3</sup>	10.00
	3.183/a	Shtrese zhavori t=10cm	m <sup>2</sup>	108.00
	An1	Lidhje me rrjetin ekzistues	cope	1.00

