



## PREVENTIV ZBATIMI

**II: "STUDIM PROJEKTIM RINDERTIMI I MUREVE MBAJTES TE SHESH LLATEVE NE QYTETIN FUSHE ARREZ" BASHKIA FUSHE ARREZ (LOT**

Perskrimi i punimeve	Njesia	Sasia
<b>Mure mbajtese</b>		
Germim dheu me ekskavator goma 0.25 m <sup>3</sup> , ne themele gjeresi, toke zak, kategoria III, me shkarkim ne toke	m <sup>3</sup>	1280
Mbushje me zhavorr pas mureve	m <sup>3</sup>	2000
Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m <sup>2</sup>	395
F.V hekur betoni	ton	101
Struktura monolite betoni me çakell C 12/15 shtresa	m <sup>3</sup>	62
Struktura monolite betoni C 25/30 per Mure	m <sup>3</sup>	893
Nenshtrese zhavor lumi t=10cm	m <sup>3</sup>	649
Tuba drenimi PVC D=100 mm	ml	350
Shtrese me guri granili te zakonshme 30x30 cm	m <sup>2</sup>	900
		<b>Shuma 1</b>
<b>Riparim shkallesh</b>		
Shtrese me pllaka guri te zakonshme 30x30 cm	m <sup>2</sup>	25
Struktura monolite betoni me çakell C 12/15 shtresa	m <sup>3</sup>	16
Ulluk Distancues 5x5 cm	ml	150
		<b>Shuma 2</b>
		<b>Shuma (1 +2 )</b>
		<i>Fondi rezerve 3 %</i>
		<b>Shuma</b>
		<i>T.V.SH 20 %</i>
		<b>Shuma totale</b>

