



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Rikonstruksion Rruget Nene Tereza+Lunxheria seg + Ndertim Ramadan Sino+Lukove+Lenie+Butrinti+ seg. rruga Lezhe

OBJEKTI : Ndertim Rruga Nene Tereza L=790 ml +B= 11 m Basft 6m,(2 x 0.5) kunete, + (2x 2.0 m) Trotuare

A	An.	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I						
PUNIME GERMIMI						
1	3.139	Germim Dheu e shtresash me Eskavator Kt III	m ³	158		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	158		
3	3 An. 8	Mbushje me çakell shkembor	m ³	79		
4	An.	Spostim Shtyllash Elektrike (komplet me Kabllo)	cope	14		
5	an	Frezim Asfalti	m ²	4740		
SHUMA I						
II						
PUNIME NE RRUGE+mure						
1	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	4740		
2	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	347.6		
3	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	9.48		
4	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	2.1		
5	3.654	Furnizim vendosje tuba drenazhi O 100	ml	32		
6	An.	Ngritje pusete+kapak gize	cope	15		
SHUMA II						
III						
PUNIME BORDURE + KUNETE						
1	2.262/4	Shtrese betoni c 16/20 Kunete betoni	m ³	79		
2	3.617	F V bordura betoni 15x25 cm	ml	1580		
3	2.262/4	Shtrese betoni c 16/20 poshte bordures 0.03 m3/ml	m ³	47.4		
SHUMA III						
IV						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.an 8	Mbushje me çakell shkembor	m ³	395		
2	3.an/1t	F.V. Tuba i brinjezuar Ø 315	ml	1548		
3	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	54		
SHUMA IV						
VI						
PUNIME TROTUARE(2 X 2)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3. an 8	Mbushje me çakell shkembor t= 20 cm	m ³	632		
2	3.620	Shtrese pllaka trotuari t=6 cm	m ²	2607		
SHUMA VI						
VIII						
PUNIME PER NDRIÇIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	790		
2	3.an/1sh	F.V. Shtylla metalike konike ndriçimi H-9m PAICC-3	cope	33		
3	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	33		
4	An	F.V Ndrices led 94W	cope	33		
5	3.An/et	F.V. morsete tre fazore +siguresa+kapak per shtyllen	cope	33		
6	3.an/ksh	F.V Elektroda tokezim 50x3 mm komplet l=150m	cope	33		
7	2.481/2	F.V Percjelles PV-500 O 2.5 mm ²	ml	363		

8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	790		
9	An	F.V kabell tokezimi 1x3.5mm	ml	53		
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1		
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	33		
12	3.An.14	F.V kuader komandimi komplet me Santeri+ Fotoelement	cope	1		
13	An.	F.V kasete shperndarese	cope	1		
14	3.139	Germime dheu me ekskavator me goma	m ³	158		
15	3.158/5a	Transport dheu me auto 5km	m ³	158		
16	2.261	Mbushje me rere	m ³	80		
17	man 3. an 8	Mbushje me cakull shkembor (kanal)	m ³	78		
SHUMA IV						
IX PUNIME PER SINJALISTIKEN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	Njesia	Sasia	Çmimi	Vlera
1	An151	Vizime me boje bikomponente (Gjatesi x 3 ane x 12 cm = totali m2)	m ²	288		
2	An138	Vizime me boje bikomponente paste per kembesore	m ²	36		
3	An155	F.V. Tabela sinjalistike rrugore	cope	10		
Shuma X			leke			
SHUMA A						
OBJEKTI : Ndertim Rruga "Ramadan Sino" Laknas						
(L = 240 ml, B = 5m, basf = 4m, 2x0.5 bankine,)						
B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	120		
2	3.158/5a	Transport dheu me auto 5km	m ³	120		
3	An. 8	Mbushje me çakell shkembor	m ³	180		
4	3.211	Shtrese çakelli T=20cm+bankine	m ²	1200		
5	3.212/b	Shtrese stabilizanti t=10cm+bankine	m ²	1200		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	960		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	960		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	62.4		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.88		
10	An.	Ngritje pusete+kapak gize	cope	0		
11	An.	Spostim shtyllash	cope	2		
12	2/426/2	Prishje mure me blloqe + transport	m ³	96		
13	An.152	Vizime me boje bikomponente 15cm	ml	520		
14	An.96	Tabele sinjalistike 60-90cm	cope	2		
SHUMA I						
II PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	134.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	134.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	112.4		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	230		
6	An-20	F.v puseta betoni me kapak gize 80x80x150mm	cope	5		
SHUMA II						
SHUMA B						
OBJEKTI : Ndertim Rruga "Lukove+Lenie"						
(L = 180ml; L=120m, B=4m, basf = 4m,)						

C	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	60		
2	3.158/5a	Transport dheu me auto 5km	m ³	60		
3	An. 8	Mbushje me çakell shkembor	m ³	144		
4	3.211	Shtrese çakelli T=20cm	m ²	1200		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1200		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1200		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1200		
8	An.	Spostim shtyllash	cope	2		
9	An.152	Vizime me boje bikomponente 15cm	ml	640		
10	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA C						
OBJEKTI : Ndertim Rruga " BUTRINTI "LAKNAS , Bashkia Kamez						
L=1020 m B= 4 .5asfalt L= 1,020						

D	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	emal jusufati
1	3.139	Germim dheu me eskavator	m ³	229.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	229.5		
3	An. 8	Mbushje me çakell shkembor	m ³	459		
4	3.211	Shtrese çakelli T=20cm	m ²	4590		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	4590		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	4590		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	4590		
8	An.	Ngritje pusete+kapak gize	cope	7		
9	An.	Spostim shtyllash	cope	5		
10	An.152	Vizime me boje bikomponente 15cm	ml	3060		
11	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA I						
II						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	678		
2	3.158/5a	Transport dheu me auto 5km	m ³	678		
3	3 An. 8	Mbushje me çakell shkembor	m ³	1200		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	400		
5	3.an/2t	F.V. Tuba I brinjezuar Ø 400	ml	650		
6	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	24		
SHUMA II						
SHUMA D						

OBJEKTI : Ndertim Rrugicat pingul me Rrugen" Fush Arrez "

(L=600 ml, B=4 m, basf= 4 m)

E	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESI	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	120		
2	3.158/5a	Transport dheu me auto 5km	m ³	120		
3	Man 3 An. 8	Mbushje me çakell shkembor	m ³	274.3		
4	3.211	Shtrese çakelli T=20cm	m ²	2400		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2400		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2400		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	2400		
8	An.	Ngritje pusete+kapak gize	cope	2		
9	An.152	Vizime me boje bikomponente 15cm	ml	1200		

10	An.96	Tabele sinjalistike 60-90cm	cope	5	
		SHUMA E			
		SHUMA A+ E			
		TVSH 20%			
		TVSH TOTALE			

Preventivues:

Ing. Hajredin MURGU



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I.-se
Ing. Flora MUÇA



MIRATOI
Rakip SULI

KRYETAR

