



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Rikualifikimi I Rrugës "Azem Hajdari"

(L = 1300 ml, B = 9m, basf = 5m, 2x0.5kunete, 2x1.5mtrotuar,)

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	650		
	Man 3					
2	An. 8	Mbushje me çakell shkembor	m ³	975		
3	3.212/b	Shtrese stabilizanti t=10cm	m ²	6500		
4	3.222/2	Shtrese binderi 1x6 cm	m ²	6500		
5	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	6500		
6	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	494		
7	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	31.2		
8	An.	Ngritje pusete+kapak gize	cope	20		
9	An.	Spostim shtyllash	cope	5		
10	An.152	Vizime me boje bikomponente 15cm	ml	2750		
11	An.96	Tabele sinjalistike 60-90cm	cope	10		
		SHUMA I				
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	910		
2	3.158/5a	Transport çakelli me auto 5km	m ³	910		
	Man 3					
3	An. 8	Mbushje me çakell shkembor	m ³	675		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	2548		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	127		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	86		
		SHUMA II				
III	PUNIME TROTUARE(2*1.5 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	195		
2	3.158/5a	Transport dheu me auto 5km	m ³	195		
3	An. 8	Mbushje me çakell shkembor	m ³	390		
4	3.208	Shtrese çakelli T=10cm	m ²	2990		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	2990		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	2600		
7	2/262/4	Beton per fiksim bordure C16/20	m ³	78		
8	3.605	Shtrese pllake t=6cm mbi shtrese betoni	m ²	2672		
		SHUMA III				
IV	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	2600		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	2600		

3	3.an/1sh	F.V. Shtylla metalike konike ndriçimi H-9m PAICC-3	cope	37	
4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	37	
5	3.an	F.V Ndricules Smart VP CLI CR M-S 250W GG FAE44	cope	37	
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=7	cope	37	
7	An	F.V Elektroda tokezim komplet l=150m	cope	37	
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	2600	
9	An	F.V kabell tokezimi 1x3.5mmk	ml	59	
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	2	
11	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	37	
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	2	
13	An.	F.V kuader komandimi per ndriçim rrugor	cope	2	
14	An.	F.V kasete shperndarese	cope	2	
15	3.139	Germime dheu me ekskavator me goma	m ³	260	
16	3.158/5a	Transport dheu me auto 5km	m ³	260	
17	2.261	Mbushje me rere	m ³	78	
18	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	182	
SHUMA IV					
SHUMA A					
TVSH 20%					
TVSH TOTALE					

Preventivues:

Ing. Eglantina Disha



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se

Ing. Flora MUÇA



**MIRATOI
Rakip-SULI**

KRYETAR

