



MIRATOHET

KRYETAR  
BENET BECI

BASHKIA SHKODER

PREVENTIV I PUNIMEVE

Objekti: Rikualifikim urban blloqe pallatesh "Isuf Sokoli"

Nr	Analiza	Emertimi i zerit te punes	Njesia	Sasia	Çmimi	Vlera
		<b>Kap I. Shtresa rrugore</b>				
1	2.426/3	Prishje shtresa betoni ( Bordura, trotuar, pusetat, shtresa betoni hyrese , rrugore etj)	m3	20		
2	3.89/b	Germim kanali me eskavator me gom 0.25m3, ne kanale me gjeresi >2m. Shkarkim ne mjet	m3	1200		
3	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1220		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri (nenshtrese per trotuarin me pllaka)	m2	930		
5	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri (nenshtrese per sheshin me pllaka)		1750		
6	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri (nenshtrese per asfaltin)	m2	1210		
7	3.212/c	Shtrese stabilizant t=10cm	m2	1210		
8	3.229/1	Shtrese binderi me zall lavatrice t=5cm me makineri	m2	1210		
9	3.233/1	Shtrese asfaltobetoni, me zall lavatrice, t=4 cm, me makineri	m2	1210		
10	An 1	F.V. Pllake betoni e presuar per trotuar	m2	2680		
11	2.261	Shtrese rere t= 4cm	m3	108		
12	3.243	Strukture monolite betoni C 16/20(per sheshin dhe trotuarin me pllaka) t = 10cm	m3	268		
13	3.183/a	Shtrese zhavori t=10cm (per sheshin dhe trotuarin me pllaka)	m2	2680		
14	3.617	Fv bordura betoni 15*25cm	ml	770		
15	3.616	Fv bordura betoni 12*25cm (per lulishte)	ml	640		
16	2.262/3	Shtrese betoni C12/15 t=10cm per fiksimin dhe hapsirat mbas bordurave) e bordurave	m3	30		
17	2.166	F.V. Hekur betoni periodik Ø 8mm	ton	7.2		
					<b>SHUMA I</b>	

PREVENTIVI I PUNIMEVE : Rikualifikim Urban blloqe pallatesh " Isuf Sokoli"

<b>Kap II. Ujesjellesi</b>					
1	3.89/a	Germim kanali me eskavator me gom 0.25m3, ne kanale me gjeresi<2m. Shkarkim ne mjet	m3	180	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	180	
3	2.491/g	F.V Tuba e rakorderi ujesjellesi PE d=90mm, t = 6.7 mm, PN 10	ml	290	
4	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm, t =3.7 mm, PN 10	ml	155	
5	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	80	
6	3.379	Ndertim drenazhi,mbushje me rere natyrore	m3	48	
7	2.258	Nenshtrese zhavori per kanale	m3	86	
8	An 2	F.v saricineske d=90 Pn 10Standart EN 1074;En 1171	cope	16	
9	An 3	Pusete kontrolli 1x1x1 m b/a 20/25,kapak gize	cope	16	
10	An 4	Lidhje me rrjetin ekzistues	cope	3	
					<b>SHUMA II</b>
<b>Kap III.Linja e KUZ</b>					
1	3.89/a	Germim kanali me eskavator me gom 0.25m3, ne kanale me gjeresi<2m. Shkarkim ne mjet	m3	490	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	490	
3	3.379	Ndertim drenazhi,mbushje me rere natyrore	m3	60	
4	2.258	Nenshtrese zhavori per kanale	m3	230	
5	3.An/1t	Fv Tub I brinjezuar HDPE SN8 Dj315mm	ml	390	
6	2.575	Pusete kontrolli 1x1x1.5m	cope	24	
7	An 5	Fv Tub I brinjezuar HDPE SN8 Dj200mm	ml	80	
8	An 6	Ringritje pusete dhe kapak gize	cope	3	
9	An 4	Lidhje me rrjetin ekzistues	cope	3	
					<b>SHUMA III</b>
<b>Kap IV. Linja e KUB</b>					
1	3.89/a	Germim kanali me eskavator me gom 0.25m3, ne kanale me gjeresi<2m. Shkarkim ne mjet	m3	295	
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	295	
3	3.An/1t	Fv Tub I brinjezuar HDPE SN8 Dj315mm	ml	270	
4	An	Fv Tub I brinjezuar HDPE SN8 Dj250mm	ml	240	
5	3.379	Ndertim drenazhi,mbushje me rere natyrore	m3	65	
6	2.258	Nenshtrese zhavori per kanale	m3	85	
7	An-23	Puseta b/a shiu 40*60cm me kapak zgare gize	cope	43	
8	An	F V Kunete betoni parafabrikat	ml	550	
9	3.183/a	Shtrese zhavori t=10cm	m2	220	
10	An 4	Lidhje me rrjetin ekzistues	cope	4	
					<b>SHUMA IV</b>

PREVENTIVI I PUNIMEVE : Rikualifikim Urban blloqe pallatesh " Isuf Sokoli"

		<b>Kap V. Ndriçimi dhe linja per fibra optike</b>				
1	3. An/53	FV shtylla metalike per ndricim, H=7m	cope	27		
2	An/E1	FV ndricues rrugor Led ,4800lm, 4000 K	cope	27		
3	3.An/ksh	F.V. krah shtylla metalike KRH - MSI 1500/1500/10	cope	27		
4	An/E4	F V pusete elektrike kontrolli betoni 30x30x30cm	cope	66		
5	An/E5	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	27		
6	An/E6	F V kuader komandimi komplet me santeri+fotoelement	cope	3		
7	An/E7	F.V. Kabell XYMM 0.6/ 1KV. 3x1.5mm <sup>2</sup>	ml	190		
8	An/E8	F.V. Kabell FG7OR 0.6/ 1KV. 4x 6mm <sup>2</sup>	ml	580		
9	3.654/1	Furnizim, vendosje tuba plastmasi ø 80 (per ndricim dhe linjen e fibrave optike)	ml	1,010		
10	3.379	Ndertim drenazhi,mbushje me rere natyrore	m <sup>3</sup>	46		
11	An/E9	F.V. percjelles CU te veshur per tokezmin	ml	40		
12	An/E10	F.V. Tuba metalik D=110mm	ml	60		
13	3.243	Stukture monolite betoni C 16/20 (per fiksime shtylle)	m <sup>3</sup>	5		
					<b>SHUMA V</b>	
		<b>Kap VI. Gjelberimi</b>				
1	An164	F.V. Fidane Peme dekorative (Liquidambar d=6-8 cm)	cope	100		
2	An165	F.V. Fidane shkurre dekorative dekorative	cope	15		
3	An/L1	Mbjellje bari	m <sup>2</sup>	700		
4	An L/9	Dhë vegjetal t=30cm	m <sup>3</sup>	230		
5	An/L2	F.V Stol dru-metal L=3m	cope	11		
6	An/L3	F.V Stol dru-metal L=2m	cope	11		
7	An/L4	F.V. Kosha mbeturinash	cope	10		
					<b>SHUMA VI</b>	
		<b>Kap VII. Sinjalistika</b>				
1	An 151	Vizime me boje bikomponente	m <sup>2</sup>	140		
2	An 158	FV tabela te ndryshme rrugore D=60cm	cope	10		
					<b>SHUMA VII</b>	

PREVENTIVI I PUNIMEVE : Rikualifikim Urban blloqe pallatesh " Isuf Sokoli"

		<b>Kap VIII. Punime ne fasada</b>				
1	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m <sup>2</sup>	3810		
2	2.308/a	Suvatim me grafiato h > 4 m (të imët 0.6-1.0mm)	m <sup>2</sup>	13,260		
3	2.404/1	Boje hidroplastike importi cilesi e I-re	m <sup>2</sup>	13,260		
4	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø100 mm	ml	748		
5	2.203	Veshje kornize llamarine xingat	m <sup>2</sup>	312		
6	2. a-122	Kanaline metalike 210x65mm	ml	813		
					<b>SHUMA VIII</b>	
		<b>SHUMA I+II+III+IV+V+VI+VII+VIII</b>				
		<b>FONDI REZERVE 3%</b>				
		<b>SHUMA PA TVSH</b>				
		<b>TVSH 20%</b>				
		<b>TOTALI</b>				

Shenim: Çmimet e perdorura jane sipas manualit te MPPT miratuar me VKM Nr.629, date 15.07.2015, dhe analiza çmimesh

**Preventivues**  
**"LENI-ING"sh.p.k.**  
**ING. NIKOLL PALUCA**