



REPUBLIKA E SHQIPERISE

BASHKIA KAMEZ

PREVENTIV

OBJEKTI : Ndertim Blloku Pakuqan I "Josif Mihali + Rrugicat Jusuf Gervalla+Llazo Palluqi+Llambro Andoni+Memo Meta " Ltot=1459 ml

OBJEKTI : Ndertim Rruga "Josif MIHALI + Rrugicat Jusuf Gervalla " Paskuqan 1 , Bashkia Kamez

L=654 m , B= 6 m , Asfalt = 4.5 m , kunete 1x0.5 m , trotuare 1x1 m

L=

654

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	441.45		
2	3.158/5a	Transport dheu me auto 5km	m ³	441.45		
3	An. 8	Mbushje me çakell shkembor	m ³	147.15		
4	3.211	Shtrese çakelli T=20cm	m ²	2943		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2943		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	2943		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	2943		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	196.20		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.91		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	5		
11	An.	Spostim shtyllash	cope	12.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	392.4		
13	An.152	Vizime me boje bikomponente 15cm	ml	1635		
14	An.96	Tabele sinjalistike 60-90cm	cope	8		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	313.92		
2	3.158/5a	Transport çakelli me auto 5km	m ³	313.92		
3	3 An. 8	Mbushje me çakell shkembor	m ³	156.96		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	785		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	32.7		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	22.00		
SHUMA II						
III PUNIME TROTUARE(1x0.75 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	83.385		
2	3.158/5a	Transport dheu me auto 5km	m ³	83.385		
3	3 An. 8	Mbushje me çakell shkembor	m ³	111.18		
4	3.208	Shtrese çakelli T=10cm	m ²	555.9		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	555.9		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1308		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	39.24		
8	2.109/2	Shtrese betoni trotuari	m ³	55.59		
SHUMA III						
II PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	261.6		
2	3.158/5a	Transport çakelli me auto 5km	m ³	261.6		
3	3 An. 8	Mbushje me çakell shkembor	m ³	130.8		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	654		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	10.00		
SHUMA II						
6. PUNIME VEPRARTI (MURE MBAJTESE)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	131		

2'	3.158/5a	Transport dheu me auto deri 5.0 km	m3	131	
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m3	164	
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	1.64	
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	3.3	
		SHUMA 6	ton		
IV		PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	654	
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	654	
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	19	
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1	
5	3.139	Germime dheu me ekskavator me goma	m³	98.1	
6	3.158/5a	Transport dheu me auto 5km	m³	98.1	
7	2.261	Mbushje me rere	m³	13.08	
8	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m³	85.02	
		SHUMA IV			
		SHUMA A			

OBJEKTI : Ndertim Rruga "Llazo Palluçi " Paskuqan 1 , Bashkia Kamez

L=168m , B=4.5 m , Asfalt = 4.0 m , kunete 2x0.5 m ,

L= 168

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m³	168		
2	3.158/5a	Transport dheu me auto 5km	m³	168		
3	An. 8	Mbushje me çakell shkembor	m³	84		
4	3.211	Shtrese çakelli T=20cm	m²	672		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	672		
6	3.222/2	Shtrese binderi 1x6 cm	m²	672		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m²	672		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m³	63.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.58		
10	An.	Ngritje pusete+kapak gize+ pastrim me makineri	cope	4		
11	An.	Spostim shtyllash	cope	4.20		
12	2/426/2	Prishje mure me blloqe + transport	m³	100.8		
13	An.152	Vizime me boje bikomponente 15cm	ml	420		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
		SHUMA I				
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m³	67.2		
2	3.158/5a	Transport çakelli me auto 5km	m³	67.2		
3	3 An. 8	Mbushje me çakell shkembor	m³	33.6		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	168		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m³	16.8		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.00		
		SHUMA II				
II		PUNIME NE KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m³	67.2		
2	3.158/5a	Transport çakelli me auto 5km	m³	67.2		
3	3 An. 8	Mbushje me çakell shkembor	m³	33.6		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	168		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	12.00		
		SHUMA II				
		SHUMA A				

OBJEKTI : Ndertim Rruga "Llambro Andoni " Paskuqan 1 , Bashkia Kamez

L=181 m , B= 5 m , Asfalt = 4.5 m , kunete 1x0.5 m ,

L= 181

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		

1	3.139	Germim dheu me eskavator	m ³	181		
2	3.158/5a	Transport dheu me auto 5km	m ³	181		
3	An. 8	Mbushje me çakell shkembor	m ³	84		
4	3.211	Shtrese çakelli T=20cm	m ²	814.5		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	814.5		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	814.5		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	814.5		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	67.88		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.70		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	4		
11	An.	Spostim shtyllash	cope	4.53		
12	2/426/2	Prishje mure me blloqe + transport	m ³	108.6		
13	An.152	Vizime me boje bikomponente 15cm	ml	543		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	72.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	72.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	36.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	181		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	9.05		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.17		
			SHUMA II			
			SHUMA A			

OBJEKTI : Nderim Rruga " MEMO METO "Paskuqan 1 , Bashkia Kamez

L=456 m , B= 6.3 m , Asfalt = 4.5 m , kunete 1x0.5 m , trotuare 1x1.2 m

L= 456

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	410.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	410.4		
3	An. 8	Mbushje me çakell shkembor	m ³	182.4		
4	3.211	Shtrese çakelli T=20cm	m ²	1824		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1824		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1824		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1824		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	171.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.28		
10	An.	Ngritje pusete+kapak gize+pastrim me makineri	cope	7		
11	An.	Spostim shtyllash	cope	11.40		
12	2/426/2	Prishje mure me blloqe + transport	m ³	273.6		
13	An.152	Vizime me boje bikomponente 15cm	ml	1368		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	182.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	182.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	91.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	456		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	45.6		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	13.03		
			SHUMA II			
II		PUNIME KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	296.4		
2	3.158/5a	Transport çakelli me auto 5km	m ³	296.4		
3	3 An. 8	Mbushje me çakell shkembor	m ³	148.2		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	456		

5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	10.00		
SHUMA II						
III PUNIME TROTUARE(1x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	45.60		
2	3.158/5a	Transport dheu me auto 5km	m ³	45.60		
3	3 An. 8	Mbushje me çakell shkembor	m ³	68.40		
4	3.208	Shtrese çakelli T=10cm	m ²	456.0		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	456.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	912		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	27.36		
8	2.109/2	Shtrese betoni trotuari	m ³	45.6		
SHUMA III						
6. PUNIME VEPRRA ARTI (MURE MBAJTESE)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	91		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	91		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	225		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	2.25		
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	4.5		
SHUMA 6						
IV PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	456		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	456		
3	3.an/1sh	F.V. Shtylla metalike konike ndricimi H-9m PAICC-3	cope	13		
4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	13		
5	An	F.V Ndricues Led 94W	cope	13		
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen	cope	13		
7	An	F.V Elektroda tokezim komplet l=150m	cope	13		
8	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	478		
9	An	F.V kabell tokezimi 1x3.5mmk	ml	20		
10	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	1		
11	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	13		
12	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	4		
13	An.	F.V kuader komandimi per ndricim rrugor	cope	1		
14	An.	F.V kasete shperndarese	cope	1		
15	3.139	Germime dheu me ekskavator me goma	m ³	91.2		
16	3.158/5a	Transport dheu me auto 5km	m ³	91.2		
17	2.261	Mbushje me rere	m ³	36.48		
18	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	54.72		
SHUMA IV						
V PUNIME PER GJELBERIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	0		
SHUMA V						
SHUMA A						
Shuma A+B+C+D						
Tvsh 20 %						
TVSH TOTALE						

V.O. Preventivi eshte hartuar ne baze te vkm nr 629 date 15.07.2015

Preventivues:

Ing. Hajredin MURGU



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se
Ing. Flora MUÇA

**MIRATOI
Rakip SULI**

KRYETAR