



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Rruget Bathore 3+4 , L= 1900 ml , Bashkia Kamez

Rruget Blloku Bathore 3 +4 deri tek Rruga Ibrahim Basha , Rruga Shupenze
l=300 m + Rruga Padre Mateo Rici l = 200 ml , Rruga Tomibn+ Rruga Sher
pali II + Rruga Pingul me rrugen Skavice + 2 Rruge Paralele me Rrugen
Skavice + Rruga Paralel me Rrugen Arbrit etj L= 1900 , B= 4 , basfalt =
3.5 + bankine 2x0.25 m

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
1	3.139	Germim dheu me eskavator.	m ³	1520		
2	3.158/5a	Transport dheu me auto 5km	m ³	1520		
3	An. 8	Mbushje me çakell shkembor	m ³	665		
4	3.212	Shtrese çakelli t=10/15cm, makadam, perhapur e ngjeshur makineri	m ²	6650		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	6650		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	6650		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	6650		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	106.88		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	3.21		
10	An.	Ngritje pusete+kapak gize	cope	29		
11	An.	Spostim shtyllash	cope	16.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	114		
13	An.152	Vizime me boje bikomponente 15cm	ml	3800		
14	An.96	Tabele sinjalistike 60-90cm	cope	16		
		SHUMA A				
		TVSH 20%				
		TVSH TOTALE				

V.O. Çmimet jane vendosur ne baze te vkm nr 629 date 15.07.2015

Preventivues:

Ing. Hajredin MURGU

Drejtori i Pergjithshem

Z.Elvis Gjika

Drejtori P.I-se

Ing. Flora MUÇA

MIRATOI

Rakip SULI

KRYETAR

