

**PREVENTIV**

**OBJEKTI: NDERTIM PRITA PER MBROJTJE NGA LUMI DEVOLL**

Nr.	Shenja Manualit	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Shuma
<b>I. NDERTIM PRITA LUMORE</b>						
1	3.101.b	Germim themeli me makineri 0.5m <sup>3</sup> B>2M shkarkim ne toke	m <sup>3</sup>	6600		
2	3.331	Gabiona rrjet xingato 1x1x1	m <sup>3</sup>	4000		
3	3.332	Gabiona rrjet xingato 1x1x1.5	m <sup>3</sup>	3200		
4	3.333	Gabiona rrjet xingato 1x1x2	m <sup>3</sup>	2100		
5	1.262/4	Shtrese betoni C-16/20 t=15cm	m <sup>3</sup>	345		
<b>SHUMA I</b>						
<b>II.SISTEMIMI I PERRENJEVE</b>						
1	3.101/b	Germim makineri 0.5m <sup>3</sup> b>2	m <sup>3</sup>	3800		
2	1.262/4	Shtrese betoni C-16/20 t=15cm	m <sup>3</sup>	445		
<b>SHUMA II</b>						
<b>III.MBJELLJE PEMESH RRAPI</b>						
1	3.101/b	Germim gropa makineri	m <sup>3</sup>	360		
2	3.966	Mbjellje peme Rrapi (16 - 18)cm, h>2.5m	cope	360		
<b>SHUMA III</b>						
<b>SHUMA I+II+III pa tvsh</b>						<b>0</b>
<b>T.V.SH</b>				<b>20%</b>		<b>0</b>
<b>SHUMA TOTAL</b>						<b>0</b>

**Shenim:** Ky preventiv eshte hartuar mbi bazen e cmimeve te manualit teknik te preventivimit te marre nga e-albania.