



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**  
**PREVENTIV**

**OBJEKTI : Ndertim Blloku Rruget Babrru Koder e Kuqe 2 "**

**OBJEKTI : Ndertim Rruga "Xhemali Dervishi " Fushe Kercik , Bashkia Kamez**

**L=238 m , B= 7 m , Asphalt = 4 m , kunete 1x0.5 m , trotuar 1+1.5**

**L= 238**

<b>A</b>	<b>An.</b>	<b>Emertimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
<b>I</b>	<b>PUNIME NE RRUGE</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	95.2		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	95.2		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	95.2		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	952		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	952		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	952		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	952		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m <sup>3</sup>	99.96		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	2		
11	.426/2	Prishje mur blloqe betoni	m <sup>3</sup>	95.2		
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vijejzime kembesoret	ml	476		
13	3.934/1	Tabele sinjalistike 60cm	cope	4		
		<b>SHUMA I</b>				
<b>II</b>	<b>PUNIME NE KUB</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	95.2		
2	3.158/5a	Transport çakelli me auto 5km	m <sup>3</sup>	95.2		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	47.6		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	233		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	11.42		
6	2.342	Puseta shiu me zgare 40x60 + kapak gize	cope	8		
		<b>SHUMA II</b>				
<b>III</b>	<b>PUNIME KUN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	130.9		
2	3.158/5a	Transport çakelli me auto 5km	m <sup>3</sup>	130.9		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	65.45		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	234		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
		<b>SHUMA III</b>				
<b>IV</b>	<b>PUNIME TROTUARE( 1 dhe 1.5 m)</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	59.5		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	59.5		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	59.56		
4	3.208	Shtrese çakelli T=10cm	m <sup>2</sup>	406.98		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m <sup>2</sup>	406.98		
6	3.616/a	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	476		
7	2/262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	14.28		
8	3.241	Shtrese betoni trotuari	m <sup>3</sup>	40.698		
		<b>SHUMA IV</b>				
<b>IV</b>	<b>PUNIME PER NDRICIMIN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>

1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	238		
2	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	6		
3	3.139	Germime dheu me ekskavator me goma	m³	47.6		
4	3.158/5a	Transport dheu me auto 5km	m³	47.6		
5	2.261	Mbushje me rere	m³	19.04		
6	3.353	Mbushje me shkemb te germuar me pare	m³	28.56		
		<b>SHUMA IV</b>				
		<b>SHUMA A</b>				

**OBJEKTI : Ndertim Pingul me Rruga "Xhemali Dervishi " Fushe Kercik**

**L= 165 m , Asphalt = 4 m +bankine**

**L= 165**

<b>B</b>	<b>An.</b>	<b>Emertimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
<b>I</b>	<b>PUNIME NE RRUGE</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m³	66		
2	3.158/5a	Transport dheu me auto 5km	m³	66		
3	3.164/1b	Mbushje me çakell shkembor+ bankine	m³	82.5		
4	3.211	Shtrese çakelli T=20cm	m²	660		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	660		
6	3.222/1	Shtrese binderi 1x5 cm	m²	660		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m²	660		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m³	49.50		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.24		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	2		
11	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	380		
12	3.934/1	Tabele sinjalistike 60cm	cope	2		
		<b>SHUMA I</b>				

<b>III</b>	<b>PUNIME NE KUN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m³	66		
2	3.158/5a	Transport çakelli me auto 5km	m³	66		
3	3.164/1b	Mbushje me çakell shkembor	m³	33		
4	3.164/1t	F.V. Tuba I brinjzuar Ø 315	ml	161		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
		<b>SHUMA II</b>				
		<b>SHUMA B</b>				

**OBJEKTI : Ndertim Rruga "Pashko Vasa", " Babrru Koder e Kuqe , Bashkia Kamez L=530 m , + shkalle B=6m , (basf= 4.5 ml+ 1x0.5 kunet+ trotuare 1x1m**

<b>C</b>	<b>L= 530</b>					
<b>An.</b>	<b>Emertimi i Punimeve</b>		<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
<b>I</b>	<b>PUNIME NE RRUGE</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m³	212		
2	3.158/5a	Transport dheu me auto 5km	m³	212		
3	An. 8	Mbushje me çakell shkembor	m³	238.5		
4	3.211	Shtrese çakelli T=20cm	m²	2385		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	2385		
6	3.222/1	Shtrese binderi 1x5 cm	m²	2385		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m²	2385		
8	2.207	Mur betoni C 16/20 + shkallet	m³	170		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	4.25		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	6		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	5		
12	.426/2	Prishje mur blloqe betoni	m³	75		
13	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	1160		
14	3.934/1	Tabele sinjalistike 60cm	cope	6		
		<b>SHUMA I</b>				

II		PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	212			
2	3.158/5a	Transport çakelli me auto 5km	m <sup>3</sup>	212			
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	106			
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	521			
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	26.5			
6	2.342	Puseta shiu me zgare 40x60 + kapak gize	cope	15			
			<b>SHUMA II</b>				
III		PUNIME TROTUARE( 1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	53			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	53			
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	79.50			
4	3.208	Shtrese çakelli T=10cm	m <sup>2</sup>	345			
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m <sup>2</sup>	345			
6	3.616/a	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1060			
7	2/262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	31.8			
8	3.241	Shtrese betoni trotuari	m <sup>3</sup>	34.45			
			<b>SHUMA III</b>				
V		PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	530			
2	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	13			
3	3.139	Germime dheu me ekskavator me goma	m <sup>3</sup>	106			
4	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	42.4			
5	2.261	Mbushje me rere	m <sup>3</sup>	42.4			
6	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	63.6			
			<b>SHUMA V</b>				
			<b>SHUMA C</b>				
			<b>SHUMA A-C</b>				
			<b>TVSH 20%</b>				
			<b>TVSH TOTALE</b>				

shenim : preventivi eshte hartuar ne baze te vkm 216 date 13.04.2023

PREVENTIVUES :  
Ing. Hajredin Murgu

Drejtoresha Projekteve dhe Investimeve  
Ing. Flora MUÇA

*b*

*[Signature]*

**MIRATOI**  
**Rakip SULI**  
**KRYETAR**

BASHKIA KAMEZ