

## PREVENTIV I PUNIMEVE

**OBJEKTI : Asfaltimi I rrugës Funarës-Zdrajsh (Loti 3, Njesia administrative Orenjë, Bashkia Librazhd)**

**Investitori: Bashkia Librazhd**

Nr	NºAn	Pershkrimi i punimeve	Njesia	Sasia
<b>I Punime prishje Shpyllezimi</b>				
1	2.426/2	Prishje mure betoni	m <sup>3</sup>	6.75
2	3.30	Prerje e sistemim pemesh ø 10 - 20 cm	Cope	120
3	2.37/5a	Transport mbeturinash auto - 5km(pemet)	m <sup>3</sup>	16
<b>SHUMA I</b>				
<b>II PUNIME DHERASH NE RRUGE</b>				
1	3.124/2a	Germim shkemb i forte me çekiç me ekskavator me zinxhir 3	m <sup>3</sup>	1,373
2	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m <sup>3</sup> , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m <sup>3</sup>	4,867
3	3.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m <sup>3</sup>	158
4	3.158/5a	Transport dheu me auto deri 5.0 km	m <sup>3</sup>	6,082
<b>SHUMA II</b>				
<b>III PUNIME SHITRESASH NE RRUGE</b>				
1	3.617	F.V bordure betoni 15x25	ml	1,840
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	10,450
3	3.21	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m <sup>2</sup>	10,450
4	3.212/b	Shtrese stabilizanti 10 cm	m <sup>2</sup>	11,550
5	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m <sup>2</sup>	7,700
6	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m <sup>2</sup>	7,700
7	3.243	Betonim kunete monolite C 16/20	m <sup>3</sup>	152
<b>SHUMA III</b>				
<b>IV PUNIME VEPRRA ARTI</b>				
1	2.258	Nenshtrese zhavori	m <sup>3</sup>	317
2	2.519	Tub Ø90 mm per kullimin e ujrave ne mure	ml	258
3	3.353	Mbushje me material shkembor (pas mureve)	m <sup>3</sup>	259
4	3.244	Struktura monilite betoni C20/25 (portali ,puseta e tombinos)	m <sup>3</sup>	38
5	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni	ml	18
6	3.365	Tombino me tuba betoni Ø600, mbi shtrese betoni	ml	6
7	3.366	Tombino me tuba betoni Ø800, mbi shtrese betoni	ml	6
8	3.367	Tombino me tuba betoni Ø1000, mbi shtrese betoni	ml	6
9	3.243	Struktura monolite betoni C 16/20(muret prites)	m <sup>3</sup>	364
10	2.166/1a	F V hekur betoni periodik Ø > 12 mm(muret e tombinos)	ton	1.6
11	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1m	m <sup>3</sup>	105
12	3.332	Gabiona me rrjete teli te zinguar e gure kave 1x1x1.5m	m <sup>3</sup>	61
<b>SHUMA IV</b>				
<b>V PUNIME TE NDRYSHME + SINJALISTIKA</b>				
1	3.942	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm Bikomponente	ml	4,400
2	3.185	Guardrail- N2 anesore me 2 valezim ne 1 ane,W4+ aksesore	ml	50
3	3.955	FV tabela te ndryshme rrugore D=60cm	cope	2
4	3.936	Tabela trekendore e vogel me A = 60	cope	12
<b>SHUMA V</b>				
<b>SHUMA I - V</b>				
<b>Fondi Rezerve 5%</b>				
<b>SHUMA</b>				
<b>T.V.SH= 20%</b>				
<b>SHUMA TOTALE</b>				