

Projektuesi: Bashkia Kucove

Objekti: Rikualifikim i rruges Niko Hoxha

Datë: 02-07-2024

PREVENTIV

NR	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA	ÇMIMI	VLEFTA
		1. PUNIME GERMIMI				
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	132.0		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	227.0		
		Shuma 1:				
		2. PUNIME SHITESASH				
3	3.182/a	Shtrese rere natyrore t=10cm	m ²	132.0		
4	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m ²	3154.0		
5	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m ²	320.0		
6	3.212/b	Shtrese stabilizant t=10cm	m ²	3154.0		
		Shuma 2:				
		3. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA				
7	3.164/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	330.0		
8	3.169	F V shtylla metalike per ndriçim, H=7m, d=160mm	copë	13.0		
9	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	13.0		
10	3.175	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	copë	13.0		
11	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	13.0		
		Shuma 3:				

		4. UJESJELLES E KANALIZIM I JASHTEM				
12	2.338	Pusete shiu 40 x 40, h = 100 cm, me kapak zgare hekuri	copë	12.0		
		Shuma 4:				
		5. LINJA T/L GERMIMI I GROPAVE TE SHTYLLAVE				
13	3.497	Germim dheu per gropa shtyllash T/L, ne toke te bute kat I II, ~1.5 m, sip tabani 1.5m ²	m ³	6.0		
		Shuma 5:				
		6. PUNIME SHITRESASH 2				
14	2.262	Shtrese betoni C 6/10	m ³	19.0		
15	2.262/5	Shtrese betoni C20/25	m ³	17.0		
		Shuma 6:				
		7. INSTALIME PER NDRICIM				
16	2.496	F.V. Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	copë	13.0		
17	2.481/4	F.V percjelles PV-500 Ø 6 mm ²	ml	1320.0		
		Shuma 7:				
		8. PUNIME TE NDRYSHME				
18	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	m	330.0		
19	3.617	FV Bordura betoni 15x35 cm	m	330.0		
		Shuma 8:				
		9. NENSHTRESA DHE SHITRESA NE TERRITORIN E NDERTESAVE				
20	2.288	Trotuar me pllaka, pa borduren e betonit	m ²	495.0		
		Shuma 9:				
		10. B. SINJALET HORIZONTALE				
21	3.942	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	710.0		
		Shuma 10:				
		11. PUNIME BETONI DHE B/A				
22	2.202	Themel e xokol butobetoni C16/20	m ³	163.0		

23	2.112	Mure buto betoni C 12/15	m3	399.0		
		Shuma 11:				
		12. ANALIZA TEKNIKE				
24	3.233/4	Shtrese asfaltbetoni me zall lavatrice, 7cm, me makineri	m2	3154.0		
		Shuma 12:				
		13. PUNIME BETONI E BETONARMEJE				
25	3.247	Struktura monolite betoni me çakell C 25/30	m3	164.0		
		Shuma 13:				
		14. PUNIME HEKUR BETONI				
26	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.0		
27	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	10.0		
		Shuma 14:				
Shuma Analiza						27,109,562.00
Fondi Rezervë (0.0%)						0.00
Shuma Analiza + Fondi Rezervë (0.0%)						27,109,562.00
TVSH (20%)						5,421,912.50
Shuma me TVSH						32,531,474.50
Totali						32,531,474.00

Preventivuesi:

Shënime: