

# PREVENTIV

**OBJEKTI : Zgjerimi i kupes se rezervuarit Helshan 2**  
**Vendodhja : Helshan, Has**  
**Porositesi : Bashkia Has**

NR	NR/AN	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
<b>PUNIME NDERTIMORE</b>						
1	3.104/b	Germim dheu me eskavator shkarkim ne automjet.	m <sup>3</sup>	42100		
2	3.104/a	Germim dheu me eskavator per kanalin ushqyes	m <sup>3</sup>	467		
3	3.158/1	Transport dheu me mjete deri 1 km	m <sup>3</sup>	42100		
4	3.161/1	Rrafshim skrapate dige me eskavatore	m <sup>2</sup>	4230		
5	3.164	Rrafshim e ngjeshje dheu ne dige	m <sup>3</sup>	42100		
6	3.244/1	b/a per shkarkuesin katastrofik	m <sup>3</sup>	148.0		
7	3.377	Ndertim drenazhi, mbushje me gure lumi	m <sup>3</sup>	258.0		
8	3.376	Gure kave 20cm per veshjen e bieftit te siperm	m <sup>3</sup>	150.0		
9	1.39/p	Parapet b/a parafabrikat	m <sup>3</sup>	74.0		
10	3.25/c	Germim me krahe per kanalin vadites seksion detyruar me gjeresi , h=1.5 m	m <sup>3</sup>	570.0		
11	2.262/3	Veshje me beton kanali U1+U2+U3 C12/15	m <sup>3</sup>	110.0		
12	2.575	Puse kontrolli 1x1x1.5m	cope	2.0		
13	3.244/1	Punime Betoni e Betonarmeje - B/a per bazamentin e pompes	m <sup>3</sup>	8.0		
14	3.244/1	Punime Betoni e Betonarmeje - B/a per diafragmen	m <sup>3</sup>	2.8		
15	4.74	F.V tub celiku ne ujeleshues	ton	1.2		
16	4.122/7	F.V Saracineske fi 200	cope	1.0		
17	An	F.V Pompe uji fuqi 20 kw + instalime elektrike	cope	1.0		
<b>SHUMA A-Z</b>						-
<b>T.V.SH</b>						-
<b>SHUMA I</b>						-