



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI: Ndertim Rruget Blloku 3 Bathore 7

OBJEKTI : Ndertim Rruga "Lucie Miloti" Bathore7

(L =217ml, basf= 4m)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86.8		
2	3.158/5a	Transport dheu me auto 5km	m ³	86.8		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	86.8		
4	3.211	Shtrese çakelli T=20cm	m ²	868		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	868		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	868		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	868		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	484		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	3		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Lek Dukagjini" Bathore7

(L =220ml, B=5ml, basf= 4m,+0.5mkub bankine ne dy anet, KUB -D=315mm)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	88		
2	3.158/5a	Transport dheu me auto 5km	m ³	88		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	88		
4	3.211	Shtrese çakelli T=20cm	m ²	880		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	880		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	880		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	880		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	490		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

**II
PUNIME NE KUB**

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	211.2		
2	3.158/5a	Transport dheu me auto 5km	m ³	211.2		
3	3.396	Mbushje me cakell pas mureve	m ³	180		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	217		
5	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	9		
SHUMA III						
SHUMA I-II						

OBJEKTI : Ndertim Rruga "Peqini" Bathore7

(L =220ml, basf= 4m, KUZ -D=315mm)

I PUNIME NE RRUGE						
----------------------	--	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	88		
2	3.158/5a	Transport dheu me auto 5km	m ³	88		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	88		
4	3.211	Shtrese çakelli T=20cm	m ²	880		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	880		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	880		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	880		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	490		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		

SHUMA I

III	PUNIME NE KUZ					
-----	---------------	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	264		
2	3.158/5a	Transport dheu me auto 5km	m ³	264		
3	3.396	Mbushje me cakell pas mureve	m ³	236		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	217		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
		SHUMA III				
		SHUMA I-III				

OBJEKTI : Ndertim Rruga "Marie Logoreci" Bathore7

(L =290ml, basf= 4m,KUZ -D=315mm)

I	PUNIME NE RRUGE					
---	-----------------	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	116		
2	3.158/5a	Transport dheu me auto 5km	m ³	116		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	116		
4	3.211	Shtrese çakelli T=20cm	m ²	1160		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1160		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	1160		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	1160		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	630		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		

SHUMA I

II	PUNIME NE KUZ					
----	---------------	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	278.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	278.4		
3	3.396	Mbushje me cakell pas mureve	m ³	247		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	284		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	6		
		SHUMA II				
		SHUMA I-II				

OBJEKTI : Ndertim Rruga "Paralel me Peqinin" Bathore7

(L =150ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)

I	PUNIME NE RRUGE					
---	-----------------	--	--	--	--	--

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
-----	-------	-----------------------	--------	-------	-------	-------

1	3.139	Germim dheu me eskavator	m ³	60		
2	3.158/5a	Transport dheu me auto 5km	m ³	60		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	60		
4	3.211	Shtrese çakelli T=20cm	m ²	600		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	600		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	600		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	600		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	350		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						
II						
PUNIME NE KUZ						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	144		
2	3.158/5a	Transport dheu me auto 5km	m ³	144		
3	3.396	Mbushje me cakell	m ³	127		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	147		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3		
SHUMA II						
SHUMA I-II						
OBJEKTI : Ndertim Rruga "Pingul me Azem Hajdari" Bathore7						
(L =165ml, basf= 4m, KUZ -D=315mm)						
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	66		
2	3.158/5a	Transport dheu me auto 5km	m ³	66		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	66		
4	3.211	Shtrese çakelli T=20cm	m ²	660		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	660		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	660		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	660		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	380		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						
II						
PUNIME NE KUZ						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	158.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	158.4		
3	3.396	Mbushje me cakell pas mureve	m ³	140		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	162		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3		
SHUMA II						
SHUMA I-II						
OBJEKTI : Ndertim Rruga "Synej+seg.paralel me Synej" Bathore 7						
(L =620 ml, B =7m, basf= 4.5m, 0.5kunete,2x1 trotuar,)						
A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	248		
2	3.158/5a	Transport dheu me auto 5km	m ³	248		
3	3.164/1b	Mbushje me çakell shkembor	m ³	248		
4	3.211	Shtrese çakelli T=20cm	m ²	2790		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2790		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2790		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri + 3 rampa	m ²	2830		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	294.6		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	3		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	14		
11	2.426/2	Prishje mur me blloqe	m ³	196		
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	1320		
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	8		
		SHUMA I				
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	248		
2	3.158/5a	Transport dheu me auto 5km	m ³	248		
3	3.396	Mbushje me cakell pas mureve	m ³	178.8		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	607		
5	2.262/4	Shtrese betoni c 16/20 Kunete betoni M - 200	m ³	26.21		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	22		
		SHUMA II				
III		PUNIME TROTUARE(2x1 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	124		
2	3.158/5a	Transport dheu me auto 5km	m ³	124		
3	3.164/1b	Mbushje me çakell shkembor	m ³	248		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	806		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	806		
6	3.616/9	FV Bordura betoni 15x25 cm	ml	1240		
7	2.262/4	Beton per fiksime bordure C16/20	m ³	37.2		
8	2.262/4	Shtrese betoni trotuari C 16/20	m ³	76.7		
		SHUMA III				
III		PUNIME NE KUZ				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	595.2		
2	3.158/5a	Transport dheu me auto 5km	m ³	595.2		
3	3.396	Mbushje me cakell pas mureve	m ³	510		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	655		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	13		
		SHUMA IV				
IV		PUNIME PER NDRICIMIN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	620		

2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	620		
3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	17		
4	3.139	Germim dheu me eskavator	m ³	124		
5	3.158/5a	Transport dheu me auto 5km	m ³	124		
6	2.261	Mbushje me rere	m ³	49.6		
7	3.353	Mbushje me shkemb te germuar me pare	m ³	74.4		
		SHUMA IV				
		SHUMA I-V				
		TOTALI				
		TVSH 20%				
		TVSH TOTALE				

shenim : preventivi eshte hartuar ne baze te vkm 216 date 13.04.2023

Preventivues:

Ing. Eglantina Disha



Drejtori P.I-se

Ing. Flora MUÇA


