



**MIRATOI
KRYETARI BASHKISE
TONIN MARINAJ**

PREVENTIV I PUNIMEVE

Objekti: Sistemim, asfaltim rruga e Virit Kosan

| | | Gjatesia e rruges | Metra | 718.75 | | |
|------------|-----------------------------------|--|-------------|---------|-------|-------|
| Nr. | Analiza | Emertimi i Punimeve | Njësia | Sasia | Cmimi | Vlera |
| 1 | Punime Germimi | | | | | |
| 1 | 3.7 | Shkulje rrenjeve bimeve te vogla | m2 | 340.0 | | - |
| 2 | 3.89/a | Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet | m3 | 215.0 | | - |
| 3 | 3.45/1 | Germim kanalesh ne toke te zakonshme, me krahe, me seksion deri 0.75 m ² | m3 | 32.0 | | - |
| 4 | 3.158/5a | Transport dheu me auto deri ne 5 km | m3 | 247.0 | | - |
| | | Shuma | 1 | | | - |
| 2 | Riparime shtresash rrugore | | | | | |
| | 3.205/2 | Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri | m2 | 3,200.0 | | - |
| 2 | 3.212/b | Shtrese stabilizant t=10cm | m2 | 3,200.0 | | - |
| 3 | 3.222/2 | Shtrese binderi me granil gur kave,6cm,me makineri | m2 | 2,300 | | - |
| 4 | 3.212/a | Shtrese stabilizanti t=5cm bankine | m2 | 900.0 | | - |
| | | Shuma | 2 | | | - |
| 3 | Punime te ndryshme | | | | | |
| 1 | 3.243 | Struktura monolite betoni C 16/20 | m3 | 5.7 | | - |
| 2 | 2.426/2 | Prishje mure blloqesh betoni (mure rrethues) | m3 | 2.0 | | - |
| | | Shuma | 3 | | | - |
| I | | Shuma(1-3) | Leke | | | - |
| II | | TVSH 20 % | | 20% | | - |
| III | | VLERA TOTALE (I + II) | Leke | | | - |

Shenim: Preventivi eshte vleresuar me cmimet e V.K.M. Nr. 216 date 13.04.2023

**PROJEKTUESI
LENI-ING SHPK shpk
Ing Nikoll Paluca**