

Projektuesi: Rroland Hajro

Objekti: R

Datë: 3

## PREVENTIV

NR	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA
<b>1. PUNIME SHITESASH</b>				
1	3.197/2	Prishje shtresash ekzistuese, t=10cm.	m2	144.0
2	3.178	Ndertim kasonete ne toke te bute	m2	144.0
3	3.212/c	Shtrese stabilizant t=15cm	m2	144.0
4	3.212/b	Shtrese stabilizant t=10cm	m2	30.0
5	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur me makineri	m2	288.0
6	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	30.0
7	3.198	Cilindrim kasonete me rul	m2	144.0
8	3.183/a	Shtrese zhavor lumi t=10cm	m2	90.0
<b>Shuma 1:</b>				
<b>2. PUNIME GERMIMI</b>				
9	3.87/b	Germim dheu me ekskavator goma, 0.25 m³, ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m3	570.0
10	3.111/b	Germim dheu me ekskavator zingjir 1.0 m³, ne kanale gjeresi > 2 m, prani uji ~ 1m, kategoria IV, me shk ne mjet	m3	261.0
<b>Shuma 2:</b>				
<b>3. PUNIME DHEU</b>				
11	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	831.0
<b>Shuma 3:</b>				
<b>4. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME</b>				
12	3.401/Rroland Hajro	Mbushje me gredhe me gramature 280 g/m2	m2	160.0
13	3.396/1	Mbushje me zhavorr pas mureve	m3	315.0

Digitally signed by  
Rroland Hajro  
Date: 2024.06.24  
11:23:13 +02'00'

<b>Shuma 4:</b>				
<b>5. ANALIZA TEKNIKE</b>				
14	3.222/2	Shtrese bideri me granil gur kave, 6cm, me makineri	m2	144.0
15	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	144.0
<b>Shuma 5:</b>				
<b>6. PUNIME BETONI E BETONARMEJE</b>				
16	3.247	Struktura monolite betoni me çakell C 25/30	m3	150.0
17	3.246	Struktura monolite betoni me çakell C 20/25	m3	114.0
18	3.240	Struktura monolite betoni C 12/15	m3	26.0
<b>Shuma 6:</b>				
<b>7. PUNIME TE NDRYSHME</b>				
19	3.626	H / Izolim me emulsion, 2 K. Katr. + 3 duar bitum	m2	155.0
<b>Shuma 7:</b>				
<b>8. PUNIME HEKUR BETONI 3</b>				
20	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	43.0
<b>Shuma 8:</b>				
<b>9. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA</b>				
21	3.901	F.V - guardrail H2 anesore per ure me 3 vale ne 1 ane ,W5(elem+ lart)	ml	21.0
<b>Shuma 9:</b>				

Shuma Analiza

Fondi Rezervë (5.0%)

Shuma Analiza + Fondi Rezervë (5.0%)

Shuma me TVSH (20%)

Totali

Rroland  
HajroDigitally signed by  
Rroland Hajro  
Date: 2024.06.24  
11:23:13 +02:00